

February 29, 2016

GMDC Limited
Lignite Project Rajpardi

NOTE : CORRIGENDUM

Sub : Changes to be made in tender for construction of bore well in village
Maljipura-2(Sarsa Dungar)

Ref : Tender no. GMDC/JLP/03/2015-16

With reference to the above tender, following technical changes are being made to suit our requirement.

Sr.no.	Item no.	Existing Description	New/changed Description
1	2	Providing & lowering of 6.0 inch diameter M.S. "C" class ISI make ERW blank pipe	Providing & lowering of 7inch diameter UPVC heavy duty pipe of approved ISI make
2	4	Providing & fixing of clamp, bore plug, bail plug suitable to 6.0 inch dia. ERW pipe	Providing & fixing of clamp, bore plug, bail plug suitable to 7.0 inch dia. UPVC pipe
3	7	Providing 4"(ID) dia UPVC heavy duty threaded pipe of approved ISI make including necessary packing sheet etc. complete.	Providing 3"(ID) dia UPVC heavy duty threaded pipe of approved ISI make including necessary packing sheet etc. complete.
4	9	Providing, supplying installing & commissioning of 15HP capacity of 2500 RPM approved ISI make motor, 7stages with a head of 80mts and guarantee for one year from the date of commissioning.	Providing, supplying installing & commissioning of 15HP capacity of 2500 RPM approved ISI make motor, V6-7stages with a head of 80mts and guarantee for one year from the date of commissioning.

On account of above changes project will not incur any extra expenses and the cost of job will remain within the approved limit.


To facilitate the above changes we may extend the date of issue of tender up to 05.03.2016 as approved by local tender committee.

Thus General Manager(P) is kindly requested to provide consent to incorporate the above changes in the tender document.


Civil supervisor


Sr. Manager(Geo)


Safety Officer


General Manager (P)

Name of work : Construction of bore well in village Maljipura-2(sarsa dungar) at
Lignite Project Rajpardi

Sr. no	Item description	Qty.	Rate	Per	Amount
1	Drilling of 7.0" dia borehole by DTH rig including lowering of pipe assy, gravel packing, clay packing etc. complete.	100		Rmt	
2	Providing & lowering of 7.0" dia(ID) UPVC heavy duty pipe of ISI make	20		Rmt	
3	Electro logging for recording different type of geological layer in bore.	1		L/S	
4	Providing & Fixing of clamp, bore plug, bail plug, suitable to 7.0 inch UPVC pipe	1		L/s	
5	Providing of best quality well sorted sevalia gravel of size 4mm to 6mm as per instruction.	10.0		Cmt	
6	Development of bore of above mentioned drilled & reamed borehole by air compressor having 400CFM/100PSI capacity till sand free discharge.	10		Hrs	
7	Providing 3" (ID) dia UPVC heavy duty threaded pipe including necessary packing sheet, etc. complete.	80		Rmt	
8	Supply of panel board with all relays switches, buttons, safety device & preventor of approved make ISI mark & preparation of earthing pit as per instruction of				

	Engineer I/c	1		No	
9	Providing & Supplying 15 HP ISI mark & approved make capacity 2500 RPM with motor, V6- 7stages with a head of 80mts and guarantee for one year from the date of commissioning	1		No	
10	Providing & Supplying 3 core flat PVC cable 10 sq.mm finolex brand	200		Rmt	
11	Providing & fixing Non-return gate valve of 4" dia size of ISI make approved brand	1		No	
12	Providing & laying PVC pipe 110mm dia of 6.0kg/cm.sq working pressure including fitting like coupling, elbow, tee etc comp.	100		Rmt	
13	Providing & fixing of gun metal heavy duty wheel valve of 4" dia. Of approved ISI mark	1		No.	
	Total Amount Rs.				

Stamp & Signature of contractor