

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED

Name of Work : T- No-16-BVN-PAVER BLOCK WORK-2021 (Re invite) Providing and Fixing paver block in GMDC Colony at Lignite Project Bhavnagar

PRICE BID

Sr.No	Item Description	Qty	Unit	Rate	Amount
1	Dismantalling Rubber Dye inter locking concrete paver block 80 mm thick and sand badding , including stacking of seviceable materials and disposal of unserviceable materials with all lead and lift out side of colony premises and transporting useful materials and block in colony premises up to 400 mts lead , including all labour , tools , tackles, transportaion, loading , unloading ,etc. complete as directed by EIC.	1489	Smt	0	0
2	Providing and Fixing pre cast rubber dye inter locking concrete paver block 80 mm thick as approved by EIC , with grade of concrete M 250 pneumatic compressed by mechanically pressed and as per approved design including 75 mm sand layer for leveling , compaction with mechanical compector and filling the joint with sand in proper line and level etc. complited including all required material, labour , tools , tackles , transporttain , loading , unloading etc. complete as directed and specified.	1042	Smt	0	0
3	Fixing the old Pre Cast Rubber Dye inter Locking concrete Paver Block 80 mm thick including cleaning the old block and fixing the block including 75 mm thick sand layer in proper line & level including compaction with mechanically compector etc. complete including required material, tools , tackles, loading , unloading , transportation ertc. complete .	447	Smt	0	0
TOTAL					