

Sub: 16/FK/Renovation & Refurbishment works of quarters –Mines office /2022 Works Renovation & Refurbishment of 30 nos. of 'D' Type and 8 nos. "C" type colony quarters and Mines office building at GMDC Fluorspar Project Kadipani Tal: Kawant , Dist- Chhotaudepur

Price Bid-Part-3- Electrical works for 'Mines Admin office '					
NOTE: For all below mentioend items Scope of work include Providing , supplying , installation and testing with all material , labour , tools , tackles, loading , unloading , transportaion , scffolding etc complete as directed by EIC.					
SR.	ITEM WISE DESCRIPTION AND SPECIFICATION	TOTAL QTY.	UNIT	Rate	Amount
1	Providing and Fixing 250 Amp 4 Pole, 35kA Capacity MCCB, MAKEL:L&T, C&S, HAVELLS,ABB etc as directed by EIC ,	1	NOS		
2	Providing and FixingDISTRIBUTION BOX: 8 WAY, VOLTAGE 240 - 415 V AC, INSIDE DISTRIBUTION BOX INCLUDING 40 AMP, 30 mA DP ELCB-04 NOS.per BOX	3	NOS		
3	Providing and Fixing DISTRIBUTION BOX:WAYS :4-6 UNITS, INSIDE DESTRIUTION BOX INCLUDING 40 AMP DP MCB-01 NOS., 20 AMP SP MCB-01 NOS AND 16 AMP SP MCB-01 NOS, MAKE: OREVA, POLYCAB, ANCHOR, L&T, C&S	12	NOS		
4	Providing and FixingSWITCH:20 AMP - 1 WAY SWITCH, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	5	NOS		
5	Providing and Fixing SWITCH:6 AMP - 1 WAY SWITCH, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	88	NOS		
6	Providing and Fixing SWITCH:16 AMP - 1 WAY SWITCH, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	33	NOS		
7	Providing and Fixing SWITCH:6 AMP - 1 BELL SWITCH, MAKE:OREVA, ANCHOR, HIFI. POLYCAB, HAVELLS	6	NOS		
8	Providing and Fixing SOCKET: 6 AMP - 2 x 1 SOCKET WITH SHUTTER, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	15	NOS		
9	Providing and Fixing SOCKET: 20 AMP - UNIVERSAL SOCKET, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	5	NOS		
10	SOCKET: 16 AMP - UNIVERSAL SOCKET, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	33	NOS		
11	Providing and Fixing4 STEP FAN REGULATOR - 1M, MAKE: OREVA,ANCHOR, HIFI, POLYCAB, HAVELLS	13	NOS		
12	Providing and Fixing PVC BOARD: 8-9 WAY MODULAR PVC BOARD, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	23	NOS		
13	PVC BOARD: 4 WAY MODULAR PVC BOARD, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	8	NOS		
14	Providing and FixingPVC BOARD: 1 WAY MODULAR PVC BOARD MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	13	NOS		
15	Providing and Fixing6 AMP HOLDER WITH ADEPTER, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	98	NOS		
16	Providing and FixingPVC CONDUTE PIPE, SIZE: 40 MM FOR 4 SQ. MM 3 CORE CABLE LAYING, STANDARD MAKE	150	Rmt		
17	Providing and FixingPVC CASING CAPPING PIPE FOR 25 MM FOR 2.5 SQ. MM & 1.5 SQ. MM CABLE LAYING, SIZE: 25 MM, STANDARD MAKE	380	Rmt		
18	Providing and FixingCABLE: 4 SQ. MM 3 CORE FLEXIBLE CABLE, 1.1 KV GRADE FLEXIBLE COPPER WIRE, MAKE:ANCHOR, POLYCAB, AVOCAB, HAVELLS, OREVA	375	Rmt		

19	Providing and FixingCABLE: 1.5 SQ. MM SINGLE CORE FLEXIBLE COPPER WIRE, MAKE:ANCHOR, POLYCAB, AVOCAB, HAVELLS, OREVA, TOTAL CABLE INCLUDING PHASE, NEUTRAL & EARTHIN WIRE CODE AS PER CEA	850	Rmt		
20	Providing and FixingCABLE: 2.5 SQ. MM SINGLE CORE FLEXIBLE COPPER WIRE, MAKE:ANCHOR, POLYCAB, AVOCAB, HAVELLS, OREVA, TOTAL CABLE INCLUDING PHASE, NEUTRAL & EARTHIN WIRE CODE AS PER CEA	80	Rmt		
21	OLD WIRING REMOVING WORK AND OLD MATERIAL SUBMITTED TO GMDC with keeping necessary records and as ditected by Engineer in charge with all lead & lifts	1	JOB		
Total Amount					