

# **GMDC LIMITED**

LIGNITE PROJECT, RAJPARDI

TENDER NO. GMDC/JLP/ 6 /2022-23

## NAME OF WORK

WORK OF CONSTRUCTION OF OFFICE CABIN  
FOR POLICE STATION LOCATED AT VILLAGE  
RAJPARDI NEAR LIGNITE PROJECT RAJPARDI  
TA: JHAGADIA, DIST. BHARUCH

:2:

*Tender No: GMDC/JLP/ 6 /22- 23*

**Name of work: Work of Construction of office cabin for police station located at village Rajpatdi near Lignite Project Rajpardi Ta. Jhagadia, Dist. Bharuch.**

The work is to be completed within a period of 60 days.

Decision of the Management for awarding the work based on the details submitted by the contractors is final and binding to them and no correspondence will be entertained from the tender in this regard.

The Corporation reserves the right to reject any or all the tenders without assigning any reason thereof.

Signature & Stamp of the Contractor

**:3:**

The contractor will submit R.A.bill of minimum Rs. 2.0 lacs for the work executed. Final bill shall be accompanied with detailed measurement sheets duly certified by the Engineer In-charge/Architect and/or authorized person of the employer.

Final bill become payable within 15 working days from the date of receipt of the bill at Project Office after deducting there from.

1. Income Tax, Sales Tax TDS, Turn over tax etc. etc. as per the provision of respective act from time to time.
2. Security Deposit & Retention Money.
3. Cost of any services provided by the Employer and/or material supplied by the employer.
4. RA/Final bill must be submitted along with the names of the labourers employed for the work, salaries paid to them, amount of P F deducted from the salary of the labourers and employer's contribution amount deposited in RPFC against each labour name and copy of the challans for the amount deposited in RPFC office till previous month duly certified by the project office.. Contractor has to maintain wages register and the same will have to be certified by the Engineer In charge.

Other deduction either statutory or for any reason, if any.

5. Earnest money deposit [EMD] and Security Deposit [SD] will not bear any Interest.

The contractor shall have to full fill and abide by the provision of labour laws, Contract Labour Regulations and Abolition Act, 1970 [Central Act 37 of 1970] pertaining to the employment ad labour.

:4:

## PREFACE

The employer M/s Gujarat Mineral Development Corporation Ltd. [hereafter referred to as 'employer'] proposes work of construction of office cabin for police station located at village Rajpardi, Ta. Jhagadia under Tender No. GMDC/RAJ/ 6/22-23

All decisions to award the contract will be made by the employer.

The Architect/Civil Engineer/any Officer authorized by the Corporation is entitled to ask the contractor to discontinue any work which does not meet the excepted an/or specified standards. The works already executed may be rejected and asked to remove for the said reasons, at the risk and cost of the contractor.

The Contractor has to do this work strictly according to the drawings, estimate and specifications appended herewith and which together with general conditions, technical specifications, bills of quantities and contract agreement will be called 'Documents of Contract'

The tenders are requested to take the note of documents to be enclosed and sent along with the quotations, as stated in this quotation and to attach the same with the quotation so as to avoid further correspondence on the same.

: 5:

## **TENDER NOTICE**

Sealed item rate Tender super scribed with Tender numbers and closing date are invited from experienced contractors for the work mentioned below:

1.	<b>Name of work</b>	Work of construction of office cabin for police station located at village Rajpardi, Ta. Jhagadia near Lignite Project - Rajpardi Tender No. GMDC/RAJ/ 6 /22-23
2.	<b>Location</b>	At Village – Rajpardi, Ta. Jhagadia
4.	<b>Earnest Money Deposit</b>	Rs. 6200/- in form of DD or net banking in favour of GMDC Limited, payable at Rajpardi.
5.	<b>Time of completion</b>	60 Days
6.	<b>Date of issue of Tender</b>	06.03.2023 to 13.03.2023 up to 03.00 PM
7.	<b>Last date for receipt of Tender</b>	16.03.2023 up to 02.00 PM
8.	<b>Date for opening of Tender</b>	16.03.2023 04.00 PM
9.	<b>Tender Fee</b>	Rs. 500/- +GST 18% by net banking [Non-refundable if required by post Rs. 50/- extra]
10	<b>Defect liability period</b>	12 months
11	<b>Penalty</b>	0.10% of contract value per day maximum up to 10% of contract value.
12	<b>Period of honoring of the bills</b>	15 working days after issue of certificate from Architect / Civil Engineer.
13	<b>Refund of Security deposit</b>	Within 1 month from date of expiry of defect liability period, on demand.
14	<b>Submitted to</b>	General Manager (Project) Lignite Project - Rajpardi

**General Manager (P)**

.....6/-

:6:

Tender must be accompanied by EMD of Rs. 6200/- Paid in form of DD or net banking, which will be returned to unsuccessful quotationer.

SD is 5% of the contract value including EMD, have to be paid on acceptance of the tender either in form of Demand draft payable at Rajpardi or by Bank Guarantee from any of the nationalized bank in the form and manner approved by the employer and retention money will be deducted from the running bills at @ 5 % of the bill amount. If the value exceeds the contract value, then further deduction of SD at 5% will be made from the running bills. retention money will be refunded after one month from the date of completion work on demand by party, SD will be refunded after completion of defect liability period of Twelve months.

The successful tenderer who fails to deposit further sum of security deposit within the specified time and fails to execute the agreement and/to commence the work, his EMD paid will be forfeited.

EMD , SD & RMD will not bear any interest.

The Corporation do not bind themselves to accept the lowest tender and reserve the right to reject any or all the tenders without assigning reasons thereof.

Issued to M/s: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

:7:

**Following documents are to be enclosed and sent along with the tender:**

1. If the tenderer is partnership firm a certified copy of the partnership deed and if the tenderer is a limited company a certified copy of the incorporation certificate along with the certified copy of the latest annual report of the company.
2. Declaration by the contractor in the form as stated here after in the tender.
3. Minimum 3 certificates of having carried out similar work satisfactorily by the tenderer along with the details of the work.
4. If the tenderer is an approved Govt. contractor a certified copy of such registration issued by the Government in favour of the tenderer.
5. If the tenderer is an approved contractor by any Govt. of India under taking Gujarat State under taking or any other state Govt. under taking a certified copy of such registration.
6. Latest Income tax clearance certificate
7. Copy of the PF registration no. received from RPFC Office.

**NOTE:**

- [1] The contractor approved either by the Central State Govt. or Central or state govt. undertaking is not exempted by this corporation for paying EMD, SD etc. Any quotation without EMD will be summararily rejected by the Corporation.

Date:

Place:

Signature & Stamp of the Contractor

:8:

## **DECLARATION-I**

To:  
The GM [Project]  
Lignite Project  
RAJPARDI

**Sub:                   Work of Construction of office cabin for  
police station located at village Rajpatdi near  
Lignite Project Rajpardi Ta. Jhagadia, Dist.  
Bharuch.**

Dear Sir:

I/We have carefully gone through and clearly understood the tender notice and tender form and have tendered to execute and satisfactorily complete the whole of the work strictly in accordance with the said tender form.

I/We hereby solemnly declare that any of our partners jointly or severally and/or individually or our firm/company have not been black listed by the central Govt. or any state Govt. or its undertaking.

I/We here by further declare that, if the above declaration is found untrue, then GMDC Ltd, shall be entitled to take any action against us severally and or individually or our firm/company in this regard in any manner that may be deemed fit by GMDC.

Yours faithfully,

Signature & Stamp of the contractor

Place:

Date:

:9:

DECLARATION -II

From :

The GM [Project]  
Lignite Project  
RAJPARDI

Sub:

**Work of Construction of office cabin for police station located at village Rajpatdi near Lignite Project Rajpardi Ta. Jhagadia, Dist. Bharuch.**

Dear Sir:

I/We having carefully gone through and clearly understood the preface, tender notice, plans, specifications and conditions of contract for the above mentioned work, do hereby tender to execute and complete the whole work strictly in accordance with the said plans and specifications and conditions of contract at the rates set out in the priced schedule and quantities attached hereto.

I/We agree to finish the whole of the work as per instructions within 60 days from expiry of fifteen days from the date of issue of Letter of Intent or actual commencement of the work whichever is earlier.

I/We have deposited as EMD Rs. 6200/- by DD or net banking along with the tender in your office which amount is not to bear any interest and I/We do hereby agree that this sum shall be liable to be forfeited by the corporation at its sole discretion, in the event of your accepting my/our tender and I/We fail to execute the contract when called upon to do so.

It is understood by me/us that the lowest or any tender will not necessarily be accepted and that no reason shall be given for such non-acceptance.

I/We agreed to keep our offer valid for 180 days or for a further period as would be desired by the corporation, from the date of the opening of the tender. We agree to all the terms and conditions of the tender.

Yours faithfully,

Signature & Stamp of the Contractor

Place:

Date:

:10:

To:  
The GM [Project]  
Lignite Project  
RAJPARDI

**Sub: Work of Construction of office cabin for police station located at village Rajpatdi near Lignite Project RajpardI Ta. Jhagadia, Dist. Bharuch.**

**NO DEMAND CERTIFICATE**

We \_\_\_\_\_ hereby certify that we have received the payment of all our bills in full and final settlement of our claims in respect of Tender No. 6/22-23 for Work of Construction of office cabin for police station located at village Rajpatdi near Lignite Project RajpardI Ta. Jhagadia, Dist. Bharuch.

The payment received by us is in full and final settlement of our all the claims towards the amount with respect to the work under reference.

Hence, we do not have any outstanding claim against GMDC for the work under reference. We shall not claim any further amount from GMDC in future, either one way or the other.

This certificate is given without any prejudice and in the presence of two witnesses.

Signature & Address of  
Witnesses

[1] \_\_\_\_\_

Signature & Stamp of the Firm

[2] \_\_\_\_\_

## INSTRUCTIONS BEFORE QUOTING THE TENDER

1. If the party does not accept the work order, issued by GMDC, then the amount of the EMD paid by the party will be forfeited.
2. Tenderer is required to quote the rates strictly as per the terms and conditions mentioned in the tender document. Any conditional tender will not be entertained and will be rejected.
3. Tenderer is required to visit the site along with the purchased tender copy, to study the actual working condition before submitting the offer.
4. Successful tenderer is required to insure the whole work and their personnel under Workmen Compensation Act against any accident, minor and major injuries arising out of the work situation.
5. The successful tenderer shall have to start the work within expiry of the period of 15 days from the date of receipt of the Letter of Intent. In case of non-compliance of the above condition the contract may be terminated.
6. The rate quoted is inclusive of all labor and material required for the Job.
7. The total works under this tender is with a 'providing and laying/fixing' the materials. In the event of missing of above phrase in the description of schedule of quantities, will not mean that materials will be supplied by the client and tenderer has to deploy only labors for completing the items.
8. Quantity mentioned in schedule of quantities against each item is only for guidance to quote the rate and no claim will be entertained on either increase or decrease in the quantity.
9. Water for the execution and curing & electricity will have to be managed by the tenderer at his risk and cost. However, if possible water and electricity will be supplied by corporation at a 1% of bill amount against water charge and actual charge of electricity against power consumption. Electric meter is to be installed by the contractor.
10. No escalation in price/rate will be allowed on any ground. Even if there is a delay in completion of the work due to client, then extension in time limit may be granted with an explicit understanding that no price escalation will be paid.
11. In absence of detail specification, the work should be carried out based on either relevant IS code and/or fair engineering practice prevailing in the market.
12. All the rates quoted by the tenderer must be inclusive of all taxes, duties, Octrai, transportation, labor, sales tax, turn over tax, loading, unloading & **But excluding the applicable GST** .
13. Successful tenderer will have to submit the three copies of the detail bar chart in the manner as per the Performa issued by the client for timely completion of the work.

14. Tenderer is required to submit the copy of the PF Registration number received from RPFC Office, along with the tender. However, each R A Bill must be submitted along with the name of the labour/employee deployed for the work salaries paid to them, amount of PF deducted from their salaries employees and employer's contribution, amount deposited in RPFC Office against each labor name and copy of the challan for the amount deposited in RPFC office till previous month duly certified by the project office, failing which no payment will be made for the RA Bill submitted by the contractor at Project/HO. Further, successful tenderer will have to submit the name of the labor/employee deployed for the work, salaries paid to them, amount of PF deducted from their salaries, employees and employer's contribution, along with the running bills.
15. The tenderer will have to submit '**NO DEMAND CERTIFICATE**' along with the final bill of the work, as per the Performa given earlier.
16. Successful tenderer is supposed to enter in to the agreement with the corporation on a appropriate stamp paper [to be provided by the contractor] after accepting the Letter of Intent and having agreed to and accepted the terms and conditions of the tender.
17. Any material issued by GMDC will be from GMDC stores. The transportation arrangement will be borne by contractor.
18. Successful tenderer have to submit royalty clearance certificate at the time of releasing of SD, if applicable..
19. Successful tenderer have to make payment to their employees through bank account only.
20. The cost of executed work (all tender items together) varies beyond (+/-) 10% of the tender value even if the quantities increase to any extent the present rate as mentioned will hold good and no price escalation will be allowed the quoted rates shall remain valid till completion of works from the date of the work order whichever is later.
21. Applicable GST will be paid/adjusted/reimbursed to the contractor as per the prevailing rates & rules to the extent directly related to the service Rendered or goods supplied by the successful bidder under the said contract subject to production of documentary proof and contractor will mention the GST amount separately in the invoice/bill along with SAC|HSN code under GST. Further if the bidder does not upload the invoice within four months from the invoice date on GSTN portal GST will not be reimbursed to them.
22. Successful tenderer shall have to obtain license under the Bombay shop and Establishment Act and it shall pay wages and benefits in accordance with the applicable laws and shall not pay less than as notified by the Government Authorities from time to time and shall maintain the employment records as required under applicable laws.

FOR GMDC LTD.

General Manager (Project)

Seal & Signature of Contractor

GUJARAT MINERAL DEVELOPMENT CORPORATION

LIGNITE PROJECT RAJPARDI

**SCHEDULE OF QUANTITY**

Name of work : Work of Construction of office cabin for police station located at village Rajpatdi near Lignite Project Rajpardi Ta. Jhagadia, Dist. Bharuch.

Sr.no.	Item Description	Qty.	Rate	Per	Amount
1	Excavation work in all sorts of soil up to 1.5 to 3.0m depth and disposal of surplus earth a directed by EIC within 50mt lead.	21.57		cmt	
2	filling in foundation and plinth with murrum or selected soil in layers of 20 cm thickness including watering, ramming and consolidating etc. complete	39.61		cmt	
3	Providing and laying brick masonry up to plinth level in CM (1:6) In true line & level curing etc completed.	23.77		cmt	
4	Half brick masonry in common burnt clay building bricks having crushing strength not less than 35 kg/sq.cm. in cement mortar 1:4 (1-cement : 4-sand) in foundation and plinth (A) Modular	10.5		smt	

5	Providing and laying controlled cement concrete M.200 exposed work with curing etc. complete . Including the cost of formwork but the excluding cost of reinforcement for RCC Work in (A) Beams , coloumn, slab, Foundaation, chhajja etc complete.	20.36		cmt	
6	Providing & laying P.C.C. (1:3:6) for wall foundation & floor etc complete including curing, cost of formwork etc complete.	7.61		cmt	
7	Providing and laying vitrified tiles 8 to 10 mm thick , 24" x 24" in flooring treads of steps and landing laid on a bed of 12 mm thick cement mortar 1:3 (1-cement :3-coarse sand) finishing with flush pointing in white cement.	33.57		smt	
8	Providing and fixing alluminium Door including fixtures , hold fasts etc complete.	4.2		smt	

9	<p>Providing and fixing window having extruded aluminum colour anodized section frame main outer size 63.50 x 38.10 x 1.95 mm @ wt. 1.094 kg/rmt, horizontal two track member size 61.85 mm x 31.75 mm x 31.75 x 1.20 mm @ wt. of 0.695 kg/mt with sliding shutters of horizontal member size 40 mm x 18mm x 1.29 mm @wt. of 0.456 kg/mt, @wt.0.457 kg/mt with 5 mm thick transparent bronze colour tinted float glass with powder coated aluminum fittings and fixtures and transparent silicon sealant glass fixing to frame as per details etc complete for window.</p>	5.4		smt	
10	<p>Providing and 15 mm thick smooth cement plaster in cement mortar 1 :6 (1-cement :6-sand) including curing etc complete.</p>	138.01		smt	
11	<p>20 mm thick sand faced plaster on walls up to height 10 meters above ground level consisting of 12 mm thick backing coat of C.M. 1:3 (1-CEMENT :3-SAND) and 8 mm thick finishing coat of C.M.1:1 ( 1-Cement :1-sand) etc. completed .</p>	104.13		smt	

12	Distemping two coats with oil bound distemper of approved brand and manufacture and of required shade on wall surface to give an even shade including priming coat , brushing the surface free from mortar dropping, sand papered smooth.	138.01		smt	
13	Finishing wall with water proofing cement paint of on wall surface two coats to give an approved brand and manufacturing and of required shape even shade after through brushing the surface to remove all dirt and remains of loose powder materials.	104.13		smt	
14	Providing TMT Bar FE 415 Reinforcement for R.C.C. work including cutting, bending, placing in position complete up to floor two level	2036		kg	
15	Providing and fixing MS structures for Grill, column, purlins, rafter etc. for the fixing of GI shed with required 'J Bolt', washer, nuts etc as per instruction of EIC including cutting,welding,2 coats of oil paint etc completed as per drawing/sketch	135		kg	
16	providing and laying water proofing treatment by (a) Applying neat cement slurry 2.75 kg /m2 of cement admixed with water	34.77		smt	

	<p>proofing compound after cleaning the surface.(b) Laying of bricks bats of 25 to 75 mm size in CM 1:5 (1 Cement :5 course sand ) admixed with water proofing compound over 20mm thick layer of cement mortar 1:5 to required slop including rounding of junctions of walls and slab with spacing not more than 30 mm (c) After two days of proper curing applying a second coat of cement slurry and cured for another two days (d) Finishing the surface with 20mm thick cm 1:4 and cured for two days (e) Providing and laying china mosaic flooring using broken pieces of glazed tiles to be laid over cement sand mortar screed (1:2) and cement grouting with water proofing compound in required levels and slope and to be temped by wooden mallet and filling the joints with white cement as required including rounding of junctions at walls, curing etc. As directed and specified. Water pond should be carried out for a period of three days as directed by EIC . Vata shall be considered in square meter. Note-Five years guarantee bond need to be provided , 10 % contract amount to be retained and released after guarantee period of five years.</p>				
	ELECTRICAL WORK :				

17	<p>Point wiring for light/Bell with 2-1.5sq.mm &amp; earth wire of 1.5sq.mm(green) both are of ISI marked 1.1 kv grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected with 6A Modular type switch/bell push &amp; accessories and earth continuity of following type, erected on PVC/Metallic/wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on/in wall (concealed type) ceiling as per pipe erected, with necessary lamp holder/ceiling rose/ H.D. connector as directed.</p> <p>(a) With medium class rigid PVC pipe and accessories erected concealed in wall/ceiling complete.</p> <p>Call bell gong type suitable for 230 volts, 50 c/s. Ac supply complete erected</p> <p>Light Point Bell Point</p>	09 02			
18	<p>Point wiring for FAN with 2-1.5 sq.mm &amp; earth wire of 1.5 sq.mm (green) both are of ISI marked 1.1KV Grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected with 6A Modular type switch and hum free EME step type electronic fan regulator mounted and accessories with earth</p>	02			

	continuity of following type erected on PVC/Metallic/wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on/in wall/ceiling as per pipe erected with necessary ceiling rose/HD connector as directed. Partial PVC pipe and drops in oval conduit/pvc casing capping erected concealed in wall/ceiling complete.				
19	For 16A plug and 16 amp switch with 2-4 sq.mm & earth wire of 2.5 sq.mm(green) both are of ISI marked 1.1kv Grade FRLS PVC insulated multi strand copper wires up to 10 mtr length Cu. Wire from mcb db board with medium class Rigid PVC pipe and accessories erected concealed in wall/ceiling with complete.	02			
20	Point wiring for on board Looped plug with 6A Modular type switch & 5 pin socket erected on PVC/Metallic/wooden box, single mounting base frame covered with textured/ metallic/white front plate modules erected on/in wall/ceiling with following type accessories.	11			
21	Providing and erecting mains with 1.1kv grade FRLS PVC insulated ISI marked strand copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling with 1.5sq.mm copper				

	<p>conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size: with (a) 3 wire 2.5sq.mm &amp; (b) 3 wire 4sq.mm</p> <ol style="list-style-type: none"> <li>1. 25Amp, 2 pole, 230 volt, 6KA, reputed ISI marked ELCB switch for incomer.</li> <li>2. 6 to 20 Amp single pole MCB metallic switch for distribution</li> </ol>	01 01 01  04			
22	<p>Providing &amp; erecting switch board for computer or electric apparatus consisting of following modular type accessories mounted with PVC/Metallic concealed/open box with single mounting base frame covered with textured/metallic/white front plate, modules erected with necessary connections as directed</p> <p>1 no. 6A/16A universal plug-switch combined. 4 nos. 6A switch 4 nos. 6A 5pin plug</p>	02			
23	<p>Earthing Pit – depth 2 mtr, width 1x1mtr with 11 brick chamber for maintain earth resi- with PVC cover.</p> <p>GI plate- 25x25x3mm, GI pipe dia 1.5 inch, GI pattie- 6x6x3mm with using coal salt etc.</p>	01			
	TOTAL COST Rs. (Excluding GST)				

**Stamp and signature of Contractor**

