

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED					
SUB:	Name of Work :-T-No-16-BG-Colony Road work-2023-Resurfacing of existing roads of GMDC colony locatyed at Calcined bauxite project Gadhsisa Tal:-Mandvi Dist:-Kutchh.				
PRICE BID					
SR NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Preparing surfaces by brushing with wire brushes for removing caked mud etc. sweeping with brooms and finally fanning the cleaned surface with gunny bags to remove all loose dirt etc. as directed for pot holes as per EIC.(ii)black top surface.	2390.00	Smt	0.00	0.00
2	Providing and laying 25mm thick B.M with B.T Aggregate as per MORT and H Specification and asphalt (VG-3) for tack coat at 2.50 Kg./10 Smt with mechanical sprayer and bitumen Grade 60/70 (VG-30) for mixing at 34.00 Kg/MT i.e 3.4 percent of total mix ((1) Metal 19.00 to 26.50 mm-0.0330 (2) Kapchi 13.20 to 19.00 mm -0.1518 (3) Grit 4.75 to 13.20 mm -0.3036 (4) Grit-2.36 to 4.75 mm-0.0990 (5) Stone dust 0.075 to 2.36 mm-0.0726 )) including heating the aggregate and asphalt in drum mix plant and spreading the same by paver finisher and consolidation with vibratory road roller including providing all materials, equipments, tools and plants, fire wood, oil, kerosene, labour charges etc. complete using contractor's own machinery drum mix plant and paver finisher etc. complete.	138.00	MT	0.00	0.00
3	Providing and laying 20mm thick Mix Seal Surfacing using stone chipping and Aggregate as per MORT and H Specification and asphalt grade (VG-30) for mixing at 50.90 Kg/MT i.e 5.09 percent of total mix ((1) Grit-5.6 mm to 11.20 mm-0.198 (2) Grit-2.80 mm to 5.60 mm)-0.290 (3) Stone dust 0.075 to 2.36 mm- 0.172))and VG-30 tack coat at 2.5kg/10sqmt including heating the aggregate and asphalt in continuous batching drum mix plant and spreading the same by paver finisher and consolidation with vibratory road roller and flushing sand at 0.30 cum/100 smt including providing all materials, equipments, tools and plants, fire wood, oil, kerosene, labour charges etc. complete using contractor's own machinery drum mix plant and paver finisher etc. complete.	115.00	MT	0.00	0.00
4	Filling road side path way with murrum in layers of 5cm thickness including watering,ramming and consolidating and rolling of earthwork in layers with power roller including filling in depressions which occur during the process.	57.00	cumt	0.00	0.00