

## GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED

SUB: 5/FK/Renovation & Refurbishment works-C type quarters /2023- Works Renovation and Refurbishment of 98 nos. of 'C' Type colony quarters at GMDC Fluorspar Project Kadipani Tal: Kawant , Dist- Chhotaudepur

NOTE: For all below mentioned items scope of work include providing, supply, installation and testing with all material, labour, tools, tackles. Loading, unloading, transportation, scaffolding etc. complete as directed by EIC.

### PRICE BID-PART-II-ELECTRICAL WORKS

SR.	ITEM WISE DESCRIPTION AND SPECIFICATION	QTY. PER QTR	UNIT	RATE PER UNIT	Amount
1	PROVIDING AND FIXING DISTRIBUTION BOX:WAYS :7-9 UNITS, VOLTAGE 240 - 415 V AC, SIZE :L.285 X W.260 X H.105 MM INSIDE DISTRIBUTION BOX INCLUDING 32 AMP,30mA DP ELCB-01 NOS., 20 AMP SP MCB-03 NOS AND 16 AMP SP MCB-02 NOS, MAKE: OREVA, POLYCAB, ANCHOR, L&T, C&S	117	NOS	0.00	0.00
2	PROVIDING AND FIXING SWITCH:6 AMP - 1 WAY SWITCH, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	2076	NOS	0.00	0.00
3	PROVIDING AND FIXINGSWITCH:20 AMP - 1 WAY SWITCH, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	344	NOS	0.00	0.00
4	PROVIDING AND FIXINGSWITCH:6 AMP - 1 BELL SWITCH, MAKE:OREVA, ANCHOR, HIFI. POLYCAB, HAVELLS	117	NOS	0.00	0.00
5	PROVIDING AND FIXINGSOCKET: 6 AMP - 2 x 1 SOCKET WITH SHUTTER, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	560	NOS	0.00	0.00
6	PROVIDING AND FIXINGSOCKET: 20 AMP - UNIVERSAL SOCKET, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	344	NOS	0.00	0.00
7	PROVIDING AND FIXING4 STEP FAN REGULATOR - 1M, MAKE: OREVAM ANCHOR, HIFI, POLYCAB, HAVELLS	231	NOS	0.00	0.00
8	PROVIDING AND FIXING PVC BOARD: 8 WAY MODULAR PVC BOARD, MAKE:OREVA, ANCHOR, HIFI, POLYCAB	111	NOS	0.00	0.00
9	PROVIDING AND FIXING PVC BOARD: 6 WAY MODULAR PVC BOARD, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	229	NOS	0.00	0.00
10	PROVIDING AND FIXING PVC BOARD: 4 WAY MODULAR PVC BOARD, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	344	NOS	0.00	0.00
11	PROVIDING AND FIXING PVC BOARD: 1 WAY MODULAR PVC BOARD FOR BELL, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	118	NOS	0.00	0.00
12	PROVIDING AND FIXING PVC BOARD: 4 WAY MODULAR PVC BOARD FOR 20 AMP POWER POINT, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	344	NOS	0.00	0.00
13	PROVIDING AND FIXING 6 AMP HOLDER WITH ADEPTER, MAKE:OREVA, ANCHOR, HIFI, POLYCAB, HAVELLS	1633	NOS	0.00	0.00
14	PROVIDING AND FIXING PVC CASING CAPPING PIPE, SIZE: 30 MM, STANDARD MAKE	6925	MTR	0.00	0.00
15	PROVIDING AND FIXING CABLE: 1.5 SQ. MM FLEXIBLE SINGLE CORE 1.1 KV GRADE FLEXIBLE COPPER WIRE, MAKE:ANCHOR, POLYCAB, AVOCAB, HAVELLS, OREVA, TOTAL CABLE INCLUDING PHASE, NEUTRAL & EARTHIN WIRE CODE AS PER CEA	10850	MTR	0.00	0.00
16	PROVIDING AND FIXING CABLE: 2.5 SQ. MM SINGLE CORE 1.1 KV GRADE FLEXIBLE COPPER WIRE, MAKE:ANCHOR, POLYCAB, AVOCAB, HAVELLS, OREVA, TOTAL CABLE INCLUDING PHASE, NEUTRAL & EARTHING WIRE CODE AS PER CEA	9250	MTR	0.00	0.00

17	PROVIDING AND FIXING CEILING FAN:1200 MM SIZE CEILING FAN WITH REGULATOR, MAKE: ORIENT, BAJAJ, USHA, CROMPTON GREAVES	231	NOS	0.00	0.00
18	PROVIDING AND FIXING TUBELIGHT: T5 LED LIGHT, MAKE:USHA, SURYA, HAVELLS, BAJAJ. CROMPTON GREAVES	347	NOS	0.00	0.00
19	OLD WIRING REMOVING WORK AND OLD MATERIAL SUBMITTED TO GMDC	117	JOB	0.00	0.00
20	PROVIDING AND FIXING CABLE: 4 SQ. MM THREE CORE 1.1 KV GRADE FLEXIBLE COPPER WIRE, MAKE:ANCHOR, POLYCAB, AVOCAB, HAVELLS, OREVA, TOTAL CABLE INCLUDING PHASE, NEUTRAL & EARTHING WIRE CODE AS PER CEA	1416	MTR	0.00	0.00
21	PROVIDING AND FIXING 9 WATT LED LAMP, MAKE:USHA, SURYA, HAVELLS, BAJAJ. CROMPTON GREAVES	589	NOS	0.00	0.00
22	PROVIDING AND FIXING DOOR BELL AS STANDARD MAKE	118	NOS	0.00	0.00
23	PROVIDING AND FIXING SINGLE PHASE ENERGY METER WITH BOX FOR ALL 144 NOS. OF "C" TYPE QTRS	143	NOS	0.00	0.00
24	PROVIDING AND FIXING DISTRIBUTION BOX WITH INCLUDING 125 AMP MAIN 4 POLE MCCB, 32 AMP 2 POLE MCB- 08 NOS, 100 AMP BUSBAR WITH NEUTRAL & EARTHING LINK	11	NOS	0.00	0.00
	<b>TOTAL</b>				