

**CORRIGENDUM-1**

**Tender ID No. 605950**

**RFP: Design, Supply, Installation, Testing & Commissioning of Heavy - Duty Machine Room Less 20 passenger Lifts and Staircase with 5 years AMC at Shree Shyamji Krishna Varma Memorial Experiential Centre at Mandvi, Kachchh Bhuj**

<b>Sr. NO</b>	<b>Relevant Section in RFP and Page NO.</b>	<b>Query</b>	<b>Response from GMDC-GVT</b>
1.	General Query	Will the authority allow private sector work amount also in Pre-Qualifications Criteria clause no.9	Yes

**Annexure A: Bill of Materials**

<b>Sr. NO</b>	<b>Item Code</b>	<b>Items</b>	<b>Unit</b>	<b>Qty.</b>
1	-	SITC of 20 Passengers MRL Gearless Elevator with big vision glass center opening auto door lift with outside steel structure as per specification. (Make - Gulf Elevator/Johnson Lift/ Kone/ Schindler/ Otis/Indel)	No.	1
2	-	SITC of elevator air-conditioner including the required electrical work and all the accessories. Make - Branded	No.	1

3	-	<p>Providing and fixing of approved make 120mins Hollow metal fire rated doors tested and certified design as per IS 3614 part-2 &amp; BS 476 part-20 &amp; 22 at NABL Approved Laboratory for its stability and integrity. Galvanized steel sheet to be used should be confirming to IS 277. Recommended fire door design should be similar to earlier test evidence from NABL Approved Laboratory with or without vision lite for maximum fire rating of 2hrs . Doors should be finished in Powder Coating with film thickness of 60 microns approx. in desired RAL Shades.</p> <p>Door Size : 1200 X 2100 mm  Door Shutter Thickness : 46 mm  Infill : Honeycomb Core  Frame : 100 X 57 mm / Single Rebated  Finish : Powder Coated  Door Hardware included  Door Closer : fire rated  Vision Panel : 200x 300mm - 2 hrs fire rated  Panic Bar : Push Type  External Trim : with key  Including the Door Frame and required demolished to make the necessary space and civil work and paint to match the existing interior finishing.  Make - Branded</p>	No.	1
4	-	Providing and fixing of external façade glass for Lift structure including the required sealant, mounting accessories etc.	Job.	1
5	-	Providing and fixing of Staircase Handrail glass including the mounting accessories etc.	Job.	1
6	-	SITC of 1200mm Air curtain, ISO 9001:2015,CE certified, white colour suitable for wall / ceiling mounting having copper motor winding , Suitable for height up to 10 feet and should operate on 220v + - 10%, 50 Hz, single phase AC supply.	No.	1
7	11001 AA	<p>Steel work, riveted in built up sections framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. (A) In beams and joists, channels angles Tees, flats, with connecting plates or angle cleats as in main and cross beams. Hip and jack rafters, purlins connected to common rafters and the like.</p> <p>Make list: - Tata steel/ Apollo steel/ Jindal Steel/ Sail steel for structural steel work  Make list: - Asian paints, Berger, Dulux for Red oxide work</p>	Quintal	201.88

8	14012 AA	Providing and laying polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1-cement : 6-coarse sand) or L.M. 1.1.5 (1-Lime putty :1.5 - coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. complete. (A) 25mm thick.	Sqm	13.75
9	-	Supply & fixing and bending of Aluminum Composite Panel (ACP), 4 mm thick of brand Aludecor, aulomax, Alstrongetcin required colours for exteriors consisting of two layers of aluminum skins of 0.50 mm thick sandwiching a thermo plastic core in continuous lamination process with PVDF coating for exterior grades ensuring long colour and no fungal attacks. With Base frame work with aluminum sections of 50mm X 25mm of 1.5 mm thk and should be of Jindal / Hindalco or (IS spec) brand, AND 100 MM EMBOSSING IT WITH BLACK ACP WITH CNC WORK shall be fixed over the fabricated grid of 50 X 50 HSS pipe with not less than thickness of 3 mm as per drawing, and the above aluminium panels shall be fixed to the frame work as cladding with material:- 3M tape and silicone dowcorring 789weather silicone in 995 dowcorring. Also provide the Cantex Jali behind the elevation treatment. Rates includes cost of labour, Bending of ACP, accessories, adhesives, scaffolding, wastages, transport, taxes, fixing into a neat finish in aesthetic point of view, without any undulations in facias all complete and some other miscellenous items not mentioned shall be as per the Instruction of engineer in-charge.	Sqm	46.88
10	-	Required Electrical work, Panel, cable, conduit, General Light Fixture and accessories ro carried out the electrical work for lift and staircase complete in all respect, as per site requirement and instructions given by the consultant/engineer, to the Lift Contractor. Required civil work for foundation, flooring and Scaffolding necessary for erection, and all minor builder's work for cutting away and making good to walls and masonry work required, including repairs to plaster, whitewash etc. Further, all chase cutting, and openings as required by the Lift Contractor and shown on his drawings, will be carried out by the Lift Contractor. Machine RS beams and/or MS channels for support of lift machinery and buffers of reputed Make such as Jindal, Tata Steel or SAIL only shall be supplied and erected including civil works, complete in all respect, as per site requirement and instructions given by the consultant/engineer, to the Lift Contractor.	Job.	1
11	-	5 Year Comprehensive AMC amount of Lift		