



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
<b>A</b>	<b>Part-1</b>				
1	Demolition of brick work & stone masonry with any type of plaster, paint, skirting, dedo etc. including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (III) In cement mortar.	58.20	Cu.mt	0.00	0.00
2	Demolition of any type of R.C.C work with TMT bars, any type of plaster, paint, skirting, dedo etc. including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (I) R.C.C work.	114.00	Cu.mt	0.00	0.00
3	Dismantling all type of tiles flooring, or stone flooring laid in mortar, any type of flooring with mortar, waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	1823.00	Sq.mt	0.00	0.00
4	Dismantling all type of wall tiles, dedo and any type of (stone/ tiles) clading laid in mortar, any type of flooring with mortar, waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	590.00	Sq.mt	0.00	0.00
5	Dismantling all type of wooden flooring, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	78.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
6	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	2017.00	Sq.mt	0.00	0.00
7	Dismantling any type of doors, windows, ventilators etc. (wood of steel) shutters with chowkhats, architraves, holdfasts, any type of frame and other attachments etc complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (i) Not exceeding 3 Sq.M in area	25.00	Each	0.00	0.00
8	Dismantling any type of doors, windows, ventilators etc. (wood of steel) shutters with chowkhats, architraves, holdfasts, any type of frame and other attachments etc. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (II) Exceeding 3 Sq.M in area	11.00	Each	0.00	0.00
9	Dismantling fixed glazing including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (II) Exceeding 3 Sq.M in area	75.00	Sq.mt	0.00	0.00
10	Removing dry or oil bound distemper, all type of paint and texture paint by a washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	3469.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
11	Remove of existing Fabrication and steel structure including plates, rolled steel joists, channels, angles and all type of accessories etc. including stacking of the materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	6699.00	Kg	0.00	0.00
12	Removal of existing Male toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank, Urinal, all type of cock, accessories, basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (Male Toilet)	1.00	Per toilet	0.00	0.00
13	Removal of existing Female toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank, all type of cock, accessories, basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (Female Toilet)	1.00	Per toilet	0.00	0.00
14	Removal of existing Existing attached toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank, all type of cock, accessories, basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (attach Toilet)	2.00	Per toilet	0.00	0.00
15	Dismantling wooden boardings (Wooden skirting/base) thickness above 25 mm up to 40 mm in lining of walls and partitions, including stacking the materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	82.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
16	Removing and scraping of old deteriorated plaster of any thickness from wall / R.C.C member including stacking of serviceable material and disposal of unserviceable from site of work with all lead and lift. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	54.00	Sq.mt	0.00	0.00
17	RCC Core cut : Drilling with core cutting machine in RCC beams,slabs,floors etc.,for laying pipes and rendering the same in RCC 1:2:4 finishing the same to the satisfaction of the Architect/EIC.etc., complete, at all levels. The rate shall also include for providing EPOXY based water proofing compound for sealing the joints around the pipes upto any depth at all heights & levels. Work complete including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC. a) 100 mm dia	20.00	Nos	0.00	0.00
18	RCC Core Cut : b) 150mm dia.	10.00	Nos	0.00	0.00
19	RCC Core Cut : b) 200mm dia.	10.00	Nos	0.00	0.00
20	Providing & laying any thick Brick Masonry work using common burnt clay building bricks having crushing strength not less than 35 Kg/Sq. Cm. at all levels in cement mortar 1:6 (1 cement :6 fine sand) - including proper filling of all masonry joints, curing etc. complete. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. (II) Conventional brick work	26.00	Cu.mt	0.00	0.00
21	Providing and laying Half brick masonry in common burnt clay building bricks having crushing strength not less than 35 Kg./Sq. Cm. in cement mortar 1:4 (1 cement : 4 coarse sand) in superstructure - at all floor levels including proper filling of all masonry joints, curing etc. complete. Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/EIC. The rate includes providing and placing in position 2 Nos 6 mm dia bars at every third course of masonry work.	337.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
22	15 mm thick cement plaster : Providing and laying average 15 mm. thick single coat smooth finishing using steel float (mala finish) plaster in CM 1:4 (1 cement : 4 coarse river sand), on brickwork, RCC work, blocks, sills, soffits, jambs etc. at all floors, all levels, all heights, all shapes and for all sizes with necessary scaffolding, curing, chicken mesh at the junction of masonry & RCC work using screw / dhoba nails, making moulded, grooves, drip moulds, tapak, chemical bonding agent etc., for all lead, lift, height and levels etc., complete as per specification and as directed by the EIC. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	1052.00	Sq.mt	0.00	0.00
23	20 mm thick Sand Faced Plaster: Providing and applying 20mm thick sand faced plaster (Using Wooden Gutka/Float) to all external surfaces at all levels and in any shape, in two coats, 12 mm thick average base coat in cement mortar 1:5 and 8mm thick finish coat in cement mortar 1:2 using fine sand for finish coat, including preparation of surface to uniform texture, staging, double scaffolding, curing, chicken mesh at the junction of masonry & RCC work using screw / dhoba nails, making moulded, grooves, drip moulds, tapak etc., complete as per specification and as directed by the EIC. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	738.00	Sq.mt	0.00	0.00
24	Providing 20 mm thick double coat mala cement plaster on interior brick / concrete work for plastering comprising of base coat of 12 mm thick cement plaster in cement mortar (1 Cement : 4 coarse sand) in rough finishing and 8 mm thick top coat of cement mortar 1:2 (1 Cement : 2 Coarse sand) finished with trowel including scaffolding, safety measures , curing etc. complete.	4.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
25	Providing and laying cement concrete 1:4:8 (1- Cement : 4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete. including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	26.00	Cu.mt	0.00	0.00
26	Filling in plinth with sand under floors including watering ramming, consolidating and dressing complete. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	330.00	Cu.mt	0.00	0.00
27	Providing and laying ordinary cement concrete 1:2:4 (1-Cement 2-coarse sand: 4-graded stone aggregates 20 mm nominal size) for R.C.C lintel including finishing smooth with, curing, safety measures etc. complete including the cost of form work but excluding the cost of reinforcement. including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	4.00	Cu.mt	0.00	0.00
28	Providing and laying controlled cement concrete M.250 and curing complete including finishing smooth with, curing, safety measures etc. complete including the cost of form work but excluding the cost of reinforcement. including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. in (C) Slabs, landing, shelves, Balconies, Lintels, Beams, Girders and Cantilever etc.	68.00	Cu.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
29	TMT Bars: Providing, straightening, cutting, bending, binding and laying in position of TMT FE 500/500D grade steel reinforcement confirming to IS 1786 : 1990 or latest code, to correct all shape and size as per detailed drawings, specifications for all RCC work etc, at all levels and all heights with necessary chairs and laps; with correct size PVC cover blocks or approved quality concrete cover blocks of same grade of concrete and binding wire of 18 gauge etc. complete with test certificate of the steel bars from manufactures as well as approved laboratory test certificates directed by Engineer in charge, etc. complete. Rate shall be inclusive of binding wire, cover, lap, chair etc. Work shall complete up to any levels, all floor & as per the instruction of EIC.	7715.00	Kg	0.00	0.00
30	Carring out plinth treatment to post construction / existing structure by spraying chemical solution for termite control treatment including labour and material consistment with I.S.I specification. Using Chlordene and Chiorpurfiles 20 EC. As Per 6131_paret-II Consentration Weight one percent is recommended i.e one litre 20 EC chemical emulsion with 19 liter give 1 % concentration inclusive of one litre chemical emulsion appication at the rate of 5 Litre chemical / Sqm of surface is recommended as per I.S. The whole work is to be executed through specialized agency with a guarantee of 5 (Five) years given on a prescribed proforma duly stamped. The waterproofing work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools, tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instnuction of EIC/Client/Architect.	1853.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
31	<p><b>Toilet Waterproofing</b> : Providing and Applying of waterproofing treatment in toilet block as per below specification.</p> <p>The concrete surface must be brought into surface saturated dry condition (SSD). Providing &amp; Applying 2 coats of high performance two component prepacked cementitious waterproofing, Dr. Fixit Pidifin 2K, with a mix ratio of (liquid: Powder), parts by wt. - 1:2 at the rate 0. 55 - 0.58 Sq.mt / Kg for 2 coats to achieve the DFT of 1mm in a span of 4 - 6 hours with a roller / brush on the prepared concrete substrate. Over the splash zone / shower wall taking the coating up the full height and up to 1 meter height on vertical surface and on other walls and 0.3 metre on horizontal surface below threshold for complete bathroom waterproofing. All the coats to be applied in perpendicular direction to each other. Allow the coating to air cure for 3- 5 days before conducting water ponding test for 24 Hrs. The coating shall have Elongation at break &gt; 50% as per ASTM D 412, Tensile strength &gt; 1 N/mm2 as per ASTM D 412, Adhesion strength: 0.80 N/mm2 as per ASTM D 4541, crack bridging upto 1mm as per ASTM C 836, Water penetration (5 bar pressure) as per BS EN 12390.</p> <p>The whole work is to be executed through specialized agency with a guarantee of 5 (Five) years given on a prescribed proforma duly stamped. The waterproofing work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools , tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instuction of EIC/Client/Architect.</p>	23.00	Sq.mt	0.00	0.00
32	<p><b>Rising Dampness and Negative side waterproofing for internal walls:</b> For rising dampness and encapsulation treatment of dampness on internal walls treatment to be done with Diasen -Watstop, a 3 component product having resistance to water ingress of 9.5 ATM for both Negative side and positive and should have excellent resistance to Salt. Diasen - Watstop to be applied in 2 coats at consumption rate of 1 kg/m2. The application can be done by Brush or roller to give smooth and even finish good enough for putty/paint application. Work complete including all type of tools , tackles, scaffolding etc complete at any level and height. work complete as per the instuction of EIC/Client/Architect.</p>	22.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
33	<b>Toilet Flooring</b> : Providing and laying Lapato/Matt/Glossy/ Non Skid/Rustic finish /Sugar finish Vitrified tiles flooring using minimum 10 mm thick tiles of as per approved make list by architect/client, tile size (600 mm X 600 mm) including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing/ instruction and approval by architect. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of tile is Rs. 40/Sqft	39.00	Sq.mt	0.00	0.00
34	<b>Toilet Dado Work</b> : Providing and laying Lapato/ Matt /Glossy/ Non skid,/Rustic finish/sugar finish Vitrified tiles in dado using minimum 10 mm thick tiles as per approved make list by architect /client (tile size 600 mm X1200mm) fixed in dado on 10 mm th. Cement plaster 1:3 (1 cement: 3 coarse sand) All surfaces must be dimensionally stable according to IS 1443-1972, level, cured, undamaged, compact,rigid,resistant, dry and free from any debonding agents tiles fixed by approved tile adhesive and all application shall be done under instruction of manufacturer guideline and specification, and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. Basic rate of tile is Rs. 45/Sq.ft	245.00	Sq.mt	0.00	0.00
35	<b>Vitrified Flooring:</b> Providing and laying Lapato/ Glossy/ Matt/ Rustic/ Sugar/ Satin finish Vitrified tiles flooring using minimum 10 mm thick tiles as per approved make list or selected by Architect , tile size 600 x 1200 mm including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand ) and jointed with 3mm thick epoxy grouting of approved shade and colour in proper line and level as per detailed drawing/ instruction and approval by architect.The rate shall be inclusive of protecting the flooring by plaster of Paris and plastic and/or bubble top sheets. Basic rate of tile is Rs. 55/Sqft.	5.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
36	<b>Vitrified Flooring : Matt finish tile size 800 x 1600 mm</b> "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 70/Sqft.	166.00	Sq.mt	0.00	0.00
37	<b>Vitrified Flooring : tile size 1200 x 1800 mm: Matt finish Intra Gray</b> "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 90/Sqft.	696.00	Sq.mt	0.00	0.00
38	<b>Vitrified Flooring : Matt finish tile size 600 x 600 mm</b> "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 40/Sqft.	46.00	Sq.mt	0.00	0.00
39	<b>Vitrified Flooring : Designer Mosaic tile size 200 x 200 mm</b> "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 150/Sqft.	115.00	Sq.mt	0.00	0.00
40	<b>Vitrified Skirting work :</b> Providing and laying Lapato /Glossy finish vitrified tiles in skirting using minimum 10 mm thick vitrified tiles of approved make list or as selected by Architect of premium quality fixed in skirting on 10 mm thick Cement plaster 1:3 (1 cement : 3 coarse sand) and jointed with 6 mm thick-min. 75 mm height laticrete grouting of approved shade and colour in proper line and level for average 125 mm height as per detailed drawing/ instruction and approval by architect. Basic Rate of tile is Rs.55/Sqft.	2.00	Sq.mt	0.00	0.00
41	<b>Vitrified Skirting work :</b> "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 70/Sqft.	7.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
42	<b>Vitrified Skirting work :</b> "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 40/Sqft.	6.00	Sq.mt	0.00	0.00
43	<b>Vitrified Skirting work :</b> "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 90/Sqft.	3.00	Sq.mt	0.00	0.00
44	<b>Dry cladding : 1200 x 600 mm Tiles</b> Providing and laying finish minimum 10 mm thick Travertine tiles Cladding ( 1200 x 600) of approved make list or as selected by Architect of premium quality on fixed on Aluminum framework of 25x40 mm section fixed on wall with clamps, pins & required fittings. All joint sealed with approved sealant approved shade and colour in proper line as per detailed drawing/ instruction and approval by architect. work complete including all type of fittings, fixtures etc shall be per approved make by Architect, bending, bidding, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client.Basic rate of tile is Rs.55/Sqft.	679.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
45	<p><b>Dry cladding : 2400 x 1200 mm : BULL BERRY GREY : Lift lobby</b> Providing and laying Lapato/Glossy finish minimum 10 mm thick vitrified tiles in cladding of approved make list or as selected by Architect of premium quality fixed in cladding on 12mm thick cement sheet with approved adhesive. Cement sheet fixed on Aluminum framework of 25x40 mm section fixed on wall with clamps, pins &amp; required fittings. All joint sealed with approved sealent approved shade and colour in proper line as per detailed drawing/ instruction and approval by architect. work complete including all type of fittings, fixtures etc shall be per approved make by Architect, bending, bidding, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Basic rate of tile is Rs. 125/Sqft.</p>	185.00	Sq.mt	0.00	0.00
46	<p><b>Corner Guard:</b> Providing and fixing 1.2mm thick &amp; 14mm high Stainless Steel profile corner guard (304 grade) with powder coated of approved make list or as selected by Architect. All joint sealed with approved sealent approved shade and colour in proper line as per detailed drawing/ instruction and approval by architect. work complete including all type of fittings, fixtures etc shall be per approved make by Architect, bending, bidding, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client.</p>	62.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
47	<b>Granite Stone Flooring</b> : Providing & laying approved quality 18 mm thick Granite stone flooring of approved shade, in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Granite stone is Rs. 150/ Sqft.	332.00	Sq.mt	0.00	0.00
48	Granite Stone work: Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias, risers of steps, dedo and pillars and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish, grooving etc. complete at all levels. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Granite 150/ Sq.ft	150.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
49	<b>Artificial Stone Flooring</b> : Providing & laying approved quality 15 mm thick Artificial stone flooring of approved shade, in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Artificial stone is Rs. 150/ Sqft.	111.00	Sq.mt	0.00	0.00
50	Providing and laying 25mm thick polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1-cement : 6-coarse sand) or L.M. 1.1.5 (1-Lime putty :1.5 - coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. All complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue.	49.00	Sq.mt	0.00	0.00
	<b>Total Amount</b>				<b>0.00</b>
<b>B</b>	<b>Part-2</b>				



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
51	Providing and laying polished kota stone slab 25mm thick in risers of steps,skirting Dedo and pillars laid on 10mm thick cement mortar 1:3 (1- Cement : 3 coarse sand) and jointed with gray cement slury mixed with pigment to match the shade of slab including rubbing and polishing etc. All complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue.	5.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
52	<b>Vinyl flooring</b> : Providing and fixing 2 mm thick wooden finish Vinyl flooring (Tile / plank) including necessary material, adhesive tools, tackles, fittings etc complete. Work complete for at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC.Sample mock shall be approved from Architect/EIC.	114.00	Sq.mt	0.00	0.00
53	<b>Artificial Stone door frame (up to 250 mm width):</b> Providing & laying approved quality 15 mm thick Artificial stone work of approved shade (selected and sorted for its uniform colour and thickness)., in door frame etc. in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. including 4 mm deep groove, at all floors, all levels, all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue .Basic rate of Artificial stone is Rs. 150/ Sqft.	109.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
54	<b>Artificial Stone window sill (up to 250 mm width)</b> : Providing & laying approved quality 15 mm thick Artificial stone work of approved shade (selected and sorted for its uniform colour and thickness), in window sill etc. in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. including 4 mm deep groove, at all floors, all levels, all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue .Basic rate of Artificial stone is Rs. 150/ Sqft.	82.00	Rmt	0.00	0.00
55	<b>Granite stone/ Artificial stone Pantry Platform:</b> Providing & fixing two layers of Pantry Platform, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of 15 mm thick Granite stone, joined together with 1:4 Cement mortar bedding / approved tile adhesive, to true plane & level or to slopes, or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 1'6", cutting stone as per required shape & size to fit sink & 3" to 9" fascia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. finished as per design in detail drawing and instruction of Architect/EIC.sample mock shall be approved from Architect/EIC. Basic rate of stone is Rs.150/ Sqft.	20.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
56	<b>Artificial Stone Counter:</b> Providing & fixing two layers of Platform, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of 15 mm thick Artificial stone, joined together with 1:4 Cement mortar beding / approved tile adhesive, to true plane & level or to slopes,or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including both sides & niche in same stone, cutting stone as per required shape & size with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. finished as per design in detail drawing and instruction of Architec/EIC.sample mock shall be approved from Architect/EIC. Basic rate of stone is Rs.330/ Sqft.	5.00	Rmt	0.00	0.00
57	<b>Artificial stone top Wash basin counter for toilet:</b> Providing & fixing two layers of wash basin counter, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of 15 mm thick Artificail stone, joined together with 1:4 Cement mortar beding / approved tile adhesive, to true plane & level or to slopes,or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 1'6", cutting stone as per required shape & size to fit Wash basin & 3" to 9" facia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. finished as per design in detail drawing and instruction of Architec/EIC.sample mock shall be approved from Architect/EIC.Basic rate of Artificial stone is Rs.150/ Sqft.	7.00	Rmt	0.00	0.00
58	<b>Single Leaf Flush Door finish with one side veneer &amp; one side laminate:</b> Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with one side 4 mm thick veneer with matt finish monocoat polish and one side 1 mm thick Laminate as approved, wooden frame with polish, Hardware fittings like door closer, Door handle, lock , Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings , fixtures, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. Basic Rate of veneer - 120/Sqft. & Equivalent to VNR series laminate.	5.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
59	<b>Single Leaf Flush Door finish with VNR laminate:</b> Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 1 mm thick VNR laminate s approved, 8mm toughened milky Glass view panel, door fixed on frame (excluding stone frame), Hardware fittings like concealed door closer or floor spring, Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, bending, bidding, safety measures , as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Equivalent to VNR series laminate.	26.00	Sq.mt	0.00	0.00
60	<b>WPC shutter with laminate finish (Duct area):</b> Providing and fixing in position 12 mm thick WPC shutter of approved make with laminate finish as approved, shutter fixed with floor and above pivot of approved make, pivot cover plate, safety measures, lock & handle etc fixtures of approved make list with all necessary fittings etc. aluminium frame 25x30 Complete as per detailed drawings and specifications.	38.00	Sq.mt	0.00	0.00
61	<b>Acoustic Door:</b> Providing & fixing Single Leaf Flush Door 50 mm thick with both side veneer finish with Polish; Door frame shall be from Ply with -Veneer with matt finish monocoat polish, infill 25mm thick rockwool (48 kg/cumt density) with necessary vinyl gripper, necessary fittings. Hardware fittings like concealed door closer Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures etc shall be per approved make by Architect, bending, bidding, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Basic Rate for material only teak veneer - 120 /Sq.ft.	8.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
62	<p><b>Sliding window: Domal section : 27x65 mm series</b>            Supply &amp; Fixing of Aluminium sliding window with powder coated as per by approved make &amp; sample by architect/EIC.            Frame section: 40 x 89 x 1.5 mm            Shutter section : 27x 65 x 1.5 mm            Mosquito shutter : 27 x 65 x 1.5 mm            Glass : 6mm Thick SGU Toughened Glass of Saint Gobain ET125 6mm FT Neutral shade approved make list .            including EPDM Gasket, Woolen In Shutter, Multiple Lock, Anti Rattling Guide, Lock Guide, handle Antilifting, Shutter Corner Clit, Shutter wing Connector, Interlock EPDM Gasket, Interlock Guide, Anti Capillary Pad, Bush Bottom silicon all side &amp; All Necessary Hardware etc. complete as per detailed drawings, mock sample and specifications.</p>	2.00	Sqm	0.00	0.00
63	<p><b>Toilet ventilator</b> : Providing and fixing standard extruded of alluminium section of size 63 mm x 38.10 mm x 1.2 mm ( jindal section : 2434 @ wt. 0.643 kg per mt with colour powder coated alluminium frame for ventilation with 5 mm thick frosted / milky glass with provision of exhust fan etc complete as per drawing .</p>	2.00	Sq.mt	0.00	0.00
64	<p>Applying two coats of Birla (white cement based) or Asian (acrylic lapy- putty) or equivalent &amp; two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth.</p>	3217.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
65	<b>Interior paint</b> : Providing & laying of 3 (three) coats with Royale luxury Emulsion paint of Asian Paint or equivalent approved brand in shades and colour as directed on wall surfaces to give an even shade incl. scaffolding to at any height with all labour and material after thoroughly brushing the surface & making free from mortar droppings and other foreign matter including surface preparation etc.complete. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift, safety measures , performance warranty certificate etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. The substrate must be sound, clean, dry, free from dust, oil, grease and laitance etc. All traces of release agents must be removed. On chalky and dusty surfaces, all loose material must be removed by stiff bristle brushing. The primer / paint application is to be done with the rollers. rate shall be including crack filling and levelling as per manufacturers specification.	3217.00	Sq.mt	0.00	0.00
66	<b>Wall Punning</b> : Providing and applying 12 mm thick (average) premixed formulated one coat gypsum lightweight plaster having additives and light weight aggregates as vermiculite/ perlite respectively conforming to IS: 2547 (Part - 1 & II) 1976, applied on hacked / uneven background such as bare brick/ block/ RCC work on walls & ceiling at all floors and locations, finished in smooth line and level etc. complete.	1181.00	Sq.mt	0.00	0.00
67	<b>EWC</b> : Providing and fixing wash down water closet (European type W.C. pan with Jet) as per approved make of selection & shade with seat cover, P OR S Trap M.S. or G.I bracket , CP brass hinges and rubber buffers and Jointing the trap with soil pipe in cement mortar : 1:1 (1 cement : 1 fine sand), including cutting and making good the walls and floors where required with all labour and materials. All works to be carried out as per instructions and direction of Engineer-in-charge. Model Equivalent to Q617240110	3.00	Nos	0.00	0.00
68	Providing and fixing <b>Consealed cistern tank</b> with frame work & Flushing plate of as per approved make by architect.Model Equivalent to Q507450100 + Q507455320	3.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
69	Providing and fixing 12mm dia. <b>Health faucet</b> with 8 mm dia of as per approved make selected by Architect with flexible pipe of 1.mt. length and holding stands complete. Model Equivalent to Q503192520	3.00	Nos	0.00	0.00
70	Providing and fixing Counter top <b>Wash Basin</b> of as per approved make of selection including fittings and waste pipe etc. and fixing on wash basin counter by tile adhesive of approved make. Model Equivalent to Q827142214	4.00	Nos	0.00	0.00
71	Providing and fixing 15mm dia <b>Basin spout</b> of as per approved make of selection. Model Equivalent to Q403114221	4.00	Nos	0.00	0.00
72	Providing and fixing 15mm dia two way <b>Bib cock</b> of as per approved make of selection. Model Equivalent to FLR-CHR-5041N	3.00	Nos	0.00	0.00
73	Providing and fixing chromium plated <b>Bottle Trap</b> of as per approved make of selection with necessary coupling of approved make for wash basin & sink. Model Equivalent to Q503191720 + Q503191520	6.00	Nos	0.00	0.00
74	Urinal : Providing and fixing <b>urinal with zinnia sensor integral battery operated</b> , of as per approved make of selection including connecting the urinal with waste pipe and all works related to this item etc complete. Model Equivalent to Q257630210	2.00	Nos	0.00	0.00
75	Providing and fixing in position <b>Soap Dispenser</b> of as per approved make of selection with soap container. Model Equivalent to ACN-CHR-1135N	6.00	Nos	0.00	0.00
76	Providing and fixing <b>Toilet papers holder</b> of as per approved make of selection or as directed by EIC. Model Equivalent to ACN1153N	3.00	Nos	0.00	0.00
77	Providing and fixing <b>Towel rack</b> of as per approved make of selection or as directed by EIC. Jaquar ACN-1121N	6.00	Nos	0.00	0.00
78	<b>Handrayer</b> : Providing and fixing in position of Handrayer of as per approved make list. Work completed as per the instruction of EIC. Model Equivalent to HDR-SAP-M99ACS	3.00	Nos	0.00	0.00
79	Providing and fixing 15mm dia. <b>Angular Stop Cock</b> of as per approved make of selection. Model equivalent to Q503191120	6.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
80	Providing and fixing 15mm dia. <b>Sink Cock</b> of as per approved make of selection. Model equivalent to: FLR-5347N	2.00	Nos	0.00	0.00
81	Providing and fixing <b>Kitchen sink</b> as per approved make including all fitting material including Fixing of with necessary plumbing work as per detail drawing and plumbing work .Material approved by architect/EIC. Nirali : Grace Plain-510MM X 432MM	2.00	Nos	0.00	0.00
82	Dustbin : Providing and placing in position S.S. Solid Pedal Bin with inner removable container of as per approved make and as selected by the Architect. Size: 10" X 15"	25.00	Nos	0.00	0.00
83	Providing and fixing 6 mm thick <b>mirror</b> of Saint Gobain/ Modiguard / Asahi as per approved make shall be fixed with profile frame section (copper/brass/silver/gray/black etc.). Provision shall be made for conceal led light work as per detailed drawing / instruction of architect complete. Rate shall be inclusive of frosting work as per detail drawing.	6.00	Sq.mt	0.00	0.00
84	<b>Toilet Cubical</b> : @1000(W) X 1500(D) x 2050(H) mm Supply & Installation of Toilet Cubicles as per as per Architect selection & approved make. 12 mm Compact Grade 1.5 mm thick laminateBoard of the approved shade by Architect . Accessories for cubicles.1. Aluminum "U" Section with SS Exterior grade Finish.2. Aluminum "H" Section with SS Exterior grade Finish.3. Aluminum Top Rail with SS Exterior grade Finish.4. SS Coat Hook (SS 316 )5. SS Privacy Thumb Turn (SS 316)6. SS Door Knob (SS 316)7. SS Hinges (SS 316)8. SS Adjustable Leg (SS 316)With Rubber lining and Screw Etc. Work complete including all type of fittings, fixtures, tools, etc complete as per manufacturer specification and drawing.	2.00	Nos	0.00	0.00
85	<b>JC shutter:</b> Supply & Installation of Cubicles with shutter as per as per Architect selection & approved make. 12 mm Compact Grade 1.5 mm thick laminateBoard of the approved shade by Architect. Accessories for cubicles.1. Aluminum "U" Section with SS Exterior grade Finish.2. Aluminum "H" Section with SS Exterior grade Finish.3. Aluminum Top Rail with SS Exterior grade Finish.4. SS Coat Hook (SS 316 )5. SS Privacy Thumb Turn (SS 316)6. SS Door Knob (SS 316)7. SS Hinges (SS 316)8. SS Adjustable Leg (SS 316)With Rubber lining and Screw Etc. Work complete including all type of fittings, fixtures, tools, etc complete as per manufacturer specification and drawing.	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
86	Providing and fixing S.S. Nahni trap for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with SS/ C.I screed down or hinged grating including the cost of cutting and making good the walls.	6.00	Nos	0.00	0.00
87	Urinal Partition: Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick or required size as per drawing, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth. Basic rate of stone is 150/ Sq.ft	1.00	Sq.mt	0.00	0.00
88	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [A] 15 mm.	11.00	Rmt	0.00	0.00
89	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [C] 25 mm.	82.00	Rmt	0.00	0.00
90	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [D] 32 mm.	65.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
91	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [E] 40 mm.	60.00	Rmt	0.00	0.00
92	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [F] 50 mm.	45.00	Rmt	0.00	0.00
93	Providing laying and jointing in true line and level 50mm dia. U.P.V.C. Pipe ( SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be cancelled as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	45.00	Rmt	0.00	0.00
94	Providing, laying and jointing in true line and level 110 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diameter x 149 mm length x 145 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	68.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
95	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure polythene pipes of the following outside Dia. Low density, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(F) 75mm	100.00	Rmt	0.00	0.00
96	Fabricated work: Providing Fabrication & erection of steel structure as per drawings including materials, consisting of plates, rolled steel joists, channels, angles, chequered plates etc and also rectangular / square hollow steel sections, insert plates in RCC/Brickwork, anchor bolts for steel structure, sleeve pipes, anchor nuts, washers etc, straightening of raw steel if required, fabrication of steel structures with primer and minimum two coats of anti corrosive paint including preparation of supplementary sketches and detailed bill of materials supply of bolts, nuts, washers, shims, packs, putty. gas, welding electrodes and all other consumables, as required and carrying out surface preparation all complete. The scope includes loading, transportation, unloading and delivery and erection site of all fabricated structures, alignment and welding of all structures true to line, level, plumb and dimension, including rectification if any, splicing, site assembly all as per technical specifications and drawings, ,all complete.Contactror shall provide stability certificate for the fabrication structure. Rate inclusive of shop drawing.	5632.00	KG	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
97	<p><b>ACP Cladding:</b> Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building , for all heights and all levels etc. including: (a) Structural analysis &amp; design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design. (b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. (c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material &amp; labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium item.s The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete , as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of groove) shall be measured in sqm. up to two decimal places.</p>	69.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
98	<p><b>S.S. Railing : Vetroline 10401 T3 (M) Handrail Round 50mm</b>            Providing and fixing 1050mm high SS Railing (304 grade) system comprising 50mm dia. and 16 guage (1.6mm) Stainless steel pipe top handrail (SS 304 - Matt Finish), 35mm dia. and 16 guage (1.6mm) Stainless steel pipe at bottom &amp; vertical support and 16mm dia. and 16 guage (1.6mm) Stainless steel vertical intermediate pipe (SS 304 - Matt Finish) placed at 100mm c/c distance and as per site requirement. Railing fixed on floor with 120x50x10mm base plate. whenever required, joints to be filled with bushings for extra strength. Rates should be inclusive of welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, including fixing the railing with necessary accessories &amp; stainless steel dash fasteners, stainless steel bolts etc., of required size, on the side of waist slab/wall with suitable arrangement as per approval of Engineer/ Architect. Work shall complete includes all type of tools, tackles, all level &amp; Height, labour, safety measures, mock sample etc complete as per the detailed drawing and instruction of EIC. Note :Handrail Length will be measured from Starting to End Location</p>	229.00	Rmt	0.00	0.00
99	<p><b>Glass mosaic tiles:</b> Providing and fixing Glass mosaic tiles on finished plain wall surface of size 2.5x2.5 cm in all colour, design , fixing in customize design as per direction of Engineer-in- Charge. The glass mosaic tiles to be fixed on the wall surface with the help of approved adhesive applied at the rate of 2.5 kg per sqm and grouting of the same. The rate is inclusive of all operation, material and required pattern approved by Engineer-in-Charge: work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Model Equivalent to Piccolo Blend Aligned series. Basic rate of Mosaic 185/ Sq.ft</p>	80.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
100	<b>11 foaming LOW HEIGHT WATER FOUNTAIN:</b> Design, supply, installation, erection, commission & testing of water Fountain in water body, In the fountain design with Upvc pipe/ pipe fitting with control valves, 3 mtr cable with, Low Head High flow 3.0 hp 3 phase, pump set with suction filter unit, isolation valves, piping fittings etc set cluster of special type of uniform nozzles water distribution system in the centre water body in civil work. including under water LED WARM WHITE / MILKY WHITE / RGB Colour changing Lights water proof – 11 no Driver and RGB controller, 4 core Cabling 3 meter, Powers supply 230 to 12 Volt Dc. etc. complete. with EDGE LIGHING EFFECT FOR INFINITY TYPE.work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	2.00	Job	0.00	0.00
	<b>Total Amount</b>				<b>0.00</b>



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
<b>C</b>	<b>Part-3</b>				
101	<p><b>Gypsum 30min Fire Resistance ceiling:</b>  M/F Suspended 30min Fire Resistance ceiling includes Gypserra™ Perimeter Channel {Material-GI(IS513),YS-260Mpa,Finish- Galvanised 150GSM(IS27 )} is fixed along the perimeter of existing wall/ partition with the help of HILTI HPS - 1 (6x40) impact anchor, at 600mm centres. Gypserra™ Ceiling Angle {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is suspended by fixing it to the Gyproc® soffit cleat {GI(IS513)YS-260Mpa,Finish-Galvanised 150GSM(IS277) }. Soffit Cleat and Gyproc® Rawl Plug- Ø8x45mm {Material-IS 513 CR2 grade, Zinc coating (7 to 8 microns) pull out load- 6.8kN for M30 concrete grade} creating 1220mm x 1220mm grid. Gypserra™ Intermediate channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277) } is fixed to the Gypserra™ Ceiling Angle with M6 x 12mm Hex Bolt &amp; Hex Nut arrangement {Material-As per EN 10083 Finish – Zinc Plating} or with 2 Nos of Ø4.2x13 Gyproc® metal to metal screw {Material-Carbon steel EN-ISO 7049/50 Finish- Zinc Coating Thickness- 4.14micron.} The Gypserra™ Ceiling Section {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is then fixed to the Gypserra™ Intermediate Channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} with the help of Gyproc® Connecting Clip {Material-High carbon spring steel wire(BS970Gr.En42)-46-48HRC,Finish- Zinc plating 4-6 micron} and in direction perpendicular to the Intermediate channel at 457mm c/c. Use 50mm thick rockwool above ceiling for fire insulation, then Single layer of 15mm tapered edge Gyproc Firestop Board as per (EN 520: 2004, Type F) is then screw fixed to ceiling section with 25mm drywall screws {Material-Carbon steel EN-ISO 7049/50,Finish-Case hardened Grey Phosphating} at 230mm centres on ceiling section &amp; 150mm at periphery of ceiling. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Easy-fill 90 Jointing compound (Conforms to ASTM C475), Gyproc® Joint Paper tape. Serrated section has effective thickness of 2T ( 2xdepth), better load carrying capacity.</p> <p>The item includes providing and fixing trap door of size 600 X 1200 mm as per approved sample of Ceiling panels comprise of a powder-coated beaded steel frame with gypsum / plywood board door. Each panel features a push-latch closing mechanism with door retaining safety cable &amp; hook.Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing, , safety measures necessart framing work if required etc. complete work. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price.</p>	897.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
102	<b>Wooden ceiling finish with Veneer:</b> Providing and fixing IS 710 12 mm thick Marine plywood ceiling finish with 4 mm thick veneer as per drawing, instruction, sample approved & complete with Aluminium anodised section size 50x50x1.5 mm & 25x50x1.5 mm / GI frame work. the frame work fixed as per drawing @ 600 mm c/c. finish with 4 mm thick Veneer with matt finish monocoat polish. Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, CNC engraving , beads and also provide support/template where ever required. The rate shall be in sq.mt for all floors and at all heights including all costs. (or a sample mock of 5 Sqm minimum of the frame work and ceiling) shall be approved from Architect. 5mm Groove shall be provided at the junction of the ceiling & the wall. (considering all levels with require all Framing work and fitting from RCC slab to ceiling level). Basic rate of teak Veneer 120/Sqft	71.00	Sq.mt	0.00	0.00
103	<b>Fluted panel ceiling :</b> " -----Do-----" as per above specification for complete work. Only finish with Fluted panel instead of veneer. Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, CNC engraving , beads and also provide support/template where ever required. The rate shall be in sq.mt for all floors and at all heights including all costs. (or a sample mock of 5 Sqm minimum of the frame work and ceiling) shall be approved from Architect.(considering all levels with require all Framing work and fitting from RCC slab to ceiling level). Basic rate of Fluted panel 440/Sqft	22.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
104	<p><b>Acoustic baffle ceiling :</b> Providing and fixing senses akustik echo band hanging acoustical baffles of 50 mm thick board, HT -450 mm, CC distance 150 mm, as per approved sample and make by Architect. Nrc- 0.80, echo band is biodegradable, voc free, non formaldehyde and Green certified product - ASTM D5116, fire test - Astm e84 , class 1 or A. Baffles will be fixed using channel &amp; clamp system Accessories : Wire suspension system with hooks including all accessories The work shall be done as per specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles, adhesives consumable hardware accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor/Supplier shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Work complete as per the Detailed Drawing, &amp; instruction of EIC. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required.The rate shall be in sq.mt for all floors and at all heights including all costs material and fittings, scaffolding.make list - Senses akustik , woven image , fliz felt.</p>	96.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
105	<p><b>Accoustic ceiling :</b> " -----Do-----" as per above specification for complete work. But with 9mm thick acoustical panel with using framing and then fixing 12.5mm perforated board with the help of screw and using rock wool of 50kg density and 50MM thick between framing and perforated sheet then Fixing Ecotone make Marco polyester fiber acoustic paneling with the specification of 9MM thick having density of 1.90kg/m2 with NRC value of 0.80 surface matt finish which is fixed with solution SR505 as required. The panel should have euro class BASTME84-13 fire rating. The color shade of Panel as approved by Architect. Work Inclusive of Cutting as per detailed drawing and instruction of Architect. Including surface preparation, Including cost of all type of tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc.work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	163.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
106	<p><b>Metal wooden finish ceiling 84C</b> : Providing and fixing wooden metal ceiling as per approved sample by Architect. Panel (Galvanized Steel): Metalium make 84C Panels are roll formed using state of the art roll forming lines to 84mm / 184wide, 12.5 mm deep &amp; 0.5 mm TCT Galvanized Steel as per IS-513 with recessed flange of 24 mm. Panel length is up to approximate 4 mtr. Panel shall be Wooden Powder coated on external surface only. When two panels are to be joined, they shall be joined together by means of panel coupler suitable for 84C.Paint Detail:Wooden Powder coated panel shall be chromatized for maximum bond between metal and paint, enamelled twice under high temperature, one side with full primer and finish coat, the other side (Inner side) with a primer coating and skin coat on continuous paint line or Wooden Powder coated panel shall be 50 microns thick on exposed surface.Installation detail: The carrier shall be suspended from slab / truss by 4mm dia galvanized rod &amp; height adjustment powder coated spring steel clips at maximum 1.2 to 1.5 meter centre to centre. The 4mm dia galvanized rod shall be fixed to slab by forming one end "J" shape with roll inserts.Carrier 84-C: Carrier shall be 20mm wide at bottom and 39 mm deep with cutouts to hold the panel in a module of 100mm / 200mm, carrier shall be roll formed out of 0.45 mm GI coil and cut to a standard length of the 2.4 mtr. When two or more carriers are to be joined, they shall be joined together by means of carrier coupler which will clip on to the holes in the sides of the cut carrier and hold them firmly in place while maintaining the module of 100mm / 200mmcentre to centre.Edge Profile: Edge profile shall be L-shaped, roll formed out of 0.5mm Galvanized steel strips with wooden powder Coating in standard colors.Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required.The rate shall be in sq.mt for all floors and at all heights including all costs material and fittings, scaffolding.</p>	103.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
107	<p><b>Wood Work Channeled Ceiling</b> : Providing and Fixing Knauf or equivalent Channeled Woodworks perforated panels of width 192mm, thickness of 15mm and length 2400 mm, made of a Moisture resistant fiber board substrate with a laminated facing as per the approved shade (Portland Maple, Sea Beech, Siam Wood &amp; Mystique Walnut, Interior White, Alumina Pearl) and a melamine balancing layer on the reverse side. The boards shall have a special perforation pattern where the reverse surface has a "Helmholtz" fluted perforation with consecutive 3mm wide groove followed by 21mm of visible pane. The edges of the panel shall be "tongue-and-grooved" to fix special clips for installation and seamless visual. The back of the perforated panel shall have sound absorbing non-woven Soundtex acoustical fleece hot pressed to achieve NRC of 0.5. (Average value of Absorption Co-efficient readings taken at 250 Hz, 500 Hz, 1000 Hz and 2000 Hz) as per ASTM C423 and Humidity Resistance (RH) of 70% with camber limit less than 1mm/1000mm and bow less than 1mm/300mm.The panels shall be mounted on special aluminum splines (keel) using inside clips provided by Knauf or approved by the Architect/ Engineer-in-Charge.</p> <p>Installation - An appropriate vapour barrier (by others) shall be applied/installed on the vertical surface before the installation to properly seal against entry of any moisture. Vapour barrier (by others) shall be installed as per Manufacturer's recommendation. Install wooden batten grid (provided by others) of section 50x50mm or as approved by the Architect on the solid wall/partition to provide level and plumb surface for fixing Keel. Install Keel vertically using screws and plugs at spacing of not more than 600mm centre-to-centre. The first and last keel should not be more than 150mm from the ends. Trim the tongue of the first bottom panel and install using headless nail with groove side upward. Subsequent panels are installed with tongue side downward by engaging with each other using tongue and groove mechanism and secured by inside clip. Continue this process until required height is achieved. Shorter butt edges need to be joined using industrial/wood glue. The keel shall also be used for transition of the butt end of adjacent panel at every 7.2m. Install the Skirting (provided by others) of width 50mm or more as required by the Architect/ Engineer-in-Charge. Finish off the edges using wooden moulding of matching colour (by others).</p> <p>Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required.The rate shall be in sq.mt for all floors and at all heights including all costs material and fittings, scaffolding.</p>	144.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
108	<p><b>Full Height Partition Gypsum Partition (60min. fire rating) :</b> 100mm thick Gypserra™ stud partition which includes inner layer of tapered edge 12.5mm thick Gyboard® Plain (conforming to IS 2095 Part 1:2011, Certified board) of size 1219x2438mm and outer layer of tapered edge 12.5mm thick Gyproc® Fireline board of size 1219x2438mm is screw fixed to C-stud.48x0.5mm Gypserra™ C-stud {Material-IS 513, Y/S-300Mpa, Finish - AZ150 (IS 15961)} placed at 610mm c/c in 50x0.5mm Gypserra™ {Material-IS 513,Y/S-300Mpa, Finish - AZ150 (IS 15961)} floor and ceiling channel.Floor &amp; Ceiling channel is anchored to the floor &amp; True ceiling using Gyproc® Rawl plug Ø8x45mm {Material-IS 513 CR1 grade, Zinc coating, Pull Out Load-6.8kN for M30 concrete grade} /Hilti X-GN20MX anchor fasteners at 600mm c/c in centerline manner.Floor channel to be wrapped with 70µ Self Adhesive LDPE moisture barrier film to further improve corrosion resistance performance. 12.5mm thick Gyboard® Plain board strip of 50mm width is placed between ceiling channel and RCC ceiling slab when deflection is more than 10mm &amp; fire rating is more than 30min. A Gypserra™ noggin channel {Material-IS 513,Y/S-300 Mpa, Finish - AZ150 (IS 15961)} of 50x0.5mm width has to be provided at the horizontal joints of the two boards. First layer of Gyproc® boards to be screw fixed with Gyproc® drywall screws of 25mm at minimum spacing of 600mm at centre and 600mm at periphery. Second layer to be screw fixed Gyproc® drywall screws of 35mm at minimum spacing of 300mm at centre and 300mm at periphery. 50mm Glass wool slab of density 20kg/m<sup>3</sup> shall be placed in metal framework. Glass wool holding clip should be used to hold Glass wool slab in its position. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Pro-Fill Jointing compound, (Conforms to ASTM C475), Gyproc® Joint Paper tape or fiber tape. The junction of the partition with masonry &amp; all penetration through the partition has to be treated with Hilti/Pyroplex fire and acoustic sealant. All other detailing and specifications to be followed as per approved drawing of Gyproc.Note: Applicator need 60min. fire rating certificates from Gyproc.Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required &amp; For door frame fixing, storages, shelves, paneling etc extra Wooden members to be used shall be of CP teak wood only. Including skirting /MDF board/wooden skirting cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. including ply base for fixing of TV or Overhead storage wherever required, The rates are also inclusive of necessary scaffolding, tools, tackles,, safety measures , Internal partial support (between two sturd) at 7' height.The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. All exposed corner shall be covered with perforated angle as per manufacturer's specifications or as directed by EIC.Partition ht will be measured from finish floor to false ceiling level only.</p>	5.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
109	<p><b>Wooden solid Partition finished with Both side Veneer finish: :</b>            " -----Do -----" as per above item specification for complete work . using 4 mm thick Veneer &amp; matt finish monocoat polish instead of laminate for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Equivalent to VNR Series Laminate. Equivalent to VNR series laminate.</p>	57.00	Sq.mt	0.00	0.00
110	<p><b>Thin Profile Glass Partition:</b> Providing &amp; Fixing of STL45 ie.Single glazed modular system consist of Aluminium section of 25*45*2.5 mm thick. All sections duly Powder coated/anodised with 6063-T6 grade and required accessories ie glass to glass aluminium I sections, T section &amp; 90 degree sections &amp; Glass packing to adjust the floor level. Ceiling profile, Floor profile and wall profile are 25 mm visible face and 45 mm wide with 10mm toughen glass as per approved make &amp; insertion of Thermoplastic gasket to adhere the glass firm &amp; airtight.The sound reduction Value is from 32 to 35 Db.With 6 mm Groove inbuilt in system to accomodate the carpet &amp; the uneven surfaces.Work including horizontal thin profile member at lintel lvl. as per drawing.</p> <p>Accessories/Hardware: neutral cure glazed &amp; metal silicon sealant of approved make on the periphery of the glass &amp; wood etc.Partition ht will be measured from finish floor to false ceiling level only. The rate shall be in sq.mt for all floors and at all heights including all costs. Glass width size shall be as per sugestion by EIC. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, safety measures, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC.The work including required frame work and board finish above ceiling and the contractor shall take care of noise transfer.</p>	13.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
111	<p><b>Fluted Glass partition:</b>            " -----Do -----" as per above item specification for complete work. using 5 mm thick Fluted glass instead of thin profile glass for partition work, as per approved by Architect/Client. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, safety measures, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC. Basic rate of Fluted glass Rs.220/Sq.ft.</p>	7.00	Sq.mt	0.00	0.00
112	<p><b>Frosted sparkling glass film (Colour film) :</b> Providing and fixing frosted glass film of approved make Translucent, cast PVC, self-adhesive vinyl, special CRYSTAL-effect film to reproduce Sand-blasting effect on glass with customised designs. MCS warranty of 3 (if exposed to direct sunlight) to 10yrs (indoors) must be endorsed by manufacturer. Rate shall be inclusive of plotter cutting design as per Architect/Client suggestion. Contractor shall provide shop drawing for approval of Architect/Client. Work complete including all type of tools, tackles, scaffolding etc complete as per suggestion of Architect/Client. If in case any application finishing will not as per satisfaction contractor shall remove all film at their cost. Contractor shall do a sample mock of 5 Sqm minimum of glass film), shall be approved from Architect/Client.</p>	6.00	Sq.mt	0.00	0.00
113	<p><b>Aluminium Skirting :</b> Providing and Fixing of Aluminium Skirting as per approved make having width of 75 MM X thickness of 2mm made out of 6063 Grade Aluminium alloy duly anodised as desired in the Ral Colour code decided by the architect having neat screw fixed arrangement with Rubber seal over it as per Manufacturers Specification. work complete as per the instruction of Architect. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description.</p>	261.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
114	<p><b>Double Leaf Glass Door:</b>  Supply &amp; Installation of Modular Aluminium Glass door frame of Kubik or equivalent make 45mm System, Using KOPS 001 &amp; KOPS DF 103 ( 45mm x 25mm) for Glass door frame  Doorframe Dimension – 45mm x 25mm.  Finish – SILVER finish / Powder coating as per approved sample by Architect. 10mm thk. clear toughened Glass  KUBIK Glass Hinge, HAFELE Open Door closer with saddle plate, KUBIK Mortise lock with handle, KUBIK Door stoper etc complete.  Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, sample mockup, all floor, all levels, all heights, safety measures, necessary frame work, Scaffolding etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC.</p>	4.00	Sq.mt	0.00	0.00
115	<p><b>Double Leaf Profile Glass Door:</b>  "-----Do-----as per above specification for complete work.  Using 8mm thick toughened glass instead of 10mm thk. clear toughened Glass.  Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, sample mockup, all floor, all levels, all heights, safety measures, necessary frame work, Scaffolding etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC.</p>	39.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
116	<p><b>Veneer panelling:</b> Providing &amp; fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work finish with 4mm thick Veneer &amp; matt finish monocoat polish. The frame work shall be made from square hollow aluminium anodised section size of 50x50x1.5 mm &amp; 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c &amp; horizontal 600 mm c/c horizontally. All ply/wooden shall be treated with anti- termite treatment . Measurements for paneling work to be recorded upto finished false ceiling level only irrespective of aluminium frame work, which shall be provided from gr. level to RCC slab / beams soffit level. Rates shall also be inclusive of cost of making CNC/engraving /cut outs/ openings for electrical fixtures, tube lights /air-conditioners ,grills, diffusers etc &amp; providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall &amp; board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. All curved surfaces, recesses, waffles shall be part of the paneling including openable shutter wherever required area and finished with the same material.Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, groove, adhesive, tape, headless nails, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC. only the clear elevation area of finished plywood wall paneling with Veneer shall be measured and paid. sample mock shall be approved from Architect/Client. Basic rate of veneer is 120/ Sq.ft</p>	234.00	Sq.mt	0.00	0.00
117	<p><b>Veneer Fluted panelling:</b> " -----Do -----" as per above item specification for complete work. using 12mm thick Veneer Fluted panelling &amp; matt finish monocoat polish instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Basic rate of veneer fluted panel is 340/ Sq.ft</p>	78.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
118	<p><b>Fluted panelling:</b>            " -----Do -----" as per above item specification for complete work. using 12mm thick Fluted panelling with bronze &amp; brass finish instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Basic rate of Fluted panel is 440/ Sq.ft</p>	28.00	Sq.mt	0.00	0.00
119	<p><b>Laminate Panelling :</b>            " -----Do -----" as per above item specification for complete work . using 1 mm thick laminate instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Equivalent to VNR Series Laminate.</p>	55.00	Sq.mt	0.00	0.00
120	<p><b>Fabric panelling:</b>            Providing and fixing Fabric Wall Paneling made of 50mm thick glass wool of density 24 Kg/cum and wrapped on the front side with an acoustically transparent and fire-resistant fabric with an option of colors as approved by Architect. providing a minimum sound absorption level of 0.95 NRC. Installation of Acoustic Fabric panels on GI frame work of section 50mm x 50mm on GI pipe frame factored at Sl. No. 10. GI panels fixed horizontally at spacing of 600mm center to centre and screwed aluminum extruded keel for channeled wood works. 6mm thick BWP ply (Duro/ century / Green) to be fixed on the frame work. Wall panel impellers shall be fixed to the GI frame using self taping screws.            Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, groove, adhesive, tape, headless nails, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC. only the clear elevation area shall be measured and paid. sample mock shall be approved from Architect/Client. Basic rate of fabric Rs. 1500 / Rmt</p>	5.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
121	<p><b>Writable with magnetic glass board</b> : Providing &amp; fixing 4mm thick writable coloured magnetic glass on existing partition/wall as per approved sample by Architect/Client.</p> <p>work Including cost of all type of fittings , accessories , tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc.work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.Only the clear elevation area shall be measured and paid.</p>	4.00	Sq.mt	0.00	0.00
122	<p><b>Gypsum panelling:</b> Gypsum panelling :The M/F wall lining includes 12.5mm Gyproc® Quattro Gypsum Board, screw fixed with drywall screws of 25mm at 300mm centers to one side of 45X18X0.5mm Gypliner ceiling channel (0.5mm thick having 18mm flange each made of GI Steel) placed at 600mm center to center in 195X29.5X0.9mm fixing bracket at 900mm c/c with 25X25X0.5mm Gypliner angle at bottom and top of the channel such a manner that joints staggered to avoid leakage through joints. Fixing strip of 75X0.5mm should be installed at horizontal joint of boarding. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Jointing compound and Joint Paper tape. 50mm Glasswool of density 20kg/m3 should be placed in metal frame.Necessary fabrication with anticorrosive paint work , scaffolding, anchor fasting , bolting HILTI or equivalent make with testing certified in scope of contractor)Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. Panelling item including openable shutter wherever required area and finish with the same material. Only the clear elevation area shall be measured and paid.</p>	10.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
123	<p><b>Accoustic Panelling :</b>            Providing and fixing wall acoustical paneling with using CS55 and IC91 framing directly to the wall and then fixing 12.5mm perforated board with the help of screw and using rock wool of 50kg density and 50MM thick between framing and perforated sheet then Fixing Ecotone make Marco polyester fiber acoustic wall paneling with the specification of 9MM thick having density of 1.90kg/m2 with NRC value of 0.80 surface matt finish which is fixed with solution SR505 as required. The panel should have euro class BASTME84-13 fire rating.            The color shade of Panel as approved by Architect.            Work Inclusive of Cutting as per detailed drawing and instruction of Architect.            Including surface preparation, Including cost of all type of tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc.work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.Only the clear elevation area shall be measured and paid.</p>	250.00	Sq.mt	0.00	0.00
124	<p>Extra labor rate for providing various sizes as per the detailed drawing CNC cutting / Engraving work for any type of material approved by EIC / Architect. The rate shall be for all floors, at all heights, all shapes including all costs.</p>	13.00	Sq.mt	0.00	0.00
125	<p><b>Metal Profile :</b> Providing and fixing of 5mm thick S.S. T Profile Copper or as per approved sample by Architect including necessary material, adhesive tools , tackles, fittings etc complete. Work complete including all type of tools, tackles, scaffolding, mock sample, etc complete as per instruction of Architect/EIC.</p>	336.00	Rmt	0.00	0.00
126	<p><b>SS Metal Jali with PVDF coating:</b> Providing and fixing SS Jali with PVDF coating as per approved sample by Architect. including necessary material, adhesive tools , tackles, fittings etc complete. Work complete including all type of tools, tackles, scaffolding, mock sample, etc complete as per instruction of Architect/EIC.</p>	31.00	Sq.mt.	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
127	<b>Soft Board</b> : Providing and fixing on wall 12mm thick approved quality soft board with cotton cloth/fabric of approved make and shade on 12mm thick IS 710 ply 50 mm th approved Glass wool sheet with PVC grip, as approved sample and as directed by EIC. The work shall be measured & paid in Sqm. for all floors, all level and at all heights including all costs .Only the clear elevation area of the cloth/fabric shall be measured and paid. All the work complete as per the detailed drawing, mockup sample and instruction of Architect/EIC.Basic rate of cotton cloth /fabric for 54" wide shall be Rs. 200/Rmt.	7.00	Sq.mt	0.00	0.00
128	<b>Ply palmet</b> : Providing and fixing wooden pelmets of upto 200 mm x 300 mm L shape made of 19mm thick ply as per IS 710 and beading of 4mm thick and 25mm wide Ghana Teak wood for projection screen. Rate to be inclusive of lipping, cutting, wastages, necessary fixtures, nails, adhesives, necessary scaffolding, fixing at all heights and for all floors as per drawing and approved sample etc should also take load of all the all roller blinds.	55.00	Rmt	0.00	0.00
129	<b>Roller Blinds</b> : Providing and fixing blinds as per approved make as per suggested shade & spring drive system with steel ball chain/one touch with speed control action roller blind with end brackets with head rail, components, bottom bar. Fabric : screen classic 3% to 5% Fabric value : 470 Gsm , Thickness : 0.60 to 0.70 mm Construction: 75 % PVC & 25 % Polyster Fabric to be as per approved sample. All the work complete as per the detailed drawing, mockup sample and instruction of Architect/EIC. All complete as per approval of designer. The mode of Measurement: The size of the blind will be measured from end to end bracket (Left to Right bracket) height will be measured from top of the palmet to sill bottom level and clear opening size only there will be not extra payment towered overlapping.& mockup sample approved by the Architect/ EIC.	14.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
130	<p><b>Restaurent Cash-counter table:</b>            Table top : 1800 x 750x1050 mm ht, MDU-450x450X650mm,            Providing and fixing table unit consist main table with MDU unit with all necessary accessories keyboard, CPU stand, cable manager, modesty panel etc. with all required necessary accessories. All finishes laminate, powder coating shade shall be approved by architect. Rate shall inclusive of mock up sample providing and fixing at site of unit for approval of architect.            All Table top &amp; outside : 18mm thick Artificial stone as per approved sample (reverse bull nose).            Outer sides: IS 303 BWR ply with side 4 mm thick teak Veneer finish with approved polish.            Inside: 0.8mm thick laminate fixed on approve plywood finish as per selection and laminate as per selection suede /satin/VNR finish            Flip open-Aluminium powder coated flip open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets.            Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN &amp; electrical cables            Vertical Legs and support : Made from metal as per selected design and powder coating finish            Modesty panel: Made formed/Partial prelaminated edge finish PVC considered on the main spine and leg to leg modesty is considered            MDU: Made up of with prelaminated MDF/particle board and all exposed edge finish with 2 mm th matching PVC edge banding. Hardware make hettich/haffle or equivalent. Providing 3 nos drawers with profile handle as per selection including locking arrangement            CPU stand keyboard - as per selection with approved powder coated.            Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, finishing, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing , mock-up sample and instruction of Architect/Client. VNR Series Laminate. Basic rate of stone Rs.300/Sq.ft.</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
131	<p><b>Back side storage unit</b> (750 H x 450 D) mm:            Storage Comprising from IS 303 BWR 19 mm thick and 12 mm ply, finish with 1 mm thick Laminate finish as per approved make and shade by Architect.            Storage top : 35 mm thick post foam top edge finish as per selection and laminate as per selection suede /satin/VNR finish.            Solid Shutter : 25 mm thick comprising from IS 303 BWR ply &amp; finish with 1 mm thick VNR Laminate .            Shelf: 19 mm thk IS 303 BWR ply finish with both side approved laminate. Inner area shall be finished with linear laminate.            Ledge/Niche comprising from IS 303 BWR ply finish with 1 mm thick Laminate , required lighting arrangement.            The work shall be done as per the detailed drawing, specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles, adhesives, grooves, consumable hardware &amp; required SS 304 grade hardware/accessories, Profile handle, Wooden frame, monocoat polish, pvc edge banding, of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Equivalent to VNR series laminate.</p>	2.00	Sqmt	0.00	0.00
132	<p><b>Console</b> : Providing &amp; fixing Console complete as per drawing/Ref Image. Approx size : 1500 x 400 x 1050 mm made from up of 19 mm thick BWR grade ply &amp; finished of Laminate as per approved make and shade and solid wooden leg with matt finish monocoat polish as per drawing. Rate shall be inclusive of providing, fixing all necessary brass satin finish nickel plated/ S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Rod locks, Multipurpose lock, Rate shall be inclusive of 2nos. of drawer unit of 19mm thick IS 303 BWR ply and laminate, PVC edge beading. All external &amp; internal exposed woodwork to be finished in PU semi gloss paint finish polish as per specified item's manufacturer's specifications. Rate shall inclusive of providing mock up sample for approval of architect. Equivalent to VNR series laminate.</p>	11.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
133	<p><b>Media room table : 2400 x 600 x 1050 mm</b>            Providing and fixing as per detail shape and size table unit consist table with all required necessary accessories.            Top &amp; both sides : 50 mm thick comprising from 18 mm thick Artificial stone as per approved sample (reverse bull nose).            Front &amp; back sides: IS 303 BWR ply with both side 4 mm thick teak Veneer finish with approved polish. Ply box for cable runway comprising from IS 303 BWR ply with both side 4 mm thick Veneer finish with polish.            Popbox: Flip open-Aluminium SS finish or approved finish open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets            Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN &amp; electrical cables.            MDU: Providing 3 nos drawers with profile handle as per selection including locking arrangement            Rate inclusive of providing and fixing as per requirement of socket and quantity Pop up tabletop electrical WIRE MANAGEMENT BOX SS finish. The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles, adhesives consumable hardware &amp; required SS 304 grade hardware/accessories, grooves pvc edge banding, etc of approved make for all floors, monocoat polish, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Basic Rate of Veneer is Rs.120/ Sqft. Basic rate of stone is 450 / Sq.ft</p>	1.00	Nos	0.00	0.00
134	<p><b>Judges table: 6000 x 600 x 1050 mm</b>            "-----Do-----" as per above specification for complete work.</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
135	<p><b>Control room near Foyer Area.</b>            Providing and fixing desk based linear workstation of size 1200x600x1050 ht at below mentioned locations. The table top-Table top to be made up of 25 mm thk prelaminated MDF/particle board with 2 mm thick matching PVC edge banding            Flip open-Aluminium powder coated flip open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets.            Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN &amp; electrical cables            Metal Legs: Metal legs as per selection of shapes &amp; powder coating.            Modesty panel :Prelaminated MDF/particle board with exposed edges 2 mm th matching PVC edge banding considered on the main spine and leg to leg modesty is considered Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. As approval of EIC. All the work complete as per the detailed drawing , mock-up sample and instruction of Architect/EIC. Work complete as per the instruction of EIC.</p>	2.00	Nos	0.00	0.00
136	<p>Keyboard : Providing and fixing key board as per approved make. Metal keyboard tray with Outer Dimension of the Keyboard tray is 507 x 245mm made of 1mm thick CRCA as per approved shade powder coating fixing with require all necessary accessories etc complete</p>	2.00	Nos	0.00	0.00
137	<p>CPU stand : Providing and fixing CPU trolley ebco or eqvilant approved make. CPU Trolley base is made of 1.6 mm thck CRCA and the sides are made of 1.2mm thick. The width of the trolley can be varied to accompany various width CPU. The CPU is mounted on lockable castors.</p>	2.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
138	<p>Pedestal Unit: @400x470X545 MDU: Made up of with prelaminated MDF/particle board and all exposed edge finish with 2 mm th matching PVC edge banding. Hardware make hettich/haffle or equivalent. Providing 3 no's drawers with profile handle as per selection including locking arrangement</p> <p>Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. As approval of EIC. All the work complete as per the detailed drawing , mock-up sample and instruction of Architect/EIC. Work complete as per the instruction of EIC.</p>	2.00	Nos	0.00	0.00
139	<p><b>Full Height Storage with Laminate Finish</b> : 450 mm Depth</p> <p>Storage Comprising from IS 303 BWR 19 mm thick and 12 mm ply, finish with 1 mm thick Laminate finish as per approved make and shade by Architect.</p> <p>Solid Shutter : 25 mm thick comprising from IS 303 BWR ply &amp; finish with 1 mm thick Laminate .</p> <p>Shelf: 19 mm thk IS 303 BWR ply finish with both side approved laminate. Inner area shall be finished with linear laminate.</p> <p>Ledge/Niche comprising from HDF / Lacquered glass finish w, required lighting arrangement.</p> <p>The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles, adhesives , grooves , consumable hardware &amp; required SS 304 grade hardware/accessories , Profile handle, Wooden frame, monocoat polish, pvc edge banding of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Equivalent to VNR series laminate.</p>	7.50	Sq.mt	0.00	0.00
140	<p><b>Overhead storage :</b></p> <p>" -----Do-----" as per above specification for complete work.</p>	2.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
141	<p><b>Pantry below storage</b> : Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure and both side 1 mm th laminate finish shall be of approved make &amp; shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks,6"handle , 75 mm tower bolts, ball catches/Magnet, The rate shall be inclusive of shelf both side laminated finish and as per detail drawer unit with SS 304 grade kitchen basket as per selction by architect The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings &amp; instructions.Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) &amp; raw manufacturing to be got approved in advance from EIC &amp; Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements &amp; or assembled at site as per the requirement and directed by EIC &amp; Architect. All material to be used shall be as per the drawings &amp; confirm to the relevant detailed material specifications of this document. The work shall be measured &amp; paid in sqm The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Equivalent to VNR series laminate.</p>	15.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
142	<p><b>Pantry above storage -350DX600 H:</b> Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure and both side 1 mm th laminate finish shall be of approved make &amp; shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks, 6" handle , 75 mm tower bolts, ball catches/Magnet, The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings &amp; instructions. Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) &amp; raw manufacturing to be got approved in advance from EIC &amp; Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements &amp; or assembled at site as per the requirement and directed by EIC &amp; Architect. All material to be used shall be as per the drawings &amp; confirm to the relevant detailed material specifications of this document. The work shall be measured &amp; paid in sqm. The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Equivalent to VNR series laminate.</p>	12.00	Sq.mt	0.00	0.00
143	<p><b>Center Table: size of bigger table-2'6" Dia and smaller table-2' Dia Location: Project room, workstation</b>            Providing &amp; fixing of center table            Table top: 15 mm thick Artificial stone top.            Vertical support: Metal with powder coating.            Work complete including all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	8.00	Pair	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
144	<p><b>Corner Table: Size-1'6" Dia</b> Table top: 15 mm thick Artificial stone top. Vertical support: solid wooden Leg with matt finish monocoat polish with busher. Work complete including Providing &amp; fixing , all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	17.00	Nos	0.00	0.00
145	<p><b>Two Seater:</b> 1500mm (L) x 870 mm (B) x 800 mm (H) made up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density thikness &amp; back shall be 32 density foam &amp; finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC. Leg : Solidwood All external &amp; internal exposed woodwork to be finished in PU semi gloss finish polish.The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 1000 Rmt</p>	12.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
146	<p><b>Three seater: 2100 (L) x 870 mm (B) x 800 mm (H)</b> comprising of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density &amp; back shall be 32 density foam &amp; finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC.            Leg : Solidwood            All external &amp; internal exposed woodwork to be finished in PU semi gloss finish polish.            The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 1000 Rmt</p>	2.00	Nos	0.00	0.00
147	<p><b>Waiting Lounger chair</b> :The seat shall 150 mm th 40 density &amp; back shall be 32 density foam &amp; finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC.            Leg : Solidwood            All external &amp; internal exposed woodwork to be finished in PU semi gloss finish polish.            The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 1000 Rmt</p>	18.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
148	<b>Sofa Seating</b> :Providing and fixing as per requirement seating base made from BWP ply with veneer finish and seating made from 40 density PU foam with fabric finish as per selection of architect complete. The work shall be done as per drawing specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. The unit shall be manufactured in parts and these parts shall be assembled at site. Basic Rate of veneer : 120 Sq.mt	21.00	Rmt	0.00	0.00
149	<b>Planter box</b> : Providing making, fixing as per detail drawing and required length and depth shall be made from 19mm IS 710 BWP ply with both side laminate finish and providing lighting arrangement cutout and fixing as per detail drawing and instruction. Rate shall inclusive all necessary hardware and fitting, ms framing, paint. The work shall be done as per the specifications, sample approved and as directed by the Architect/ Client. Rate shall inclusive of providing mockup sample for approval of Architect/ Client. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessorie, sample mockup etc as described in item description.work complete as per the instruction of Client/EIC.	8.00	Sq.mt	0.00	0.00
150	Chair Type-2A -Model equivalent make - HOF MAR-1004 Mid Back * Chair with Moulded Ply in Seat and Back. * PU Moulded foam on Seat & Back. * Adjustable Arms with PP cladding. * Chrome Base. * Synchronized Mechanism & Gas Lift. Work complete as per the approved sample & instruction of EIC.Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.	5.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
	<b>Total Amount</b>				<b>0.00</b>
<b>D</b>	<b>Part-4</b>				
151	Chair (Media room) -Model equivalent make - Model equivalent to WILSON HB HIGHBACK CHAIR as per approved sample list. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	11.00	Nos	0.00	0.00
152	Chair (Media room) -Model equivalent make - Model equivalent to HOF-Evo training as per approved sample list. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric is 800/ Rmt	24.00	Nos	0.00	0.00
153	Chair (Restaurent & breakout area Chair) -Model equivalent make as per approved sample list. Make : Solidwood , Structure : Solidwood, Outside : Fabric Finish Leg : Solidwood All exposed woodwork to be finished as per approved polish. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric is 800/ Rmt	75.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
154	<p>Chair (Auditorium area Chair) -Model equivalent MERRYFAIR PREMIERE CHAIR of Monarch make as per approved make list.</p> <p>Chair With frame in MS, PU foam in back &amp; Moulded PU Seat, Chrome Arms with PU cladding &amp; Synchro Mechanism, Chrome base, &amp; Gas Lift.</p> <p>Auto -Return Seat with Spring Mechanism</p> <p>Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	162.00	Nos	0.00	0.00
155	<p><b>6 Seater table : 1800 x 750 mm</b></p> <p>Table top: 15 mm thick Artificial stone top.</p> <p>Structure : Solidwood</p> <p>Vertical support: Metal with powder coating.</p> <p>All external &amp; internal exposed woodwork to be finished in PU polish.</p> <p>Work complete including all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of stone is 300/ Sq.ft</p>	7.00	Nos	0.00	0.00
156	<p><b>4 Seater table : 1250 x 750 mm</b></p> <p>" -----Do-----" as per above specification for complete work.</p> <p>Basic rate of stone is 300/ Sq.ft</p>	9.00	Nos	0.00	0.00
157	<p><b>2 Seater table : 600 x 750 mm</b></p> <p>" -----Do-----" as per above specification for complete work.</p> <p>Basic rate of stone is 300/ Sq.ft</p>	7.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
158	<p><b>Podium table : 600 x 750 x 1050 mm</b> Podium table : Outdoor side 19mm thick IS 303 BWR ply with teak veneer finish monocoat polish. Inner side 19mm thick IS 303 BWR ply with veneer finish monocoat polish. MDU consist 3nos. of drawers. Work complete including Providing &amp; fixing , all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic Rate of veneer : 120 Sq.mt</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
159	<p><b>Reception table:</b> Table top : 3000 x 750x1050 mm ht, MDU-450x450X650mm, Providing and fixing table unit consist main table, side table with MDU unit with all necessary accessories keyboard, CPU stand, cable manager, modesty panel etc. with all required necessary accessories. All finishes laminate, powder coating shade shall be approved by architect. Rate shall inclusive of mock up sample providing and fixing at site of unit for approval of architect.</p> <p>Table top : 35 mm thick post foam top edge finish as per selection and laminate as per selection suede /satin/VNR finish</p> <p>Outer sides: 18 mm thick Onyx stone finish with back light of approved polish with approved IS 303 BWR ply.</p> <p>Inside: 0.8mm thick linear laminate fixed on approve plywood finish as per selection and laminate as per selection suede /satin/VNR finish</p> <p>Flip open-Aluminium powder coated flip open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN &amp; electrical cables</p> <p>Vertical Legs and support : Made from metal as per selected design and powder coating finish</p> <p>Modesty panel: Made formed/Partial prelaminated edge finish PVC considered on the main spine and leg to leg modesty is considered</p> <p>MDU: Made up of with prelaminated MDF/particle board and all exposed edge finish with 2 mm th matching PVC edge banding. Hardware make hettich/haffle or equivalent. Providing 3 nos drawers with profile handle as per selection including locking arrangement</p> <p>CPU stand keyboard - as per selection with approved powder coated.</p> <p>Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, finishing, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing, mock-up sample and instruction of Architect/Client. VNR Series Laminate. Basic rate of stone Rs.450/sq.ft.</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
160	<p>Art work: Providing and fixing in position commissioned art works inside the building on the wall or ceiling and extension of the same till floor/ceiling. The composition of the commissioned art work shall be from any type of wood, metal like copper, brass, SS, MS, fabric, acrylics, rubber, plastic, tough boards, cementitious boards, fibers, gypsum, POP etc. all. The form of material may also vary based on material properties like sheets, wires, blocks, inclusion of cutouts, bending of the materials, profile cutting and shaping of the materials, manufacturing at site as well as at site, covering the prepared material by means of the bubble sheets, jute bags or in wooden packing materials. The commissioned art work may require any shade, finish and texture of duco painting, specialty painting, PU painting, general painting to paintable surfaces, galvanizing, powder coating, anodizing etc. The base surface where the commissioned art work is to be installed also needs some modification to enhance the effect of art works. The use of material like fiber glass wool/ boards, filler fabric, mounting material may also essential based on the design of the art work by artist. The rate shall be inclusive of any type of lighting features to be added into it includes LED lights, neon lights including its supporting and suitable wiring for the same within the art works. Only one electrical control point connection will be given as close to art works. The rate shall be inclusive of making necessary provisions within the commissioned art works of fixing of the same. The provisions of the fixing of the art work may be in parts but it shall be inclusive of the all arrangements like LN key, studs, anchors, nuts and bolts etc. all.. The concept of the art work will be generated by architect and interior designer and based on that offers from the artists to be invited for design and execution of the artwork. The selection of the artist is to be done by architect and interior designer only. Main contractor is bind to follow the methodology suggested by architect and interior designer to be followed for development of commissioned art work. The overall outline area covered by art work is to be considered for the measurement instead of actual area of art work. Deductions of the internal cutouts, spaces in between of the art work shall not be made. Since there is huge variance in types of the commissioned art works, the same is to be completed in all respect inclusive of the materials and methodology is stated above and may not be. For any additional materials, process, methodology no extra payments shall be made. The quotations of the artist shall be got approved in advance including area of the proposed art works. Total payment of the artwork will be done as per basic rate and difference between actual cost per sqm and basic rate per sqm will added or deducted without any consideration of the, overhead and profit over the difference. It is the responsibility of the main contractor to provide scaffolding, power, water, facilitating the areas required for developments and storage of the art work etc. The protection and cleaning of the pre and post installation of the art work is the responsibility of the main contractor.</p>	57.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
161	Signages : Providing and fixing signages comprising form ss plate with Vinyl film letter , Hdf finish as per instruction of Archiect/EIC. Contractor shall submit mock up sample.	6.00	Sq.mt	0.00	0.00
162	Logo Work : Providing and fixing standard Logo using virgin acrylic or other material like Colored HDF/cementsheet /SS plate with CNC work complete as per architect selection , letters as per detailed drawings and fixed with approved adhesive with necessary fittings and provision shall be made for conceal LED light as per detail drawing. (logo size will be aprox. Size - 600 mm dia )	2.00	Nos	0.00	0.00
163	<b>Floor Number Signages</b> : Providing and fixing Signages comprising from ACP sheet, Vinyl letter with framing work if required with anti corrosion paint. The rate shall be for complete item inclusive of all material, buffing edge, labor, wastages, necessary tools & tackles, adhesives, consumable hardware & required SS 304 grade hardware/ accessories of approved make. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per drawings, specifications & instruction of Client/EIC.	11.00	Sq.mt	0.00	0.00
164	<b>Floor wise Direction signage</b> : Providing and fixing Signages comprising from ACP sheet, Vinyl letter with framing work if required with anti corrosion paint. The rate shall be for complete item inclusive of all material, buffing edge, labor, wastages, necessary tools & tackles, adhesives, consumable hardware & required SS 304 grade hardware/ accessories of approved make. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per drawings, specifications & instruction of Client/EIC.	31.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
165	<p><b>indicator signage at Ground floor</b> : Providing and fixing Signages comprising from ACP sheet, Vinyl letter with framing work if required with anti corrosion paint.</p> <p>The rate shall be for complete item inclusive of all material, buffing edge, labor, wastages, necessary tools &amp; tackles, adhesives, consumable hardware &amp; required SS 304 grade hardware/ accessories of approved make.</p> <p>Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per drawings, specifications &amp; instruction of Client/EIC.</p>	5.00	Sq.mt	0.00	0.00
166	<p><b>Trap Door : 12.5mm thick Gypboard® Plain</b></p> <p>Providing and fixing trap door as per approved sample of Ceiling panels comprise of a Aluminum Alloy 6063 T6 Extrusione ( Powder coated) with MR gypsum Board . Each panel features a push- latch closing mechanism with door retaining safety cable &amp; hook.Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing, etc. complete work.</p> <p>Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price. 600 x 1200 mm</p>	35.00	Nos	0.00	0.00
167	<p><b>Carpet Flooring Work:</b> Providing &amp; laying carpet flooring as per approved make &amp; Sample by Architect. Carpet fixed with SR 505 Pidilite or equivalent tile adhesive and underlay foam material. carpet should be laid as closure to each other.Contractor will take care for level matching with other area flooring. Scope includes labour, under lay material, disposal of debris, necessary cutting of tiles without damaging the edges, including to provide &amp; fixing of SS 304 finish end profile , skirting ,edge profile etc to protect and cleaning, etc. complete. All works are carried as per detail drawing / instruction of architect / EIC. Before laying carpet contractor shall prepare even surface as per required. equivalent Welspun Relay Welspun : Carpet tiles Lime  AC:CT000702 : Iron   AC:CT000705. Carpet tiles or basic rate of carpet is Rs. 300/Sqft</p>	261.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
168	<b>Kota stone on steel staircase</b> : Providing and laying 25 mm thick polished Kota stone slab flooring above fabrication work. work including all type of fittings, fixing, accessories, polish, all type of tools, tackles, all labour, scaffolding, all type of materials, transportation, cleaning, all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	9.00	Sq.mt	0.00	0.00
169	<b>Texture paint(Stucco)</b> :Wall painting two coats with Stucco of Asian or equivalent approved brand in any shades and colour as directed on wall surface to give an even shade including applying of a one coat of Penetrating primer or equivalent and two coats of paint, scaffolding to at any height with all labour and material thoroughly brushing the surface free from mortar droppings and other foreign matter and sand prepared smooth etc. complete. The substrate must be sound, clean, dry, free from dust, oil, grease and laitance etc. All traces of release agents must be removed. On chalky and dusty surfaces, all loose material must be removed by stiff bristle brushing. The primer / paint application is to be done with the rollers. rate shall be including, safety measures , crack filling and levelling as per manufacturers specification. Top coat should have. 1) Low VOC content. 2) Crack Bridging ability upto 2.6 mm. 3) 100% pure acrylic emulsion 4) Anti-Carbonation concrete protection 5) Very Low Flame spread 6) Superior Washability	29.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
170	<p><b>Travertino Texture</b> : Providing and applying 1.5 mm thick travertino texture (matt/glossy finish) as per approved make &amp; sample by Architect. work inclusive of base primer (50-60 MICRONS) as per approved colour, HVLP spray Gun, 1 Coat Of Paint Matt Or Gloss Finish Top Coat Of 30 – 40 Microns By Brush Or Roller, including surface, Surface must be cleaned of chalk and debris. base coat of primer of relevant colour is applied on the plastered surface using a roller or brush, The material is applied using a spray gun to get the required design, water can be added in for easier application depending on the requirement, Drying time is usually between 8-24 hours depending on weather conditions. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, all accessories, Scaffolding etc as described in item description. Work complete as per the detailed drawing, mockup sample and instruction of Architect/Client.</p>	797.00	Sq.mt	0.00	0.00
171	<p><b>Custmised wall painting</b>            Canvas painting with frame work :Providing making painting/polishing and Fixing in position of wooden frames having profile as per drawing and sizes as specified for paintings with card board mounting /canvas frames including backing of required thickness of hardboard / ply board(IS 303 BWR) backing. Frame shall be hanged on the wall using key hole chaplas fixed at the back part of the frame at all heights, all floors and all levels. The rates shall be inclusive of all material, labour, wastage, antitermite treatment, polishing all tools tackles etc complete. Sample of the frame shall be got approved by Architect prior to manufacturing on large scale. D) Wooden Frames for Canvas Work as per drawings: Frame Size - 75mm x20mm Wood Work - Burma Teak Wood Frame shall be finished with PU polish work. The art work shall be hanged on the wall using heavy duty approved key-hole chaplas</p>	25.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
172	<p><b>Wallpaper:</b>            Providing and supplying wall papers as approved by Architect.            Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of wallpaper is 95 / Sq.ft</p>	5.00	Sq.mt	0.00	0.00
173	<p><b>Wallpaper:</b>            "-----Do-----" as per above specification for complete work.            Basic rate of wallpaper is 155 / Sq.ft</p>	50.00	Sq.mt	0.00	0.00
174	<p>Supply &amp; Installation of 8 mm clear glass unit with FG glass Digitecture on #2 digital printed glass with 1440 dpi resolution in approved pattern and color, as per required sizes based on drawings. The glass should be printed with electromagnetic drive technology for perfect printing precision. The ink should be ceramic-based, should be permanently fused on the glass surface and 100% resistant to UV and other environmental effects. The final product should not contain heavy metals with the following limit % in weight: Hg (Mercury), Pb (Lead) and Cr (Chromium) &lt; 0.10%, Cd (Cadmium) &lt; 0.01% The glass should be Heat-strengthened (IS 16982: 2018).A) 8mm clear glass with digitecture on #2 and white flood coat (installation on plywood backing with clear silicon.</p>	20.00	Sqm	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
175	<p><b>VERTICAL GREENARY</b> : Providing and fixing vertical garden including Plants,Vertical Garden Pots would be places on aluminium rails with plastic sheet as a backdrop to protect the wall from coming in contact with water. potting soil, Irrigation will be done with 8 liter per hour dripper via drip irrigation and installation of the same. Work including All the excess water shall be collected in the aluminium drainage channel placed at the bottom, GROW LIGHTS etc complete as per instruction by Architect.</p> <p>Work complete including all type of material, fittings, fixtures,Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, necessary frame work, Scaffolding etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC.</p>	31.00	Sqm	0.00	0.00
176	<p><b>Artificial Grass</b> : Providing and fixing Artificial Grassas per approved make &amp; Sample by Architect. Work complete including all type of finishing. Material content : Pile Weight 1.65 Kg/sq.mtr, Total Weight 3.00 Kg/sq.mtr, Pile Height 40 mm, Stitch Rate 16 Stitch / 10 cm, Tufted Dencity 16800 D/sq.mtr, Primary Back PP + Non Woven Layer, Pile Material PP+PE, Backing Synthetic Glue, Yarn Denier 11400.</p> <p>Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, necessary frame work, Scaffolding etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC.</p>	18.00	Sqm	0.00	0.00
177	<p>Point wiring for Light / Bell with 2-1.5 sq.mm &amp; earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in/ on surface on wall/ceiling complete with 6A Modular type switch / bell push &amp; accessories and earth continuity of following type, erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories CAT III</p>	400.00	Pt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
178	Point wiring for secondary light point with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling, complete with earth continuity and necessary connection with primary light with accessories erected on Metal / PVC box covered with 3 mm thick PC(Polycarbonet) / Acrylic sheet for open / concealed wiring. with necessary Lamp holder / ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories	95.00	Pt	0.00	0.00
179	Point wiring for Two Way Controlled Light Point with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (green) both are of .ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling ,complete with 6A Modular type switches and following type of accessories erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary batten/angle holder or ceiling rose or H.D.Connector as directed CATIII	20.00	Pt	0.00	0.00
180	Point wiring for FAN with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling complete with 6A Modular type switch and hum free EME four or more step type electronic fan regulator with separately mounted and accessories with earth continuity of following type erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories.CAT III	2.00	Nos	0.00	0.00
181	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate , modules erected with necessary connections as per site situation directed by Engineer In charge. (23)USB Charger with output of 5 V DC,2.1 A with inbuilt surge protection. Cat-III	11.00	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
182	Point wiring for Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling with following type accessories. CAT III	12.00	Nos	0.00	0.00
183	Point wiring for Individual Plug with & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories. For 6A Plug with 2-1.5 sq.mm Cu. Wire with medium class Rigid PVC pipe and accessories CAT III	21.00	Pt	0.00	0.00
184	Point wiring for Individual Plug with & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories.[III] For 16A Plug with 2-2.5 sq.mm Cu. Wire (a) with medium class Rigid PVC pipe and accessories.CAT-III	5.00	Pt	0.00	0.00
185	Providing & erecting Switch board for Computer or electric apparatus consisting of following items in single board erected on PVC / Metal board with 3 mm thick PC (Polycarbonate) / Acrylic sheet erected as directed for [B] modular type accessories 1 no. 6A/16A universal plug-switch combined. CATIII 3 nos. 6A Switch 3 nos. 6A 5 pin Plug	28.00	Ea	0.00	0.00
186	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (a) with medium class Rigid PVC pipe and accessories (a) 2 wire 1.5 sq. mm	3000.00	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
187	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (a) with medium class Rigid PVC pipe and accessories (B) 2 wire 2.5 sq. mm	2500.00	Mtr	0.00	0.00
188	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected in / on wall / ceiling with 2.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size. (a) with medium class Rigid PVC pipe and accessories (A) 2 wire 4 sq. mm	300.00	Mtr	0.00	0.00
189	Supply, Installation, Testing and Commissioning of suitable sweep, BEE 5 Star rated, Ceiling fan with Brush Less Direct Current (BLDC) permanent ferrite magnet Motor, class of insulation: B, Rust free 3 nos. Aluminium blades, 2 nos. canopies, shackle kit with earthing provision, copper winding, Power factor not < 0.9, Service Value (CMM/W) minimum 6.85, Air delivery minimum 215 CMM, 350 RPM, 230v (tolerance as per IS : 374-2019), THD < 10%, with remote unit for Speed Control and all remaining accessories including safety pin, nut bolts, washers, temperature rise = 75 degree C (Max.), suitable for 140 to 285 Voltage and rectifier circuit with surge, over current and overload protection , 50 Hz, Single phase AC Supply, earthing etc. Complete as required.[ Make shall be approved by Engineer in Charge] (B) 1200 mm Sweep (48")	2.00	Nos	0.00	0.00
190	Providing 2.5mm.thick laminated acrylic sheet to cover the fan hook or Fan box.	2.00	Nos	0.00	0.00
191	Supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe down rod erected duly painted for fan complete with necessary 24/ O.20, 3 core flexible wire with earthing.	2.00	Mtr	0.00	0.00
192	Supplying & erecting fan hook box of 10 mm M.S. round bar bounded to the RCC bars up to 50mm length each side and pierced through a 16 Gauge M.S. box / Heavy Duty PVC box complete erected concealed in Ceiling with necessary finishing.	2.00	Nos	0.00	0.00
193	Supplying & erecting approved make low noise decorative <b>Exhaust fan</b> having size 200mm with 1350 RPM with square frame ABS body with inbuilt lowers & square frame.	5.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
194	Supplying & erecting Electronic Type Cordless Call Bell erected on PVC/Metal board having portable bell push working on D.C. & bell on 230V A.C. supply with cells / battery	4.00	Ea	0.00	0.00
195	Supplying & erecting Approved make call bell indicator with buzzing sound and Red light indicating lamp with Red light button to attend the call suitable for 240 v 50 c/s supply to be erected.	4.00	Ea	0.00	0.00
196	"Supply Installation Testing Commissioning of Indoor deep Recessed Round downlight 18-21W Recess Mounted Round backlit downlighter with below features 1. Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. PS diffuser for optimum light transmission. Round Version. 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. Approved makes : Philips,Havells, Wipro,Tisva	45.00	Nos	0.00	0.00
197	"Supply Installation Testing Commissioning of Indoor deep Recessed Round COB downlight 18-21W Recess Mounted Round 36-40 DEGREE COB downlighter with below features 1. Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. . Round Version. 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80, High efficiency driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) recess mounted die cast ORRIN 20w Approved makes : Philips,Havells, Wipro,Tisva	60.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
198	Supply Installation Testing Commissioning of Indoor Office Lighting 7-9w Recess Mounted Tilttable Spotlight downlighter with below features 1.Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. With COB with Lens of 36-40 degree 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80, High efficiency driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) recess mounted Galaxy Pro COB 7w DL072381Y Approved makes : Philips,Havells, Wipro,Tisva	75.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
199	Supply, installation, testing, and commissioning of Amoeba Lighting System present a new concept of pendant luminaire that adapts to each space, allowing to create of compositions to the taste and need of each project, in this way the professional obtains unique and personal luminaires. The Ameba collection brings together 5 different pieces that fit together and combines perfectly together to make an 8 Ft x 4 Ft Luminaire offering an infinite amount of compositions. Available in two finishes: matt white lacquer and graphite grey. Ameba Luminaire is made with cold rolled near annealed steel having Optics made of PMMA 70% light output ratio having 5W / SQ FT and light source of OSRAM/NICHIA/SAMSUNG SMD LED with Efficacy of 130lm/W and Control of ON/OFF or DALI Driver mounting Inside the canopy and over Thermal management using Passive cooling generating overall led life time >50000hrs, CRI>80, CCT 3000K, 4000K, 5700K. The Interior lights Should comply with Indian Interior illumination standard IS 3646-1. LED Driver should be Protected up to 2.5 kV power network fast transients, High efficiency, 0.87, PF >0.95, THD<15 Built in strain relief for independent use, lacquer coating provides improved robustness in challenging climate conditions (humidity, temperature). Operating Voltage range 198 - 264 VAC, External NTC thermal input, and considering all recommendations in IS 15885 (part 2/ SEC 13) having Driver life time of more than 50000 Hours. Written Approval required for each and every lighting products of the Project after conducting lighting demonstration to Architect. KLS AMOEBA / Tisva/HAVELLS PROFESSIONAL SERIES	2.00	Nos	0.00	0.00
200	Supply Installation Testing Commissioning of Hanging light 18W, High efficiency suspended downlighter designed with microtexture CRCA powder coated housing. High efficient transmissivity diffuser provides soft light. CRI>80, IP20, Ambient temp- 0 to 45 DegC, Driver efficiency>86%, THD<10%,Powerfactor>0.9, CCT - 4000/5700K, 50,000 hrs @ L70 life. Surge protection-2 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 150-270V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Equivalant to Wipro Model No. LD99-281-XXX40PMBL. Dia 158MM, Height 160MM Luminaire lumen ≥ 1800 lm. (100 lm/W) Approved makes : Philips,Havells, Wipro,Tisva	7.00	Nos	0.00	0.00
<b>Total Amount</b>					<b>0.00</b>



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
<b>E</b>	<b>Part-5</b>				
201	Supply Installation Testing Commissioning of Multipule lines of led strip with alumnnium profile for backlighting the Onyx stone with a dotless effect and complete even lighting Remote driver to be kept for maintatinance purpose Should be around 90w-120w per square meter Approved makes : Philips,Havells, Wipro,Tisva	6.00	Sq.mtr	0.00	0.00
202	<b>Decorative Hanging light:</b> Supply Installation Testing Commissioning of 30W, High efficient coral (bell) shape made of aluminium white colour coated outside finish Upto 1m suspension. LED's provided with high efficient non yellowing PMMA diffuser provides soft light.CRI>80, IP20, Ambient temp-0 to 45 Deg C, CCT - 4000K, 50,000 hrs @ L70 life. Driver efficiency>85%, THD<10%, Powerfactor>0.95, Surge protection-4 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 150-270V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. <b>Luminaire lumen ≥ 3000 lm. (100 lm/W)</b> , Wipro Model No. LM56-301-XXX-40-WH Approved makes : Philips,Havells, Wipro,Tisva	20.00	Nos	0.00	0.00
203	"Supply Installation Testing Commissioning of Indoor Surface mounted round downlight 15-18W surface Mounted round backlit downlighter with below features Pressure die cast Aluminum alloy housing for better thermal conductivity. 1. Powder coated using Nano technology for longer durability. 2. PS diffuser for optimum light transmission. Round Version. 3. Efficacy of Fixture 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 0 deg K, 4000 deg K, 3000 deg K DLCR 18w D/L Approved makes : Philips,Havells, Wipro,Tisva	9.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
204	<p>Indoor BATTEN Lighting 28W-33w 1200MM Surface mounted TUBE LIGHT/batten with below features Extuded Aluminum alloy housing for better thermal conductivity. Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission or opiton of Lens Based profile for better task lighting. Option to be selected by Architect / Consultant Efficacy of Fixture 95 Lumens /watt Available with 5700K, 4000K &amp; 3000K CCT. CRI&gt;80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at &gt;0.9 PF. &lt;5% THD LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance &amp; Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) PF &gt;=0.95 and THD &lt;=5 % (Certificate need to be submitted from NABL Accredited lab) Equivalent to INDO BATTEN 28W 4ft Approved makes : Philips,Havells, Wipro,Tisva</p>	6.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
205	Supply Installation Testing Commissioning of Indoor recess mounted FOKUS LED Downlight: DALI DIMMABLE 18W, High efficient deep recess mounted COB LED DALI Dimmable downlighter with extruded aluminium housing with UGR<19. High efficiency PC frosted reflector optics for effective thermal management using aluminium casting. CRI>80, CCT - 4000K, 50,000 hrs @ L70 life.IP20, Ambient temp-0 to 45DegC, Driver efficiency>85%, THD<10%, Powerfactor>0.95, Surge protection-2.5 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 100-260V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Cutout Dia-ø70mm. Luminaire lumen ≥ 1620 lm. (90 lm/W), Wipro Model No.LD07-211-038-40-WH	15.00	Nos	0.00	0.00
206	Supply Installation Testing Commissioning of Indoor recess mounted profile as per below fetures Recessed Trim Magnetic Profile 23 MM Width, Length of 2 Meter, – Multiple lighting solutions and Tool less installation features, running on low voltage of 48V and On/off , Magnetic profile made from Extruded Aluminium comes with Extreme simplicity & the ease with which multiple track heads can be combined allows to free up the creativity of the project. Accent, Spot, Ambient - Any lighting effect is possible. Premium Body Finish Black. Written Approval required for each and every lighting products of the Project after conducting lighting demonstration to Architect.Equivalent Wipro Model - LDX174-1C-1M-RM Approved makes : Philips,Havells, Wipro,Tisva	1.00	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
207	Supply Installation Testing Commissioning of Indoor recess mounted profile as per below fetures Recessed Trim Magnetic Profile 23 MM Width, Length of 2 Meter, – Multiple lighting solutions and Tool less installation features, running on low voltage of 48V and On/off , Magnetic profile made from Extruded Aluminium comes with Extreme simplicity & the ease with which multiple track heads can be combined allows to free up the creativity of the project. Accent, Spot, Ambient - Any lighting effect is possible. Premium Body Finish Black. Written Approval required for each and every lighting products of the Project after conducting lighting demonstration to Architect. Wipro Model - LDX175-1C-2M-RM Approved makes : Philips,Havells, Wipro,Tisva	3.00	Mtr	0.00	0.00
208	Supply, Instllation, Testing and Commissioning of 600 MM Length Ambient Lighting Inset made with Extruded Aluminium, Premium High Transmission Opal Diffuser, 20W LED generating 1600 Lumens, 48V, 120* Degree Beam angle for wide Spread lighting distribution with 30000 Burning Hours. CRI 80, Control: on/off, dimming with RF remote. Premium Body Finish White and Black. Wipro Model - LD17L251X 2765BRF LD17L Approved makes : Philips,Havells, Wipro,Tisva	4.00	nos	0.00	0.00
209	Supply, Instllation, Testing and Commissioning of 220 MM Length Ambient Lighting Inset made with Extruded Aluminium, Premium High Transmission Collimeter Lens, 12W LED generating 960 Lumens, 48V, 36* Degree Beam angle for distribution with 30000 Burning Hours. CRI 80, Control: on/off, dimming with RF remote. Premium Body Finish White and Black. Wipro Model - LD17L151362765BRF Approved makes : Philips,Havells, Wipro,Tisva	10.00	nos	0.00	0.00
210	Supply, Instllation, Testing and Commissioning of 12 W Deep Glare free Spot Lighting Inset made with Extruded Aluminium, Premium Glare Free Lens, 12W LED generating 980 Lumens, 48V, Dia 35mm 24 deg Degree Beam angle, with LED lifetime of than 30,000 Hours. CRI 80,Control: on/off, dimming with RF remote, Premium Body Finish Black. Wipro Model - LD17T151242765BRF Approved makes : Philips,Havells, Wipro,Tisva	3.00	nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
211	Supply, Instllation, Testing and Commissioning of 9W Deep Glare free Down Lighting Inset made with Extruded Aluminium, with Collimeter lens , 9W LED generating 720 Lumens, 48V, 24* Degree Beam angle, with LED lifetime of 30,000 Hours. CRI 80, Control: on/off, dimming with RF remote, Premium Body Finish Black. Wipro Model - LD17M111242765BRF Approved makes : Philips,Havells, Wipro,Tisva	3.00	nos	0.00	0.00
212	LED Driver 100W input voltage range 85-300V, Output 48V DC, Output Current 2.1 Amp, 3 KVA SPD/ Maxmimum Length of track can be connected upto 12 Mtr or 80% of driver capacity, recommendations in IS 15885 (part 2/ SEC 13)	3.00	nos	0.00	0.00
213	LED Driver 200W input voltage range 85-300V, Output 48V DC, Output Current 2.1 Amp, 3 KVA SPD/ Maxmimum Length of track can be connected upto 15 Mtr or 80% of driver capacity, recommendations in IS 15885 (part 2/ SEC 13)	3.00	nos	0.00	0.00
214	Remote control for magnetic RF range2.4Hz	1.00	nos	0.00	0.00
215	Straight Joint Kit for electrical connection between two track	3.00	nos	0.00	0.00
216	Flexible Joint Kit for electrical bonnection between two horizontal/vertical track	1.00	nos	0.00	0.00
217	Vertical Mechnical Joint	2.00	nos	0.00	0.00
218	Horizontal Mechnical Joint	1.00	nos	0.00	0.00
219	Straight Mechnical Joint	4.00	nos	0.00	0.00
220	Track Channel Connector - INPUT LINE	2.00	nos	0.00	0.00
221	<b>BLUETOOTH CONTROLLER</b> The device can be connected to a maximum of 32 DALI LED drivers and can be controlled as DALI or 0-10V. It operates on a 100-277 VAC input voltage range and can also be configured in 0-10V mode to control one or two 0-10V controllable LED drivers, or a tunable white LED driver with two 0-10V control interfaces. Supports ON/OFF, dimming and tuning control of 32 DALI drivers This device comes with a 3.3VDC input. Input voltage range 100-277VAC, Surge protection-3 kV, Dimming range 0-100%, 1000 steps resolution, DALI 2.0, Bluetooth frequency range 2402-2480MHz, BLE 5.2 based with range of 30 mtr, Ambient temperature -20deg to 50deg	5.00	nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
222	<p><b>BLUETOOTH WALLSWITCH</b>            Wall Switch with a battery-powered switch that controls Features ON/OFF, intensity, and Correlated Color Temperature of an individual or group of luminaires. This five-button switch device operates on a 3V coin cell battery and is designed for maximum longevity. BLE4.2 based non-flooding intelligent communication, with range of 30 mtr, Ambient temperature -20deg to 50deg</p>	5.00	nos	0.00	0.00
223	<p>Supply, Installation Testing and Commissioning of LED high bay luminaire of 70W having System Efficacy, Should be in Narrow beam angle optics of 30 degree            &gt;145 lm/W, system output 10000 Lumens, THD &lt;10%, Power Factor &gt;0.95, CRI &gt;70, CCT 5700K, Full IP            65 protected single piece die cast aluminium housing having integrated PC lens cover having integrated optics with Impact resistance IK08, Life L70B50 @ 50k hrs. BIS compliant driver, EMC-EMI compliant. Driver shall have 4KV Surge protection. Luminaire should have option of wide and narrow beam angle options with Operating temperature range from 0 to 55 deg C. LM79 and LM80 reports must be submitted from a NABL accredited laboratory. BIS certificate for driver as well as the luminaire must be submitted for records. Driver and luminaire shall be of same make.            REF : Eterne 70w            Approved makes : Philips,Havells,, Wipro,Tisva</p>	11.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
224	<p>Supply Installation Testing Commissioning of Indoor recess mounted 35mm cut out (35x35mm profile light), Heavy aluminium Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination</p> <p>Anodised aluminium end caps firmly fixed on the aluminium extrusion</p> <p>Silver anodised finish for elegant look . Efficacy of Fixture &gt;=100 Lumens/Watt suitable for self adhesive Strips with driver.</p> <p>Wattage should be 40-55w/m. Should have a dotless continous effect. Should be operated using remote driver of 24V Dc kept at suitable locations for future maintainance.</p> <p>REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) Lume series Strip light LSX20Y145S4</p> <p>Approved makes : Philips,Havells, Wipro,Tisva</p>	315.00	Mtr	0.00	0.00
225	<p>Supply Installation Testing Commissioning of Indoor recess mounted 17-20mm cut out (17x16mm profile light), Heavy aluminium Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination</p> <p>Anodised aluminium end caps firmly fixed on the aluminium extrusion</p> <p>Silver anodised finish for elegant look . Efficacy of Fixture &gt;=100 Lumens/Watt suitable for self adhesive Strips with driver.</p> <p>Wattage should be 14-17w/m. Should have a dotless continous effect. Should be operated using remote driver of 24V Dc kept at suitable locations for future maintainance.</p> <p>REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) Lume series Strip light LSX20Y145S4</p> <p>Approved makes : Philips,Havells,, Wipro,Tisva</p>	40.00	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
226	Supply Installation Testing Commissioning of Indoor recess mounted profile light 1200mm lighting fixture with below features 30W 4ft, High efficiency long life Linear recessed luminaire with white powder coated finish extruded aluminium housing & continuous option with 56 mm Width & 86 mm Height. Special translucent satin finish colour LED PMMA Diffuser. LED driver duly wired up to terminal block for easy installation and long service. Luminous efficacy not less than 105lm/W. CRI>80, IP20, Ambient temp-0 to 45DegC, Driver efficiency>85%, THD<10%, CCT- 5700K, 50,000 hrs @ L70 life, Powerfactor>0.95, Surge protection-2 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 198-264V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Luminaire lumen ≥ 3150lm. Available in continuous as well as standalone configuration. Wipro Model - LM34-251XX-40RMCG1 Approved makes : Philips,Havells,, Wipro,Tisva	29.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
227	Supply, installation, testing, and commissioning of Designer Decorative Hanging Luminaire with overall diemsnion of 1300 MM x 1000 MM. Dream Luminaire is made with special MS with designer glass delivering a 60% light output ratio and has a body finish of Gold and White. The lamp source of OSRAM/NICHIA/SAMSUNG LED with an Efficacy of 110lm/W. Thermal management using Passive cooling generating overall led lifetime>20000hrs, CRI>80, CCT 3000K, 4000K, 5700K. The Interior lights Should comply with Indian Interior illumination standard IS 3646-1. LED Driver should be Protected up to 2.5 kV power network fast transients, High efficiency, 0.87, PF >0.95, THD<15 Built in strain relief for independent use, lacquer coating provides improved robustness in challenging climate conditions (humidity, temperature). Operating Voltage range 198 - 264 VAC, External NTC thermal input, and considering all recommendations in IS 15885 (part 2/ SEC 13) having Driver life time of more than 50000 Hours. Written Approval required for each and every lighting products of the Project after conducting lighting demonstration to Architect. Equivalant to KLS DREAM HANGING DECORATIVE LIGHT G9 BASE WITH SPECIAL COLOR PALETTE AND DESIGN Approved make KLS,wipro.Philips,Tisava, Lighting technolgies	1.00	Nos	0.00	0.00
228	Supply Installation Testing Commisioning of decorative wall light Surface Mounted 5W X 2 Wall-mounted compact updown light emission designed to use monochromatic Warm white (3000K) & Neutral white (4000K).Aluminum die cast housing duly Powder coated in gray colour throw upward and downward lighting(108 x 108 x 35) mm. High efficacy LEDs. High efficiency lens optics. Protection class IP65. Colour rendering index (CRI)>70. Prewired with LED driver and suitable for operating on 240V, 50Hz single phase ac supply. Driver efficiency >75%, Power factor >0.9, THD <20%, Surge protection 2KV. Luminaire dimension : 108 x 38mm. Approved makes : Philips,Havells, Wipro,Tisva	30.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
229	"Supply Installation Testing Commissioning of 600w-900w customized Chandelier light as per lighting concept given by Architect contractor shall provide lighting design with fixing detail considering all the specification, Chandelier light directly mouted on ceiling with wooden support. with 16 pcs of pendant light verious size:1200mm,1000mm & 500 mm(Dia) with below features Multiple Cluster arrangements to create fall like pattern having Chandelier length of 15 Meter. Product with premium mitsubishi acrylic material Better ambience creation and illumination for the space Long life and highly durable product Premium aesthetics maintained for a long time Brilliant light effect. Gives a notion light getting emitted for curved acrylic edges Easy height adjustment Made from non-toxic materials Colour: Iron / Gold Power: 20w to 45w per fixtrues , INTEGRAL LEDs, SMD 2835 Basic Rate of Light-Rs. 7,50,000/-	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
230	"Supply Installation Testing Commissioning of 600w-900w customized Chandelier light as per lighting concept given by Architect contractor shall provide lighting design with fixing detail considering all the specification, Chandelier light directly mouted on ceiling with wooden support. with 6 pcs of pendant light various size:1200mm,1000mm & 500 mm(Dia) with below features Multiple Cluster arrangements to create fall like pattern having Chandelier length of 1.5 Meter. Product with premium mitsubishi acrylic material Better ambience creation and illumination for the space Long life and highly durable product Premium aesthetics maintained for a long time Brilliant light effect. Gives a notion light getting emitted for curved acrylic edges Easy height adjustment Made from non-toxic materials Colour: Iron / Gold Power: 20w to 45w per fixtrues , INTEGRAL LEDs, SMD 2835 Basic Rate of Light- Rs.85000/-	1.00	Nos	0.00	0.00
231	SCULPTURE with LIGHT : Model equivalent to LED FLOOR LIGHT FL9311GD+BK as per approved sample by Architect /Client.	2.00	Nos	0.00	0.00
232	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, Conforms to IS 8623-1 & 3, IEC 61439-1 & 3 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) suitable for. (A) single phase incoming and horizontal single phase outgoing. (iv) <b>Single phase 12 way</b> SS Double door	1.00	Each	0.00	0.00
233	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) <b>Three phase 8 way</b> SS Double door for horizontal single phase outgoing	3.00	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
234	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) <b>Three phase 16 way SS Double door</b> for horizontal single phase outgoing	1.00	Ea	0.00	0.00
235	providing and erecting Miniature circuit breaker <b>single pole 6A to 25A</b> suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark Cat.III	106.00	EA	0.00	0.00
236	Providing & erecting 240 V <b>MCB double pole switch</b> for motor & inductive load ( <b>C Curve</b> ) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (B) 40 Amp.	1.00	Ea	0.00	0.00
237	Providing & erecting 415 V <b>MCB Four Pole</b> for Motor & Inductive Load ( <b>C Curve</b> ) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (a) 6 to 32 Amp. Cat.III	3.00	Ea	0.00	0.00
238	Providing & erecting 415 V MCB <b>Four Pole for Motor</b> & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity C) <b>63 Amp.</b> CAT-III	1.00	Ea	0.00	0.00
239	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 25 Amps.DP Cat. III	6.00	Ea	0.00	0.00
240	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 40 Amps.DP Cat. III	7.00	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
241	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 63 Amps.DP Cat. III	8.00	Ea	0.00	0.00
242	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables (B) 3 1/2 core 35 Sq. mm ( 16 Sq. mm 1/2 core)	50.00	Mtr	0.00	0.00
243	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables. A)4 core 16 Sq. mm	700.00	Mtr	0.00	0.00
244	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables (B) 4 core 6 Sq. mm	110.00	Mtr	0.00	0.00
245	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables C) 4 core 10 Sq. mm	50.00	Mtr	0.00	0.00
246	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cable. (C) 3 core 6 Sq. mm	90.00	MTR	0.00	0.00
247	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cable. (A) 3 core 2.5 Sq. Mm	70.00	MTR	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
248	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand / Solid Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cables. (A) 4 core 2.5 Sq. mm	70.00	MTR	0.00	0.00
249	Providing and, fixing heavy duty flange type brass double compression type cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. (B) 3 & 1/2 core 35/50 Sq. mm	2.00	EA	0.00	0.00
250	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. D) 2 to 4 core 16 Sq. mm	12.00	Ea	0.00	0.00
<b>Total Amount</b>					<b>0.00</b>
<b>F</b>	<b>Part-6</b>				
251	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. (B) 2 to 4 core 6 Sq. mm	6.00	Ea	0.00	0.00
252	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. C) 2 to 4 core 10 Sq. mm	2.00	Ea	0.00	0.00
253	Solder less crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (D) 35/50 Sq.mm.	8.00	Ea	0.00	0.00
254	Solderless crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (C) 16/25 Sq.mm.	48.00	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
255	Solderless crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. B)10 Sq. mm	8.00	Ea	0.00	0.00
256	Solder less crimping type Copper lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (B) 6 Sq.mm	16.00	Ea	0.00	0.00
257	Solder less crimping type Copper lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (A) 1.5/2.5 to 6 Sq.mm	8.00	Ea	0.00	0.00
258	providing and erecting Approved make <b>Four pole moulded case circuit breaker</b> having breaking capacity ICU of 25 KA. at 415 V, having normal current rating up to <b>25 A to 100A</b> . with Fixed thermal & magnetic release suitable to work on A.C. supply 50 c/s. with all internal connections & complete erected in existing 16 G.M.S. housing. ICS=100% of ICU only. Cat III	10.00	Each	0.00	0.00
259	Providing and erecting HOT deep Galvanised iron strip wire 8 to 16 SWG.	30.00	KG	0.00	0.00
260	Providing and erecting required size HOT deep Galvanised iron strip for earthing of H.T. , OCB/ ACB/ Transformer LT panel board, Motors etc. using proper clamp.	50.00	KG	0.00	0.00
261	Supplying and erecting approved make online Un-interruptible Power Supply system comprising flat cum-boost charger, static Inverter & sealed maintenance free SMF batteries. The charger having operating capacity for input 160-270V AC & inverter having output 230V,50 Hz Ac with 0.8 load power factor with battery, over/under voltage output with over load & short circuit protection equipment. The system housed in CRC sheet duly powder coated paint with following power backup.with MS painted batteries stand, 10% Overload capacity for momentary load. (E) 10 KVA 3 - phase with 1Hr Backup	1.00	EA	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
262	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed (b) 25 mm	100.00	Mtr.	0.00	0.00
263	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed (c) 32 mm	100.00	Mtr.	0.00	0.00
264	Supplying and laying UPVC cable trunking system comprising unplasticised polyvinyl, chloride rigid material with ignition free and flame proof confirming BS with necessary end caps Internal and external bend, flat bends, coupler, tee etc..All necessary accessories and measuring of following sizes (1) 75 mm x 50 mm trunking	70.00	RMT	0.00	0.00
265	(2) 100 mm x 50 mm trunking	40.00	RMT	0.00	0.00
266	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..150 X 50 X 1.5 mm Thick	250.00	RMT	0.00	0.00
267	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge.300 X 50 X 1.5 mm Thick	20.00	RMT	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
268	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (3) 150 X 50 X 1.6 mm Thick 90° Elbow	4.00	EA	0.00	0.00
269	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (5)300 X 50 X 2.0 mm Thick 90° Elbow	2.00	EA	0.00	0.00
270	Supplying under floor pregalvanised corrosion proof rectangular sheet steel cable trunking of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories,Junction Box, Joints as required and demanded by engineer-incharge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Cat-III [10] 150mm x 38mm x 1.6mm with Three Compartments	50.00	Mtr	0.00	0.00
271	[12] 250mm x 38mm x 1.6mm with Three Compartments	30.00	Mtr	0.00	0.00
272	Supplying under floor pregalvanised corrosion proof rectangular sheet steel cable trunking Junction Box of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories,Joints as required and demanded by engineer-incharge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Cat-III [10] 200mm x 50mm x 1.6mm with Three Compartments	7.00	Mtr	0.00	0.00
273	[12] 300mm x 50mm x 1.6mm with Three Compartments	5.00	Mtr	0.00	0.00
274	[13]400mm x 50mm x 1.6 mm with Three Compartments	1.00	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
275	SITC of 4MP Fixed Lens Dome Type Camera, H.265 4MP IR Vandal Proof Dome N/W Camera, 2.8mm/3.6mm, 30M IR, Micro SD, DC12V/PoE, IP67/IK10, Basic IVA, 1 / 2.7" CMOS, 2560 × 1440, 0.01 Lux, F1.2, AGC ON; Defog, True day/night, Digital WDR, 3D DNR, HLC & BLC, Triple streams, Smart codec by ROI, Cyber Security, Basic intelligent video analytics, NDAA Compliance, UL, CE, FCC Certified	9.00	Nos.	0.00	0.00
276	SITC of 5 MP Motorised Varifocal Lens Bullet Camera - H.265 5MP IR Bullet N/W Camera, 25/30FPS, Motorised Varifocal 2.8-12mm, IR up to 70M, Micro SD support up to 128GB, DC12V/PoE, IP67/IK10, Basic IVA, 2 MP resolution (2592 × 1944), True day/night, Digital WDR, 3D DNR, HLC & BLC, Triple streams, Smart codec by ROI, Cyber Security, Intelligent video analytics, NDAA Compliance, UL, WEEE, REACH CE, FCC Certified, IK10 & IP67, Opp Temp - 30 °C to 60 °C, ONVIF S,G,T	4.00	Nos.	0.00	0.00
277	SITC of Jack Cat 6 Keystone UTP	13.00	Nos.	0.00	0.00
278	SITC of 24 x 10/100/1000BASE-T PoE ports 4 x Gigabit RJ45/SFP Combo ports Advanced L2 switching and security features. L2+ Static Routing Optional "standard mode" or "surveillance mode" management user interface 193 W PoE budget	1.00	Nos.	0.00	0.00
279	SITC of 4 Pair LSZH CAT6 UTP Cable	780.00	Mtr.	0.00	0.00
280	SITC of 9U/600 Rack/ Welded/WM/Off White,Glass Door/9U/WM/Gray,Server /IT Rack mount power distribution unit, 1Ph, 230V, 16A, 50/60Hz, 2U standard with 6 X Indian Round Pin 5/15A, Inlet Plug type 16A Indian Round Pin, 16A MCB - PDU Rating 3.6KVA/Side feed-1.5Mt/ Black,Horz. Cable Organiser/1U/Loop,Cantilever Shelf/Type2/1U/Off White,Mounting Hardware-CR (Pack of 20),ITE / Server Rack Air Circulation module/90CFM	1.00	Nos.	0.00	0.00
281	SITC of Conduit Box for CCTV	13.00	Nos.	0.00	0.00
282	SITC of Analogue Addressable Smoke Sensor which is fully compatible with Analogue Addressable Protocol, having removable high performance chamber with Twin fire LED's allow 360 degree viewing, User selectable sensitivity modes 1% to 4.5% obs/m, Incorporate Optical elements, lock mechanism (sensor to base), Electronically addressed, Pulsing/non-pulsing controlled from panel. Approved by LPCB & VdS.	12.00	Nos.	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
283	SITC of Analogue Addressable Multi- Sensor which is fully compatible with Analogue Addressable Protocol,having removable high performance chamber with Twin fire LED's allow 360 degree viewing, User selectable sensitivity modes 1% to 4.5% obs/m, Incorporate Optical and dual Heat elements, lock mechanism (sensor to base), Electronically addressed, Pulsing/non-pulsing controlled from panel. Approved by LPCB & VdS.	5.00	Nos.	0.00	0.00
284	SITC of IP67 Rated Waterproof Addressable Multi-Heat Sensor which can be used externally and is supplied with its own fixing base which is used to fix the sensor. Flying leads from the sensor connect directly to the loop via waterproof connectors. Approved by LPCB & Vds.	2.00	Nos.	0.00	0.00
285	Supply, Installation, Testing and Comissioning of infra-red beam smoke detectors With ground Level adjust controller, Combined transmitter and receiver unit in one discrete unit. The detector shall have Range 5 to 120 metres With Light cancellation technology, Detector Should have Optional transmitter powering from controller only Approved by EN54:12, UL268 and VdS.	4.00	Nos.	0.00	0.00
286	SITC of Analogue Addressable Manual Call Point with Integral Short Circuit Isolator, Analogue Addressable Protocol having, Bi-coloured status LED (red for alarm, amber for (short-circuit), Non-frangible element fitted as standard (conforms to EN54), pulsing/non-pulsing can selectable via panel, Electronically addressed, Approved by LPCB.	4.00	Nos.	0.00	0.00
287	SITC of Intelligent Loop Powered Wall Sounder Beacon, Variable Sound Output 90 ~ 102 dB(A) (±2 dB(A)) output at 1 metre, High Intensity LED technology, 51 User-Selectable Tones (all tones EN54-3 compatible). Approved by LPCB & VdS	4.00	Nos.	0.00	0.00
288	Supply,Instllation,Testing and Commissioning of Addressable Exit Signage visible from 20 mtrs. with integral battery capacity of 3 hrs and bicoloured LED status indicator. Exit signage shall be comply with ISO 3864/ISO7010	5.00	Nos.	0.00	0.00
289	Supply, Installation, Testing and Comissioning of 2 Core 1.5 Sq.mm FRLS Cable (Red Color)	600.00	Mtrs.	0.00	0.00
290	SITC of Jack Cat 6 Keystone UTP	32.00	Nos	0.00	0.00
291	SITC of Face Plate - Single (Keystone Jack,square)	32.00	Nos	0.00	0.00
292	SITC of Back Box	32.00	Nos	0.00	0.00
293	SITC of 25MM PVC Conduit with Accessories	950.00	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
294	SITC of 32mm PVC Flexible Pipe with Accessories	100.00	Mtr	0.00	0.00
295	SITC of 25mm HDPE Pipe with Accessories	48.00	Mtr	0.00	0.00
296	SITC of 32mm GI Flexible Pipe with Accessories	24.00	Mtr	0.00	0.00
297	SITC of 50MM PVC Flexible Pipe with Accessories	24.00	Mtr	0.00	0.00
298	SITC of 24 x 10/100/1000 Base-T Switch with additional 4 x 10G SFP+ Ports, Rack-mountable, It should support stacking, should support features like static routing, RIP, DHCP, ACL, QoS, VLANs, LAGs, LACP, and port mirroring, Switch's Operating System should be tested under Common Criteria Certification. and complying to details technical specs in attacehd sheet	1.00	Nos	0.00	0.00
299	SITC of Maximum distance of up to 10 km Hot-pluggable Single-mode fiber 10GBASE-LX Duplex Fiber module with LC connector	4.00	Nos	0.00	0.00
300	SITC of Next generation enterprise Wi-Fi 6 (802.11ax) access points, It should be resilient, secure, and intelligent. Comes with Embedded Wireless Controller, Minumum 4 nos of 2.4 GHz 2 dBi/5 GHz 4 dBi Dipole Extranal Antenna, AP's should be tested under Common Criteria Certification. and complying to details technical specs in attacehd sheet	10.00	Nos	0.00	0.00
<b>Total Amount</b>					<b>0.00</b>
<b>G</b>	<b>Part-7</b>				
301	SITC of 85" Resolution 3840 x 2160 (UHD-4K),Brightness 300 nit,Contrast ratio 4000:1,Panel type Direct LED BLU, IP Rating IP5X,Connectivity HDMI 2.0(2), HDCP 2.2, Stereo Mini Jack, USB 2.0,Stereo Mini Jack, Ext: RS232C(in/out), RJ45,3 Side Bezel Less	1.00	Nos	0.00	0.00
302	SITC of Ceiling Speaker with 2 way. Passive, Low Impedance Power 30 W @ 8 Ohm, L100V Power 3.8W / 7.5W / 15W / 30W, L70V Power 1.9W / 3.8W / 7.5W / 15W / 30W, LF, Transducer Woofer 6.5", HF Transducer Tweeter 0.5", Frequency Range 90 Hz - 20 KHz, Coverage 155° x 155° @ 1 KHz; 75° x 75° @ 4 KHz, Sensitivity 88 dB, Max SPL 102 dB, Mounting diameter 200 mm, Fixation Rotating anchors, Material Enclosure: Metal; Grille: ABS plastic.	8.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
303	SITC of Amplifier with Mixer and Player with Low impedance (4/8/16 Ohm), Line 25/70/100 V, Power 240 W, Input Sensitivity CD: 700 mV, Tuner: 500 mV, Tape: 220 mV, Aux in: 100 mV, Mic: 2.7 mV, Line: 125 mV, Tel: 100 mV, Input Impedance CD: 80 KOhm, Tuner: 56 KOm, Tape: 20 KOhm, Aux in: 20 KOhm, Mic: 600 Ohm, Line: 47 KOhm, Tel: 20 KOhm, Connectors 4 x XLR3 / Jack combi (Mic / Line), 1 pair RCA (CD, Tuner, Tape, Aux in), RCA (Pre out, Main in), Terminals (Amp out, Tel, Priority) Controls Independent volume for each input channel, Master volume, Tone control (treble / bass), Audience zone selector, Player recorder control, Frequency Response Mic: 50 Hz - 14 KHz, Line: 30 Hz - 14 KHz, Tel: 100 Hz - 3 KHz, THD+N < 1% @ 1 KHz, Phantom Power +24 V, Other functions Selection of audience zones, recorder / player, 4 chime tones, telephone / emergency connection.	1.00	Nos	0.00	0.00
304	SITC of 2.5 sq mm Oxygen Free High Gain Loudspeaker Cable	200.00	Nos	0.00	0.00
305	SITC of Audio Microphone Cable	200.00	Nos	0.00	0.00
306	Supply, Installation, Testing and Commissioning of UHF wireless microphone system, sound clarity,impeccable performance,make the er 58 series one of the most popular wireless microphone system currently available. With head mic and inbuilt battary.	1.00	Nos	0.00	0.00
307	SITC OF Chairman unit gooseneck microphones, Priority button for chairman microphone. Optional chime tone facility preceding chairman announcements. Modern, Microphone with flexible stem and light ring. Two headphone sockets.	3.00	Nos	0.00	0.00
308	SITC OF Central Control Unit Better discussion control Controls up to 50 Discussion units 3-Band equaliser for better sound performance Audio interfaces for connecting external audio equipments	1.00	Nos	0.00	0.00
309	SITC OF System Rack 600/600/800 along with require accessories as per site requirement complete as per approve by consultant.Approved Make :- Valrack, Siemens, Elixir	1.00	Nos	0.00	0.00
310	SITC 65 INCH of Resolution 3840 x 2160(UHD-4K),PQI (Picture Quality Index) 2200,Contrast ratio: Mega Contrast,Panel type : Nonglare,AirSlim:Yes,Connectivity:WiFi, Bluetooth, HDMI(3), HDCP1.4/2.2, USB(1), RJ45,Web browser, Youtube,3 Side Bezel Less	2.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
311	SITC of Ceiling Speaker with 2 way. Passive, Low Impedance Power 30 W @ 8 Ohm, L100V Power 3.8W / 7.5W / 15W / 30W, L70V Power 1.9W / 3.8W / 7.5W / 15W / 30W, LF, Transducer Woofer 6.5", HF Transducer Tweeter 0.5", Frequency Range 90 Hz - 20 KHz, Coverage 155° x 155° @ 1 KHz; 75° x 75° @ 4 KHz, Sensitivity 88 dB, Max SPL 102 dB, Mounting diameter 200 mm, Fixation Rotating anchors, Material Enclosure: Metal; Grille: ABS plastic.	8.00	Nos	0.00	0.00
312	SITC of Amplifier with Mixer and Player with Low impedance (4/8/16 Ohm), Line 25/70/100 V, Power 240 W, Input Sensivity CD: 700 mV, Tuner: 500 mV, Tape: 220 mV, Aux in: 100 mV, Mic: 2.7 mV, Line: 125 mV, Tel: 100 mV, Input Impedance CD: 80 KOhm, Tuner: 56 KOm, Tape: 20 KOhm, Aux in: 20 KOhm, Mic: 600 Ohm, Line: 47 KOhm, Tel: 20 KOhm, Connectors 4 x XLR3 / Jack combi (Mic / Line), 1 pair RCA (CD, Tuner, Tape, Aux in), RCA (Pre out, Main in), Terminals (Amp out, Tel, Priority) Controls Independent volume for each input channel, Master volume, Tone control (treble / bass), Audience zone selector, Player recorder control, Frequency Response Mic: 50 Hz - 14 KHz, Line: 30 Hz - 14 KHz, Tel: 100 Hz - 3 KHz, THD+N < 1% @ 1 KHz, Phantom Power +24 V, Other functions Selection of audience zones, recorder / player, 4 chime tones, telephone / emergency connection.	1.00	Nos	0.00	0.00
313	SITC of NFC-Enabled Bluetooth 4.1 Music Receiver with Connect to stereo system supporting 3.5mm AUX or RCA jacks, NFC quick pairing & easy setup one click to pair up with your NFC-enabled devices as soon as getting close to the HA100 or NFC tag.	1.00	Nos	0.00	0.00
314	SITC of 2.5 sq mm Oxygen Free High Gain Loudspeaker Cable	200.00	MTR	0.00	0.00
315	FOH Left & Right Loudspeaker with 2-Way Coaxial Point Source Loudspeakers, Freq Response 48Hz-20kHz, Max SPL 135dB, Operating Mode LF/HF, DSP w/ EAW Focusing & DynO, Subsystem LF Transducer – 1x12" cone, 2.5" VC, Vented HF Transducer – 1x1-in exit, 44mm voice coil compression driver, Concentric Summation Array (CSA) loaded, Nominal Beamwidth 90 x 60 degrees, rotatable, Power Handling 600W @ 8ohms.	2.00	Nos	0.00	0.00
316	Passive Delay Speaker with Frequency Response 70Hz-20kHz, Max SPL 125dB, Operating Mode Single-Amp (LF/HF, DSP w/ EAW Focusing & DynO), Subsystem LF Transducer – 1x6.5in cone, 1.5in VC, Vented, HF Transducer – 1x1in dome tweeter, coaxial, Nominal Beamwidth 110 degrees conical, Power Handling 250W @ 8ohms.	4.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
317	Audio Amplifier For Above Speakers with Channels 4, Output power @ 4ohms 4 x 800W, Output Power @ 8ohms 4 x 400W, Output Circuitry UMAC™ Class D - full bandwidth PWM modulator with ultra-low distortion, Output Voltage 85 Vp / 170 Vpp (unloaded) // Bridged 170 Vp / 340 Vpp (unloaded), Signal To Noise-Ratio > 108 dB (A-weighted, 20 Hz – 20 kHz, 8 Ω load), THD+N (typical) < 0.05% (20 Hz – 20 kHz, 8 Ω load, 3 dB below rated power), Frequency Response 20 Hz – 20 kHz (+/- 0.5 dB, 8 Ω load, 3 dB below rated power), Protection Circuits Short circuit -, DC -, Undervoltage -, Temperature - and Overload protection, Power Supply UREC™ universal mains switch mode power supply with Power Factor Correction (PFC) and standby converter.	1.00	Nos	0.00	0.00
318	Active Subwoofer with Direct Radiation Subwoofer, Power 1500W, transducers 1x 15", Rated Impedance 8 ohms, Sensitivity (1W @ 1m) 132dB, Frequency Range 40Hz - 125Hz, Enclosure material High density wood.	2.00	Nos	0.00	0.00
319	Wall Plate for Video Connectivity with Dimension 250x90x42 mm, 1 x Universal Power, 2 x RJ45 Network, 1 x HDMI, 1 x USB, 1 x VGA, 1 x 3.5mm Audio.	1.00	Nos	0.00	0.00
320	HDMI EXTENDER OVER HDBaseT - 70 METER 4K , TX RX set, Transmitter Inputs 1xHDMI Type A , 1xIR INPUT, 1xRS232, 1xService, Outputs 1xHDBaseT Out ,1xIR OUTPUT, Receiver Inputs 1xHDBaseT In,1xIR INPUT, 1xRS232 ,1xService, Outputs 1xHDBaseT Out, 1xIR OUTPUT.	1.00	Nos	0.00	0.00
321	2.5 sq mm Oxygen Free High Gain Loudspeaker Cable	200.00	Mtr	0.00	0.00
322	Audio Microphone Cable	200.00	Mtr	0.00	0.00
323	Speaker Brackets	6.00	Nos	0.00	0.00
324	Equipment Rack 24 U (800 L X 600W X 1900H )in MM Approx	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
325	SITC of 55" Ultra Narrow Bezel LCD Video Wall Display  500 Nits Brightness  450000:1 Dynamic Contrast Ratio Bezel Width : 3.5 mm   Daisy Chain with Display Port or HDMI Option   Landscape and Portrait Mode   Pixel Shifting   Remote control by IR Simulation or LAN/RS232 Control   Supports RS232 Loop Configuration Operation: 24/7  1xVGA, 2xUSB 2.0 , Secure USB 2.0 (Internal), RJ45, RJ12, RS232, Optical SPDIF  1xHDMI 2.0 Out,DP Loop In/Out,Supports Daisy Chain   Videowall setup with Daisy-Chain,IP5x rating, Open Content Management Support, Manual Fine Color Calibration, Videowall Scheduler,Auto-Launch, Auto-switch on Failover, Panel Lock   Certifications: Safety, EMC, CE	9.00	NOS	0.00	0.00
326	SITC of Fixed wall Mounting Bracket for Videowall	9.00	NOS	0.00	0.00
327	SITC of a Digital Signage Player must have Advance user interface must be able to Publish pictures & videos, Schedule your content must have Easy screen management must be able to add Multiple users must be able to Publish website. (With 5 year Premium Licence)	1.00	NOS	0.00	0.00
328	SITC of Desktop PC with 12th Gen Intel® Core™ i5-12500 Windows 10 Pro Intel® Integrated Graphics 16 GB, 1 x 16 GB, DDR5 500 GB, 7200 RPM, 3.5-inch, SATA, HDD	1.00	NOS	0.00	0.00
329	SITC of Cables & Conenctor	1.00	NOS	0.00	0.00
330	Supply, Installation, Testing & Commissioning of POP up box, Make: Kramer (Model - TBUS-1AxI(BC))	1.00	Nos.	0.00	0.00
331	Supply, Installation, Testing & Commissioning of USB Extender cable- 15 Mtr, Make: Kramer (Model - CA-USB3/AAE-50)	2.00	Nos.	0.00	0.00
332	Supply, Installation, Testing & Commissioning of USB type Male to male - 2Mtr	2.00	Nos.	0.00	0.00
333	Supply, Installation, Testing & Commissioning of HDMI to HDMI cable - 15 Mtr (Model - C-HM/HM-50)	2.00	Nos.	0.00	0.00
334	Supply, Installation, Testing & Commissioning of HDMI to HDMI cable - 2 Mtr (Model - C-HM/HM-6)	4.00	Nos.	0.00	0.00
335	Supply, Installation, Testing & Commissioning of 2x1 HDMI Matrix Switcher, Make: Kramer (Model - VS-211H2)	3.00	Nos.	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
336	Supply, Installation, Testing & Commissioning of HDMI cable male to male - 15 Mtr, Make: Kramer (Model - C-HM/HM-50)	1.00	Nos.	0.00	0.00
337	Supply, Installation, Testing & Commissioning of HDMI cable male to male - 2 Mtr, Make: Kramer (Model - C-HM/HM-6)	3.00	Nos.	0.00	0.00
338	SITC of 75 INCH Resolution 3840 x 2160 (UHD-4K),Brightness 300 nit,Contrast ratio 4000:1,Panel type Direct LED BLU, IP Rating IP5X,Connectivity HDMI 2.0(2), HDCP 2.2, Stereo Mini Jack, USB 2.0,Stereo Mini Jack, Ext: RS232C(in/out), RJ45,3 Side Bezel Less	2.00	Nos	0.00	0.00
339	SUPPLY OF SAMSUNG MAKE VARIABLE REFRIGERANT FLOW SYSTEM : Outdoor Units : 40 HP (Top Discharge Cooling Only) System No. 3	1.00	Nos.	0.00	0.00
340	34 HP (Top Discharge Cooling Only) System No. 4	1.00	Nos.	0.00	0.00
341	30 HP (Top Discharge Cooling Only)	1.00	Nos.	0.00	0.00
342	4 Way Cassette Type Indoor Unit : 3.6 TR	1.00	Nos.	0.00	0.00
343	4 Way Cassette Type Indoor Unit : 2.0 TR	7.00	Nos.	0.00	0.00
344	4 Way Cassette Type Indoor Unit : 4.0 TR	7.00	Nos.	0.00	0.00
345	Ductable Type Indoor Unit : 4.0 TR	12.00	Nos.	0.00	0.00
346	Remote : Cordless Remote for Cassette unit	8.00	Nos.	0.00	0.00
347	Remote : Corded Remote for Ductable unit	19.00	Nos.	0.00	0.00
348	All refrigerant Joints	24.00	Nos.	0.00	0.00
349	INSTALLATION OF SAMSUNG MAKE VARIABLE REFRIGERANT FLOW SYSTEM - INDOOR & OUTDOOR UNITS AS PER DRAWINGS Outdoor Units : 40 HP (Top Discharge Cooling Only) System No. 3	1.00	Nos.	0.00	0.00
350	34 HP (Top Discharge Cooling Only) System No. 4	1.00	Nos.	0.00	0.00
	<b>Total Amount</b>				<b>0.00</b>



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
<b>H</b>	<b>Part-8</b>				
351	30 HP (Top Discharge Cooling Only)	1.00	Nos.	0.00	0.00
352	4 Way Cassette Type Indoor Unit : 3.6 TR	1.00	Nos.	0.00	0.00
353	4 Way Cassette Type Indoor Unit : 2.0 TR	6.00	Nos.	0.00	0.00
354	4 Way Cassette Type Indoor Unit : 4.0 TR	7.00	Nos.	0.00	0.00
355	Ductable Type Indoor Unit : 4.0 TR	12.00	Nos.	0.00	0.00
356	Remote : Cordless Remote for Cassette unit	7.00	Nos.	0.00	0.00
357	Remote : Corded Remote for Ductable unit	19.00	Nos.	0.00	0.00
358	All refrigerant Joints	24.00	Nos.	0.00	0.00
359	All refrigerant piping between indoor & outdoor units. Refrigerant pipes should be insulated with Nitrile Rubber Insulation.	1.00	Lot	0.00	0.00
360	Control cables between indoor and outdoor unit. Providing & fixing control cum transmission wiring Cabling of 2 core x 0.75 sqmm copper between indoor and out door unit.	1.00	Lot	0.00	0.00
361	PVC Drain piping for the units with Insulation. 32 mm dia	175.00	Rmt	0.00	0.00
362	Testing & Commissioning charges along with topping-up of refrigerant.	1.00	Lot	0.00	0.00
363	Supply & Installation of GI Duct : 24 G	190.00	Sqmt	0.00	0.00
364	Supply & Installation of 10 mm thick Armasound Accoustic Insulation	65.00	Sqmt	0.00	0.00
365	Supply & Installation of 13 mm thick Nitrile Insulation	170.00	Sqmt	0.00	0.00
366	Supply & Installation of Continue Grill	6.00	Sqmt	0.00	0.00
367	Supply & Installation of 300 mm Jet Nozzel with Damper	50.00	Nos	0.00	0.00
368	Supply & Installation of Canvass Connection	19.00	Nos	0.00	0.00
369	Ms Patala Stand for VRF Outdoor Unit	1.00	Lot	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
370	<p><b>Passenger LIFT- 1 : Schindler , Otis ,ThyssenKrupp Elevator India @16passengers : Machine room less</b>  Supply, Installation, Testing, &amp; Commissioning of Passenger lift as per approved make ,shop drawing &amp; sample by Architect / Client . work complete including all type of civil work , scaffolding , loading , unloading , transporation , fittings, fixtures , all type of safety measures , at all floor, all levels etc. complete as per shop drawings and specifications. sample mock &amp; Shop drawing shall be approved from Architect/ Client.  No extra charges will be paid for remove of existing lift , any civil works, scaffolding required for installation of lifts works. The bidder shall carry out all civil work related to installation of lift as per the drawings and as per actual site conditions. work comprises with Lift pit cleaning , as per size of company.To fill the cutout of through old lift's M/C room with rcc plastering all type of Finshing ,patch work , white wash in lift shaft, , Cuting of old lift's front wall and expansion of another , side of front wall and filling the gape of new lift (for 1 floor), scaffolding , grouting , work for all above work , with safety precautions as per instruction / satisfaction of Client / Architect. <b>The intending bidder should visit the site prior to the bidding submission.Rate shall be quoted only after by initial site inspection further no discrepancy will be allowed for whatsoever reason.</b>  <b>As per attached technical specification data sheet in tender documents .</b>  • Capacity / No. of Passengers 1088 kg / 16 Passengers , • Speed 1.5 m/s , • Number of Stops / Entrances 10 / 10 (B1, G, 1, 2, 3, 4, 5, 6, 7, 8) , • Travel height 31.95 m , • Pit depth 1600 mm , • Headroom 6400 mm,• Shaft dimensions W x D 2000 mm x 2450 mm, • Car dimensions W x D x H 1200 mm x 2100 mm x 2139 mm,• Clear car height HKC 2100 mm, • Car Door size W x H 900 mm x 2000 mm , • Car Door Type Door center opening, 2 panels , • Shaft Wall Concrete , • Building tolerance -40 mm/ +40 mm , • Landing door fire protection classification EN 81-58 E120 [ Two hours fire rated ], • Counterweight location On the left side, • Car access sides 1 • Main stop 2 • Door drive Fermator Compact, • Drive and control Full Collective control - Simplex, • Controller position In the right door jamb (LDU) , • Controller location Landing at floor 10 on side 1• Drive Power 11.7 kW • Main connection TN-S (3L+PE+N) , • Main power supply 415 V 50 Hz , • Light power supply 230 V, • Number of trips per hour 120, • Installation method Scaffoldless with hoisting device • Maintenance period 12 months• Inverter type VAF0xx REGEN• Machine Type Permanent Magnet (PM) • Communication Options Selected Intercom TAI 1; 3 ways • Remote Monitoring • Alarm by horn in hoistway• Control options Selected Automatic return to main floor • Door pre-opening • Auto.door closing final time • Position indicator car 1  • Travel direction indicator car • Auto. Rescue Device (ARD) • Fire emergency switch • Car Front Finish Stainless steel AISI441 hairline• Front cathedral • Car lighting LED • Car operating panel faceplate finish Glass • Car Operating panel display type Standard resolution matrix• Button_Description Touch sensitive glass buttonsGlass • Car door sill Aluminium • Max decoration weight allowance 89 kg • Landing door frame dimensions 60 mm x 60 mm • Landing door sill finish Aluminium sill • Landing operating panel position In the wall.• Landing operating panel installation Surface vertical in wall • Landing operating panel faceplate finish Glass • Position indicator : Yes</p>	2.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
371	<p><b>Comprehensive Maintenance : 16 Passenger LIFT- 1 :</b> Comprehensive maintenance charges with full responsibility of carrying out repair and supply of required original spare parts to keep the elevator in fully operational condition for a period of 5 years, after expiry of 1 year free servicing and warranty period both the lifts. (All parts Mechanical/ Electrical &amp; Electronics items including if any additional Manpower/Labour charge/Third party charge etc.)</p> <p><b>Parts covered under Comprehensive : (Diamond) contract</b></p> <ul style="list-style-type: none"> <li>• Main Motor • Machine Unit, Sheave &amp; Main wire ropes, STM • Machine / Brake unit parts • Speed Governor, Gov Rope • Controller spares- Contactors, Terminal blocks, interconnecting wires, Prints. • V.F Drive unit (Invertor) • Automatic Rescue Device (where provided) • Car &amp; Landing door Liners, contacts, switches, air cords • Door operator motor, drive belts, coupler unit etc • Door safety sensors • Car &amp; Landing call registration Buttons, Floor indicators, Alarm unit • Load weighing device</li> </ul> <p>Inspection and Preventative Maintenance</p> <p><b>While observing IS14665, 14671, 15785:2007 &amp; relevant applicable state rules performs on the elevator installation(s) regular inspection and preventive maintenance. This comprises:</b></p> <ul style="list-style-type: none"> <li>- functional checking and adjustment of the drive unit, means of suspension, gearbox, brakes,traction sheave and drum, ropes, deflector sheave, hoistway doors, and guiderails of the elevator installation(s);</li> <li>- greasing the aforementioned subassemblies to the extent appropriate for the use made of the elevator installation(s);</li> <li>- checking and adjustment of the travel properties of the elevator installation(s), especially of their stopping accuracy;</li> <li>- visual and functional check of the switching, control, monitoring, and other safety equipment, and of the display and lighting equipment;</li> <li>- checking of the elevator installation(s) for functioning and damage;</li> <li>- checking the oil level of the drive unit;- to the extent required to preserve their functioning, cleaning the aforementioned subassemblies of the elevator installation(s) of dirt originating within the installation;</li> <li>- cleaning the machine room, car roof, and dry hoistway pit of dirt originating within the installation. Lubricating of guide rails and wire ropes will be carried out by Housekeeping team. 6 Regular visits will be done in each AMC contract</li> </ul> <p><b>First Year : 1 Year free servicing &amp; Warranty period)</b></p> <p><b>Comprehensive Maintenance : 16 Passenger LIFT- 1 : Second Year</b></p>	2.00	Job	0.00	0.00
372	<b>Comprehensive Maintenance : 16 Passenger LIFT- 1 : Third Year</b>	2.00	Job	0.00	0.00
373	<b>Comprehensive Maintenance : 16 Passenger LIFT- 1 : Fourth Year</b>	2.00	Job	0.00	0.00
374	<b>Comprehensive Maintenance : 16 Passenger LIFT- 1 : Fifth Year</b>	2.00	Job	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
375	<p><b>Passenger LIFT - 2 : Schindler ,Otis ,ThyssenKrupp Elevator India @ 8 passengers : Machine room less</b>            Supply, Installation, Testing, &amp; Commissioning of Passenger lift as per approved make ,shop drawing &amp; sample by Architect / Client . work complete including all type of civil work , scaffolding , loading , unloading , transporation , fittings, fixtures , all type of safety measures , at all floor, all levels etc. complete as per shop drawings and specifications. sample mock &amp; Shop drawing shall be approved from Architect/ Client.            No extra charges will be paid for remove of existing lift , any civil works, scaffolding required for installation of lifts works. The bidder shall carry out all civil work related to installation of lift as per the drawings and as per actual site conditions. work comprises with Lift pit cleaning as per size of company,To fill the cutout of through old lift's M/C room with rcc plastering all type of Finshing ,patch work , white wash in lift shaft, , side of front wall and filling the gape of new lift ,scaffolding , grouting , work for all above work , with safety precautions as per instruction / satisfaction of Client / Architect. <b>The intending bidder should visit the site prior to the bidding submission.Rate shall be quoted only after by initial site inspection further no discrepancy will be allowed for whatsoever reason.As per attached technical specification data sheet in tender documents .</b>            • Capacity / No. of Passengers 544 kg / 8 Passengers • Speed 1.5 m/s • Number of Stops / Entrances 9 / 9 (G, 1, 2, 3, 4, 5, 6, 7, 8)• Travel height 28.4 m • Pit depth 1600 mm , • Headroom 6300 mm • Shaft dimensions W x D 2070 mm x 1500 mm ,• Machine room Machine room less , • Car dimensions W x D x H 1300 mm x 1100 mm x 2139 mm • Clear car height HKC 2100 mm • Car Door size W x H 800 mm x 2000 mm , • Car Door Type Door center opening, 2 panels , • Shaft Wall Concrete • Building tolerance -25 mm/ +25 mm • Landing door fire protection classification EN 81-58 E120 [ Two hours fire rated ]• Counterweight location On the left side • Car access sides 2 • Main stop 1 • Door drive Fermator Compact • Drive and control Full Collective control - Simplex • Controller position In the right door jamb (LDU)• Controller location Landing at floor 8 on side 1• Drive Power 5.5 kW • Main connection TN-S (3L+PE+N) • Main power supply 415 V 50 Hz • Light power supply 230 V • Number of trips per hour 120 • Installation method Scaffoldless with hoisting device • Maintenance period 12 months • Inverter type VAF0xx REGEN • Machine Type Permanent Magnet (PM) • Communication Options Selected Intercom TAI 1; 3 ways • Remote Monitoring • Alarm by horn in hoistway • Control options Selected Parallel operated doors • Automatic return to main floor • Auto.door closing final time • Position indicator car 1 • Travel direction indicator car • Auto. Rescue Device (ARD) • Fire emergency switch • Car Front Finish Stainless steel AISI441 hairline • Front cathedral • Car lighting LED • Car operating panel faceplate finish Glass • Car Operating panel display type Standard resolution matrix • Button_Description Touch sensitive glass buttons Glass • Car door sill Aluminium • Landing door frame dimensions 60 mm x 60 mm • Landing door sill finish Aluminium sill • Landing operating panel position In the wall. • Landing operating panel installation Surface vertical in wall • Landing operating panel faceplate finish Glass • Position indicator Yes</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
376	<p><b>Comprehensive Maintenance : 8 Passenger LIFT- 2 :</b> Comprehensive maintenance charges with full responsibility of carrying out repair and supply of required original spare parts to keep the elevator in fully operational condition for a period of 5 years, after expiry of 1 year free servicing and warranty period both the lifts. (All parts Mechanical/ Electrical &amp; Electronics items including if any additional Manpower/Labour charge/Third party charge etc.)</p> <p><b>Parts covered under Comprehensive :</b> (Diamond) contract</p> <ul style="list-style-type: none"> <li>• Main Motor • Machine Unit, Sheave &amp; Main wire ropes, STM • Machine / Brake unit parts • Speed Governor, Gov Rope • Controller spares- Contactors, Terminal blocks, interconnecting wires, Prints. • V.F Drive unit (Invertor) • Automatic Rescue Device (where provided) • Car &amp; Landing door Liners, contacts, switches, air cords • Door operator motor, drive belts, coupler unit etc • Door safety sensors • Car &amp; Landing call registration Buttons, Floor indicators, Alarm unit • Load weighing device</li> </ul> <p><b>Inspection and Preventative Maintenance</b></p> <p>While observing IS14665, 14671, 15785:2007 &amp; relevant applicable state rules performs on the elevator installation(s) regular inspection and preventive maintenance. This comprises:</p> <ul style="list-style-type: none"> <li>- functional checking and adjustment of the drive unit, means of suspension, gearbox, brakes,traction sheave and drum, ropes, deflector sheave, hoistway doors, and guiderails of the elevator installation(s);</li> <li>- greasing the aforementioned subassemblies to the extent appropriate for the use made of the elevator installation(s);</li> <li>- checking and adjustment of the travel properties of the elevator installation(s), especially of their stopping accuracy;</li> <li>- visual and functional check of the switching, control, monitoring, and other safety equipment, and of the display and lighting equipment;</li> <li>- checking of the elevator installation(s) for functioning and damage;</li> <li>- checking the oil level of the drive unit;- to the extent required to preserve their functioning, cleaning the aforementioned subassemblies of the elevator installation(s) of dirt originating within the installation;</li> <li>- cleaning the machine room, car roof, and dry hoistway pit of dirt originating within the installation. Lubricating of guide rails and wire ropes will be carried out by Housekeeping team. 6 Regular visits will be done in each AMC contract</li> </ul> <p><b>First Year : 1 Year free servicing &amp; Warranty period)</b></p> <p><b>Comprehensive Maintenance : 8 Passenger LIFT- 2 : Second Year</b></p>	1.00	Job	0.00	0.00
377	Comprehensive Maintenance : 8 Passenger LIFT- 2 : Third Year	1.00	Job	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
378	Comprehensive Maintenance : 8 Passenger LIFT- 2 : Fourth Year	1.00	Job	0.00	0.00
379	Comprehensive Maintenance : 8 Passenger LIFT- 2 : Fifth Year	1.00	Job	0.00	0.00
380	<p><b>Passenger LIFT- 3 : Schindler , Otis ,ThyssenKrupp Elevator India @10passengers : Machine room less</b>  Supply, Installation, Testing, &amp; Commissioning of Passenger lift as per approved make ,shop drawing &amp; sample by Architect / Client . work complete including all type of civil work , scaffolding , loading , unloading , transporation , fittings, fixtures , all type of safety measures , at all floor, all levels etc. complete as per shop drawings and specifications. sample mock &amp; Shop drawing shall be approved from Architect/ Client.  No extra charges will be paid for any civil works, scaffolding required for installation of lifts works. The bidder shall carry out all civil work related to installation of lift as per the drawings and as per actual site conditions. work comprises with Lift pit , exising slab cutting as per white wash in lift shaft, scaffolding , grouting , work for all above work , with safety precautions as per instruction / satisfaction of Client / Architect. <b>The intending bidder should visit the site prior to the bidding submission.Rate shall be quoted only after by initial site inspection further no discrepancy will be allowed for whatsoever reason.</b>  <b>As per attached technical specification data sheet in tender documents .</b>  • Capacity / No. of Passengers 680 kg / 10 Passengers , • Speed 1.5 m/s , • Number of Stops / Entrances 8 / 8( G, 1, 2, 3, 4, 5, 6, 7), • Travel height 31.95 m , • Pit depth 1600 mm , • Headroom 6300 mm,• Shaft dimensions W x D 1650 mm x 1750 mm , • Car dimensions W x D x H 1200 mm x 1400 mm x 2139 mm,• Clear car height HKC 2100 mm , • Car Door size W x H 800 mm x 2000 mm , • Car Door Type Door left opening, 2 panels , • Shaft Wall Concrete , • Building tolerance -40 mm/ +40 mm , • Landing door fire protection classification EN 81-58 E120 [Two hours fire rated], • Counterweight location On the left side, • Car access sides 1 • Main stop 2 • Door drive Fermator Compact, • Drive and control Full Collective control - Simplex, • Controller position In the right door jamb (LDU) , • Controller location Landing at floor 10 on side 1• Drive Power 6.9 kW • Main connection TN-S (3L+PE+N) , • Main power supply 415 V 50 Hz , • Light power supply 230 V , • Number of trips per hour 120, • Installation method Scaffoldless with hoisting device • Maintenance period 12 months• Inverter type VAF0xx REGEN• Machine Type Permanent Magnet (PM) • Communication Options Selected Intercom TAI 1; 3 ways • Remote Monitoring • Alarm by horn in hoistway• Control options Selected Automatic return to main floor • Door pre-opening • Auto.door closing final time • Position indicator car 1  • Travel direction indicator car • Auto. Rescue Device (ARD) • Fire emergency switch • Car Front Finish Stainless steel AISI441 hairline• Front cathedral • Car lighting LED • Car operating panel faceplate finish Glass • Car Operating panel display type Standard resolution matrix• Button_Description Touch sensitive glass buttonsGlass • Car door sill Aluminium • Max decoration weight allowance 89 kg • Landing door frame dimensions 60 mm x 60 mm • Landing door sill finish Aluminium sill • Landing operating panel position In the wall. • Landing operating panel installation Surface vertical in wall • Landing operating panel faceplate finish Glass • Position indicator : Yes</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
381	<p><b>Comprehensive Maintenance : 10 Passenger LIFT- 3 :</b> Comprehensive maintenance charges with full responsibility of carrying out repair and supply of required original spare parts to keep the elevator in fully operational condition for a period of 5 years, after expiry of 1 year free servicing and warranty period both the lifts. (All parts Mechanical/ Electrical &amp; Electronics items including if any additional Manpower/Labour charge/Third party charge etc.)</p> <p><b>Parts covered under Comprehensive : (Diamond) contract</b></p> <ul style="list-style-type: none"> <li>• Main Motor • Machine Unit, Sheave &amp; Main wire ropes, STM • Machine / Brake unit parts • Speed Governor, Gov Rope • Controller spares- Contactors, Terminal blocks, interconnecting wires, Prints. • V.F Drive unit (Invertor) • Automatic Rescue Device (where provided) • Car &amp; Landing door Liners, contacts, switches, air cords • Door operator motor, drive belts, coupler unit etc • Door safety sensors • Car &amp; Landing call registration Buttons, Floor indicators, Alarm unit • Load weighing device</li> </ul> <p>Inspection and Preventative Maintenance</p> <p><b>While observing IS14665, 14671, 15785:2007 &amp; relevant applicable state rules performs on the elevator installation(s) regular inspection and preventive maintenance. This comprises:</b></p> <ul style="list-style-type: none"> <li>- functional checking and adjustment of the drive unit, means of suspension, gearbox, brakes,traction sheave and drum, ropes, deflector sheave, hoistway doors, and guiderails of the elevator installation(s);</li> <li>- greasing the aforementioned subassemblies to the extent appropriate for the use made of the elevator installation(s);</li> <li>- checking and adjustment of the travel properties of the elevator installation(s), especially of their stopping accuracy;</li> <li>- visual and functional check of the switching, control, monitoring, and other safety equipment, and of the display and lighting equipment;</li> <li>- checking of the elevator installation(s) for functioning and damage;</li> <li>- checking the oil level of the drive unit;- to the extent required to preserve their functioning, cleaning the aforementioned subassemblies of the elevator installation(s) of dirt originating within the installation;</li> <li>- cleaning the machine room, car roof, and dry hoistway pit of dirt originating within the installation. Lubricating of guide rails and wire ropes will be carried out by Housekeeping team. 6 Regular visits will be done in each AMC contract</li> </ul> <p><b>First Year : 1 Year free servicing &amp; Warranty period)</b></p> <p><b>Comprehensive Maintenance : 10 Passenger LIFT- 3 : Second Year</b></p>	1.00	Job	0.00	0.00
382	<b>Comprehensive Maintenance : 10 Passenger LIFT- 3 : Third Year</b>	1.00	Job	0.00	0.00
383	<b>Comprehensive Maintenance : 10 Passenger LIFT- 3 : Fourth Year</b>	1.00	Job	0.00	0.00
384	<b>Comprehensive Maintenance : 10 Passenger LIFT- 3 : Fifth Year</b>	1.00	Job	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
385	<b>Lift Shaft Tile cladding</b> : Providing and laying Matt finish Vitrified tiles in dado using minimum 10 mm thick tiles as per approved make list by architect /client. fixed in dado on 10 mm thick Cement plaster 1:3 (1 cement: 3 coarse sand) All surfaces must be dimensionally stable according to level, cured, undamaged, compact,rigid,resistant, dry and free from any debonding agents tiles fixed by approved tile adhesive and all application shall be done under instruction of manufacturer guideline and specification , and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction all complete as per approved sample by Architect, drawings and instruction of EIC. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift , work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (B) Tile size: 600 mmX 1200 mm, Basic rate of tile is Rs. 60/Sqft	42.00	Sq.mt	0.00	0.00
<b>Total Amount</b>					<b>0.00</b>
<b>I</b>	<b>Part-9 ( Rate Only Item)</b>				
386	Providing and laying controlled cement concrete M.250 and curing complete including finishing smooth with, curing, safety measures etc. complete including the cost of form work but excluding the cost of reinforcement. including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. in (D) Columns, Pillars posts and struts etc.	R/o	Cu.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
387	<p><b>Artificial Stone Flooring</b> : Providing &amp; laying approved quality 20 mm thick Artificial stone flooring of approved shade, in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Artificial stone is Rs. 200/ Sqft.</p>	R/o	Sq.mt	0.00	0.00
388	<p><b>Italian Marble Stone Flooring</b> : Providing and laying machine cut, mirror polished 18 mm thick Italian Marble stone flooring laid in required pattern in linear portion of the building all complete as per architectural drawings, with 18 mm thick stone slab laid over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with white cement slurry @ 4.4 kg/sqm including pointing with white cement slurry admixed with pigment to match the marble shade including rubbing, curing and polishing etc. All complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Granite stone is Rs. 420/ Sqft.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
389	<b>Granite Stone Flooring</b> : Providing & laying approved quality 18 mm thick Granite stone flooring of approved shade, in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Granite stone is Rs. 150/ Sqft.	R/o	Sq.mt	0.00	0.00
390	<b>Double Leaf Flush Door finish with veneer &amp; Glass view panel</b> : Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 4 mm thick veneer with matt finish monocoat polish as approved, wooden frame with matt finish monocoat polish with chamfering, 8 mm toughened Glass view panel size 2050 x 750 mm, Hardware fittings like concealed door closer or floor spring, Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, bending, , safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Basic Rate of teak veneer - 120/Sqft.	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
391	<b>Single Leaf Flush Door finish with veneer:</b> Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 4 mm thick veneer with matt finish monocoat polish as approved, wooden frame with matt finish monocoat polish, Hardware fittings like door closer, Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. Basic Rate of teak veneer - 120/Sqft.	R/o	Sq.mt	0.00	0.00
392	<b>S. S. Railing : Vetroline 11T3 (M) Handrail Round 50mm</b> Providing and fixing 1050mm high SS Railing (304 grade) system comprising 50mm dia. and 16 guage (1.6mm) Stainless steel pipe top handrail (SS 304 - Matt Finish), 35mm dia. and 16 guage (1.6mm) Stainless steel pipe of baluster and 12mm dia. Stainless steel inclined/ horizontal intermediate pipe (SS 304 - Matt Finish) placed at 100mm c/c distance and as per site requirement. Railing fixed on floor with 120x50x10mm base plate. whenever required, joints to be filled with bushings for extra strength. Rates should be inclusive of welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, including fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the side of waist slab/wall with suitable arrangement as per approval of Engineer/ Architect. Work shall complete includes all type of tools, tackles, all level & Height, labour, safety measures, mock sample etc complete as per the detailed drawing and instruction of EIC. Note :Handrail Length will be measured from Starting to End Location.	R/o	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
393	<p><b>Full Height Partition Gypsum Partition (60min. fire rating)</b> : 100mm thick Gypserra™ stud partition which includes inner layer of tapered edge 12.5mm thick Gypboard® Plain (conforming to IS 2095 Part 1:2011, Certified board) of size 1219x2438mm and outer layer of tapered edge 12.5mm thick Gyproc® Fireline board of size 1219x2438mm is screw fixed to C-stud.48x0.5mm Gypserra™ C-stud {Material-IS 513, Y/S-300Mpa, Finish - AZ150 (IS 15961)} placed at 610mm c/c in 50x0.5mm Gypserra™ {Material-IS 513,Y/S-300Mpa, Finish - AZ150 (IS 15961)} floor and ceiling channel.Floor &amp; Ceiling channel is anchored to the floor &amp; True ceiling using Gyproc® Rawl plug Ø8x45mm {Material-IS 513 CR1 grade, Zinc coating, Pull Out Load-6.8kN for M30 concrete grade} /Hilti X-GN20MX anchor fasteners at 600mm c/c in centerline manner.Floor channel to be wrapped with 70µ Self Adhesive LDPE moisture barrier film to further improve corrosion resistance performance. 12.5mm thick Gypboard® Plain board strip of 50mm width is placed between ceiling channel and RCC ceiling slab when deflection is more than 10mm &amp; fire rating is more than 30min. A Gypserra™ noggin channel {Material-IS 513,Y/S-300 Mpa, Finish - AZ150 (IS 15961)} of 50x0.5mm width has to be provided at the horizontal joints of the two boards. First layer of Gyproc® boards to be screw fixed with Gyproc® drywall screws of 25mm at minimum spacing of 600mm at centre and 600mm at periphery. Second layer to be screw fixed Gyproc® drywall screws of 35mm at minimum spacing of 300mm at centre and 300mm at periphery. 50mm Glass wool slab of density 20kg/m³ shall be placed in metal framework. Glass wool holding clip should be used to hold Glass wool slab in its position. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Pro-Fill Jointing compound, (Conforms to ASTM C475), Gyproc® Joint Paper tape or fiber tape. The junction of the partition with masonry &amp; all penetration through the partition has to be treated with Hilti/Pyroplex fire and acoustic sealant. All other detailing and specifications to be followed as per approved drawing of Gyproc.Note: Applicator need 60min. fire rating certificates from Gyproc.Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required &amp; For door frame fixing, storages, shelves, paneling etc extra Wooden members to be used shall be of CP teak wood only. Including skirting /MDF board/wooden skirting cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. including ply base for fixing of TV or Overhead storage wherever required, The rates are also inclusive of necessary scaffolding, tools, tackles,, safety measures , Internal partial support (between two sturd) at 7' height.The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. All exposed corner shall be covered with perforated angle as per manufacturer's specifications or as directed by EIC.Partition ht will be measured from finish floor to false ceiling level only.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
394	<p><b>Acoustic Ceiling</b> : Ecophon ADVANTAGE™ E Tech with micro look edge and 15 mm thickness ,easily demountable tile , visible surface of each tile is 7 mm below the grid, Option of weekly dusting, vacuum cleaning, manufactured from High density glass wool , visible surface is a batch painted glass tissue in white, back of the tile covered with glass tissue.</p> <p>83% light reflectance. Tiles classified under sound absorption class A with "alpha w " value of 0.95 at minimum 200mm o.d.s. Sound absorption test results measured according to EN ISO 354 and classification according to EN ISO 11654 . Tiles should have white colour " White 500 " nearest NCS colour sample S 0500 - N with . Tiles withstand a permanent ambient RH up to 95% at 30 degree C without sagging , warping and delaminating ( EN 13964). Certified by the Indoor Climate labeling , emission class M1 for building materials, French VOC A and recommended by Swedish Asthma and Allergy Association. Product Certified under GRIHA council of India for Green Ratings . Fully recyclable . The glass wool core of the tiles is tested and classified as non combustible according to EN ISO 1182 with reaction to fire classification class A2 s1 d0 according to EN 13501 - 1 - European Standard. Tiles should have a recycled content of more than 70% Systems are classified as fire protective covering according to NT FIRE 003. Environmental Product declaration (EPD) acc to international ISO 14025 &amp; EN 15804 series of standards. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price. No separate charges for cutting / providing opening will be paid. Joints between the two gypsum board, (Board placed staggered) gypsum board and wall will have suitable tape and finishes with plaster of paris so as to have crack free joints. The item includes providing and fixing trap door of size 600 X 1200 mm as per approved sample of Ceiling panels comprise of a powder-coated beaded steel frame with gypsum / plywood board door. Each panel features a push-latch closing mechanism with door retaining safety cable &amp; hook.Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing, etc. complete work.Work complete including all type of tools, tackles, finishing etc complete as per approved sample &amp; instruction of Architect/Client.sample mock shall be approved from Architect/Client.</p>	R/o	Sqmt	0.00	0.00
395	<p><b>Wooden ceiling finish with Laminate</b> :</p> <p>" -----Do-----" as per above specification for complete work. Only finish with laminate instead of veneer. Equivalent to VNR series laminate.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
396	<p><b>Wooden solid Partition finished with Both side VNR Laminate:</b>            Providing &amp; fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work on both side finish with 1mm thick Laminate. The frame work shall be made from square hollow aluminium section size of 50x50x1.5 mm &amp; 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c &amp; horizontal 600 mm c/c horizontally.</p> <p>All ply/wooden shall be treated with anti- termite treatment . Both side finish with VNR Laminate. Rates shall also be inclusive of cost of making cut outs/ openings for MEP services &amp; providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall &amp; board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. work complete including all type of material, fittings, fixtures, Finish, loading, unloading, safety measures, transportation, all leads, accessories, groove, PVC edge banding, adhesive ,tape, headless nails, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC. only the clear elevation area shall be measured and paid. sample mock shall be approved from Architect/Client. Equivalent to VNR series laminate.</p>	R/o	Sq.mt	0.00	0.00
397	<p><b>Wooden solid Partition finished with one side Veneer finish and one side laminate: :</b>            " -----Do -----" as per above item specification for complete work . using 4 mm thick Veneer &amp; matt finish monocoat polish instead of laminate for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Equivalent to VNR Series Laminate. Equivalent to VNR series laminate.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
398	<p><b>Wooden solid Partition finished with Both side VNR Laminate: (3' ht Wooden + 1'-0" glass)</b> Providing &amp; fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work on both side finish with 1mm thick Laminate. The frame work shall be made from square hollow aluminium section size of 50x50x1.5 mm &amp; 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c &amp; horizontal 600 mm c/c horizontally.</p> <p>All ply/wooden shall be treated with anti- termite treatment . Both side finish with VNR Laminate. Glass shall be Lacquered glass as per selection by Architect / EIC. Rates shall also be inclusive of cost of making cut outs/ openings for MEP services &amp; providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall &amp; board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. work complete including all type of material, fittings, fixtures, Finish, loading, unloading, safety measures, transportation, all leads, accessories, groove, PVC edge banding, adhesive ,tape, headless nails, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications &amp; instruction of Client/EIC. only the clear elevation area shall be measured and paid. sample mock shall be approved from Architect/Client. Equivalent to VNR series laminate.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
399	<p><b>Single Leaf Glass Door:</b>            Supply &amp; Installation of Modular Aluminium Glass door frame of Kubik or equivalent make 45mm System, Using KOPS 001 &amp; KOPS DF 103 ( 45mm x 25mm) for Glass door frame            Doorframe Dimension – 45mm x 25mm.            Finish – SILVER finish / Powder coating as per approved sample by Architect            10mm thk. clear toughened Glass            KUBIK Glass Hinge , HAFELE Open Door closer with saddle plate , KUBIK Mortise lock with handle , KUBIK Door stoper etc complete            Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights , necessary frame work,Scaffolding , safety measures etc complete as per detailed drawings ,specifications &amp; instruction of Client/EIC.</p>	R/o	Sq.mt	0.00	0.00
400	<p><b>Alabaster panelling:</b>            " -----Do -----" as per above item specification for complete work . Using 6/8 mm thick Alabaster instead of veneer for panelling work. The rate shall be for all floors, at all heights, all shapes including all costs. Basic rate of Alabaster is Rs. 600/Sqft</p>	R/o	Sq.mt	0.00	0.00
401	<p><b>Black out curtain:</b>            Providing and fixing Blackout curtain/blinds as per approved make as per suggested shade &amp; spring drive system with steel ball chain/one touch with speed control action roller blind with end brackets with head rail, components, bottom bar.            Construction: 100 % Polyster, Coating: Blackout 3 pass foam coating            Thickness : 0.60 mm Fabric value: 390 Gsm , Fabric to be as per approved sample. All the work complete as per the detailed drawing, mockup sample and instruction of Architect/EIC.All complete as per approval of designer. The mode of Measurement: The size of the blind will be measured from end to end bracket (Left to Right bracket) height will be measured from top of the pelmet to sill bottom level and clear opening size only there will be not extra payment towered overlapping &amp; mockup sample approved by the Architect/ EIC.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
402	<p><b>Motorised Curtain : NANTUCKET - N23 (summer linen )AC POWER VIEW :BLACK REMOTE&amp;WHITE PABBLE</b></p> <p><b>System Specification :</b> Supply &amp; Fixing of of Nantucket Window Shadings from Hunter Douglas in 3" vane size having head rail and bottom rail made of aluminum alloy extruded profile, powder coated and provided in standard natural white color. The rolling tube should make up of aluminum alloy from extruded profile of Ø34 mm. The head rail dimensions should be in the range of: H 58 mm x 72 mm or 62 mm x 81 mm for the larger head rail. The cassette should conceal the working mechanism rotary-clutch that raises lowers and tilts the shade contains and protects shading fabric when fully raised. All plastic parts are in white color. Operation options: endless cord loop. Installation to be done by quick release brackets (wall or ceiling) Fabric Specification (Room Darkening-N23)</p> <p>The fabric is anti static polyester light darkening vanes which have facings between 2 sheers layers (50 mm wide) to reduce glare. Sheer layers made of white 100% knit polyester &amp; the selection of colors, textures and opacities from the Hunter Douglas® collection as specified by the architect. The shading to be operated by Easy rise mechanism with a continuous cord loop operating option. The FABRIC shall be constructed from spun-bonded 100% polyester fiber, having Green guard certified, trated with soil &amp; dust repellent require minimum regular interval cleaning.</p> <p>The rate shall be for complete item inclusive of providing &amp; fixing, all material, all motorised mechanism , labour, wastages, necessary tools &amp; tackles, hardware/accessories etc for all floors, all heights, all levels and all places within campus. Work completed as per approved sample by Architect/Client.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
403	<p><b>Waiting area Table: 900 x 900 x 400 mm</b>            Center table : 25 mm thick Solid wooden top with matt finish monocoat polish.            Vertical support: solid wooden Leg with matt finish monocoat polish with busher.            Work complete including Providing &amp; fixing , all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	R/o	Nos	0.00	0.00
404	<p><b>Waiting Lounge area Corner table : 450 x 450x 400 mm</b>            " -----Do-----" as per above specification for complete work.</p>	R/o	Nos	0.00	0.00
405	<p><b>One Seater : 900(L) x 870 mm (B) x 800 mm (H) comprising up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density &amp; back shall be 32 density foam &amp; finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external &amp; internal exposed woodwork to be finished in PU semi gloss finish polish. .The work shall be done as per drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt</b></p>	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
406	<p><b>Three seater Sofa: 2100 (L) x 870 mm (B) x 800 mm (H)</b> comprising of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density &amp; back shall be 32 density foam &amp; finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC.            Leg : Solidwood            All external &amp; internal exposed woodwork to be finished in PU semi gloss finish polish.            The work shall be done as per the drawing, specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools &amp; tackles, approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 1000 Rmt</p>	R/o	Nos	0.00	0.00
407	<p>Chair Type- 1A - Model equivalent make - HOF MAR-1003 High Back :</p> <ul style="list-style-type: none"> <li>* Chair in Moulded Ply with Head Rest.</li> <li>* Double Cladding.</li> <li>* High Density PU Foam in Seat &amp; Back.</li> <li>* Chrome Arms &amp; Cushion on it.</li> <li>* Multi Tilt Mechanism.</li> <li>* Chrome Base &amp; Gas Lift.</li> </ul> <p>Work complete as per the approved sample &amp; instruction of EIC. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.</p>	R/o	Nos	0.00	0.00
408	<p><b>Mango wood flooring</b> : Providing &amp; Fixing chemically treated Mango wood flooring above fabrication work .work including all type of fittings , fixing , accessories , polish, all type of tools, tackles, all labour, scaffolding, all type of materials, transportation, cleaning, all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	R/o	Cumt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
409	Artificial Planter/ indoor plant with Fibre finish pot as per approved sample. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	NOS	0.00	0.00
410	Natural plants with potting mix as approved: fycus lyarata, travellers palme, elephant ear, pichardia grandis or similar plants Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	NOS	0.00	0.00
411	Readymade fibre finish pots of size 300mm (12") dia height with bottom tray as per approved sample. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	NOS	0.00	0.00
412	Removing/chipping and cleaning of existing concrete carefully by low impact high frequency hammer without damaging the existing concrete or by control sand blasting including cleaning the surface by air jet etc. complete as per direction and satisfaction of Engineer-in-charge (for payment area of R.C.C member before chipping/ removing loose concrete will be measured).For any thickness of RCC members. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Cu.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
413	Applying two coats of alkaline rust converting primer of approved quality and make conforming to ASTM-B-117 (Cleaning existing reinforcement with wire/rotary wire brush, making the surfaces free from loose material, dirt etc. complete) on the rebars, including cleaning the reinforcement wire brushing to remove loose rust spalls, As per the recommendation of manufacturer complete as per direction of Engineer-in-charge. for Payment exposed length of reinforcement will be measured (Alkaline rust converting primer - REEBAKLENS RR of FOSROC / Sika Rustoff 100 of Sika / BASF/ Pidilite/ Krishna Conchem).Bars upto 12 mm Diameter. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Rmt	0.00	0.00
414	" -----Do-----as per above specification for complete work . Bars above 12mm diameter	R/o	Rmt	0.00	0.00
415	Providing and laying anticorrosive Treatment of Reinforcement by any approved make rebar corrosion protection system to existing reinforcement (The application shall be by brush). Process is to be complete as per the recommendation of manufacturer and direction of Engineer-in-charge. for payment exposed length of reinforcement will be measured. (Product - NITAZINC PRIMER of FOSROC /Fiazinc® R of Sika/ MasterEmaco P 130 of BASF or equivalent of pidilite & Krishna Conchem).Bars upto 12mm Diameter. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Rmt	0.00	0.00
416	" -----Do-----as per above specification for complete work . Bars above 12mm diameter	R/o	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
417	Makeing 'V' groove of 5 mm wide and 5mm deep over crack line by electrically operated angle grinder with diamond concrete saw blade and cleaning it by air blower as directed by Engineer-in-charge Sealing of exposed 'V' groove of 5mm deep and 5mm wide with solvent-free, moisture tolerant, thixotropic, two part structural adhesive and epoxy repair mortar cum surface levelling mortar the compressive strength of the epoxy repair mortar shall be $\geq 60$ N/mm <sup>2</sup> ( 14 Days) and Bond strength $\geq 10$ N/mm <sup>2</sup> ( 7 Days). (Product - NITOMORTAR S OF FOSROC/ Sikadur®- 31 of Sika/ MasterBrace 2200 BASF or equivalent of Pidilite or Krishna Conchem). Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Rmt	0.00	0.00
418	Driling and fixing NRV nozzles in RC members, including (fixing material : Renderoc Plug of Fosroc / Sikadur-31 of Sika/ MasterBrace 2200 of BASF or equivalent of Pidilite & Krishna Conchem). Drilling Holes: Drilling 12mm dia, 50 to 75 mm deep holes in structural members of the intervals of 350 mm in staggered manner or as directed by the consultants in RC structural elements. Cleaning of holes: Clean the holes by air blower prior to fixing nozzles. Cuttting of Nozzles: Cut the nozzles by chisel after completion of grouting without damaging structural elements: all type of structure Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Each	0.00	0.00
419	Supply and apply a polymer modified cementious boand coat. Ratio polymer : water : cement ( 1 Polymer: 4 Water: 6 Cement) by weight. Apply the patching mortar when the bond coat is tacky (Nito Bond SBR Latex of Fosroc/ Sika® latex of Sika/ MasterEmaco SBR2 of BASF or equivalent of Pidilite or Krishna Conchem) Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
420	Injecting/Grouting shrinkage free low viscosity epoxy resin grout in structural cracks, wherever required by pressure and using mechanized injector gun with accessories till nozzles refused to accept the grout. Epoxy grout material should be conforming to ASTM-881-87 type I, grade I, class B & C and compressive strength of the material shall be $\geq 55$ Mpa, (7 Days), Tensile strength $\geq 20$ Mpa (14 Days) & Bond strength 10 Mpa (14 Days). (Low Viscous epoxy grout : conbextra EP10 of Fosroc/ Sikadur <sup>®</sup> -52 of Sika/ MasterInject 1315 of BASF or equivalent of Pidilite & Krishna Conchem). Mixing of material : Mixing material components in required quantities as per manufacture's instruction. Grouting : Fill the grouting gun with low viscosity epoxy resin. Maintain desired pressure in the gun by air compressor: maintain the required pressure at exit. Grout the material through prefixed nozzles in structural elements till its refusal, seal the nozzles with epoxy putty after the refusal, monitor leakages through other nozzles while grouting and seal them as per the requirement, repeat the process for all the nozzles. complete the operation within pot life of the material. Cleaning the gun and accessories: Clean the gun and accessories (valves, pipes and other fixture) with thinner after the operation to avoid jamming of the gun. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Kg	0.00	0.00
421	Colour lamination: -----do ----- as per above specification work complete. 6mm clear glass (T) + 1.52 FG glass Vivid PVB (2 film color and 2 clear films of pvb) + 6mm clear glass (T)	R/o	Sqm	0.00	0.00
422	Supplying and erecting approved make oscillating type bracket fan A.C. 230V. 50cy/s 400/450 mm sweep wall mounted with height adjustment and rotary tilting device complete with guard, flexible Core plug top complete erected with lead wires as directed.	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
423	Supply, Supervision during installation, testing & commissioning of Round ceiling recessed luminaire, the fixed Led down light made of aluminium injected body. Main optics in shiny anodised aluminium with a glass or plastic diffuser element, depending on the version. The LED modules installed on the LED Array versions have cutting-edge technology that permits a lower average temperature in the electronics. antiglare Powder coated white painted antiglare reflector, suitable size of heat sink to be integrated with in the fixture for better performance, system delivered lumen output should not be less than 1045 lumen, the power consumption should not be more than 13W-15W, Mac Adam step 2-3 LED, 50° beam angle with tolerance of ±10 degree, CRI ≥90, UGR ≤10-≤20, CCT 4000K, L80-B50-50000h@ Ta 25°C, remote LED DALI driver, complete product should be minimum IP54, the physical dimensions of the fixture should not be more than (Dia)80mm X (H)95mm., Luminaire Finish : Matt White Approved Make :ERCO, Flos, Castaldi, BEGA, Simes	R/o	Nos	0.00	0.00
424	Supply, Supervision during installation, testing & commissioning of Ceiling Recessed Rectangular shaped fixed linear Led Downlight, Housing made of aluminium profile, designed as heat sink, with connection cable L 500mm. Mounting frame: polymer, Trim Finish white (RAL9002) with black louver. Fixing springs for ceiling thicknesses of 1-40mm. Includes DALI control gear. with 0.1%-100% dimming range, 4-pole terminal block. LED module: high-power LEDs on metal-core PCB with 1.5 SDCM, CRI 82, L90/B10 ≤50000h, L90 ≤100000h, failure rate 0.1% ≤50000h, Cut-off angle 30 °. Protection Class II Weight 1.38kg. System wattage should not be more than 29W, Led 24W 3300 lumens, delivered 2603 lumens, Optics should not be more than 60 ° wide flood, 4000K, IP20, the physical dimension of the fixture should not be more than (L)390mm X (W)62mm X (H)100mm.Approved Make :ERCO, Flos, Castaldi, BEGA, Simes	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
425	"Supply Installation Testing Commissioning of Indoor deep Recessed Round COB downlight 27-30W Recess Mounted Round 36-40 DEGREE COB downlighter with below features 1. Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. . Round Version. 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80, High efficiency driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) recess mounted die cast Legend Approved makes : Philips,Havells, Wipro,Tisva	R/o	Nos	0.00	0.00
426	Supply, Supervision during installation, testing & commissioing of Ceiling Recessed adjustable led spotlight cum downlight, suitable for Interior lighting for embedded installation with high power LED technology light sources, in Dali versions. In an upper position it functions as a downlight, and in a lower position it functions as a swivelling projector. The optical body of the luminaire is manufactured in high pressure die-cast aluminium, finished in black or white powder paint. System wattage 18W, Led 1879 lumens, delivered 918 lumens, 4000K, IP20, CRI ≥90, UGR ≤10-≤20, CCT 4000K, L80-B50-50000h@ Ta 25°C, Dali dimmable drivers, 21 degree emission, Honecomb louver, Elliptical lens louver, flood lens louver included for desired application. Dimension Ceiling Recessed Dia : 98mm X Spot Snoot Dia : 57mm X H : below ceiling 115mm, above ceiling 156mm Approved Make :ERCO, Flos, Castaldi, BEGA, Simes	R/o	Nos	0.00	0.00
427	Supply Installation Testing Commissioning of Multipule lines of led strip with alumnnium profile for backlighting the STRECH CEILING stone with a dotless effect and complete even lighting Remote driver to be kept for maintatinance purpose Should be around 90w-120w per square meter Approved makes : Philips,Havells, Wipro,Tisva	R/o	Sq.mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
428	"Supplying, Installation, testing & erecting of 80-90w Indoor decorative Circular complete backlit type Lighting, Dia=1200 mm, H=70 mm Suspended profile with below features System wattage-80-90w, Luminous Flux of luminaire to be more than 90 lumens per watt, 4000 K, CRI >80, 230V, Direct Emission, Profile in high quality powder coated, Halogen free internal wiring, should have Prismatic Diffuser for Homogenous Light distribution. Protection Class I, IP 40, .Fixture should be available in 600mm dia. Body color shall be as per architects choice, manufacturer shall provide powder coated fine finish as per Architects selected RAL code. Fixture should be suspended using MS/SS/aluminium rod with height as per site requirement Ref : Geomet fullit 1200mm Approved makes : Philips,Havells, Wipro,Tisva	R/o	Nos	0.00	0.00
429	"Supply Installation Testing Commissioning of Chandelier light with below features Product with premium mitsubishi acrylic material Better ambience creation and illumination for the space Long life and highly durable product Premium aesthetics maintained for a long time Brilliant light effect. Gives a notion light getting emitted for curved acrylic edges Easy height adjustment Made from non-toxic materials Colour: Iron / Gold Power: 24 W, INTEGRAL LEDs, SMD 2835 Dimensions per hanging (Length X Width X Height): 500 mm x 500 mm x 15000 mm Ref : TISVA LIGHTING (USHA INTERNATIONAL LTD): SL24217K Approved makes : Philips,Havells, Wipro,Tisva	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
430	"Supplying, Installation, testing & erecting of Indoor Linear Lighting 34W-38w 1200MM Suspended profile with below features Extuded Aluminum alloy housing for better thermal conductivity. Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission or opiton of Lens Based profile for better task lighting. Option to be selected by Architect / Consultant Efficacy of Fixture 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. Ref: Philips make :suspended profile 4ft Approved makes : Philips,Havells, Wipro,Tisva	R/o	Nos	0.00	0.00
431	Supply Installation Testing Commisioning of Indoor recess mounted 17-20mm cut out (17x16mm profile light), Heavy aluminium Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination Anodised aluminium end caps firmly fixed on the aluminium extrusion Silver anodised finish for elegant look . Efficacy of Fixture >=100 Lumens/Watt suitable for self adhesive Strips with driver. Wattage should be 14-17w/m. Should have a dotless continuos effect. Should be operated using remote driver of 24V Dc kept at suitable locations for future maintainance. REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) Lume series Strip light LSX20Y145S4 Approved makes : Philips,Havells, Wipro,Tisva	R/o	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
432	<p>Supply Installation Testing Commissioning of Indoor cove mounted Heavy 18X18mm corner 45degree customized Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination</p> <p>Anodised aluminium end caps firmly fixed on the aluminium extrusion</p> <p>Silver anodised finish for elegant look . Efficacy of Fixture &gt;=100 Lumens/Watt suitable for self adhesive Strips with driver.</p> <p>Wattage should be 14-17w/m Should have a dotless continous effect. Should be operated using remote driver of 24V Dc kept at suitable locations for future maintainance.</p> <p>Quantity in metres</p> <p>REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) Lume series Strip light LSX20Y145S4</p> <p>Approved makes : Philips,Havells, Wipro,Tisva</p>	R/o	Mtr	0.00	0.00
433	<p>Supply Installation Testing Commissioning of decorative Glas two head Wall lamp light 10-15w with below features</p> <p>Colour : Matt Gold</p> <p>Dimmenssions: Height (in mm): 260, Width : (in mm): 120</p> <p>Wattage: 10-15w</p> <p>Output : 900-1300Lms</p> <p>Holder type: 2 X G9</p> <p>Fixture should be more the IP20 rated</p> <p>Ref : TISVA LIGHTING (USHA INTERNATIONAL LTD) :WG2020</p>	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
434	Supply Installation Testing Commissioning of 112w 16 head mitsubishi acrylic Chandelier light with below features Protection class: Class I IP Rating: IP20 Dimming: Non-dimmable / Non-tunable lamp include: Integral LEDs, SMD 2835 Crafted with premium Mitsubishi acrylic material Light gets emitted from the curved acrylic edges,Better ambience creation and illumination for the space Long life and highly durable luminaire,Premium aesthetics maintained for a long time Average Weight: 13.7 Kg Power: 112 W Dimensions (Diameter X Height): 1000 mm x 3000 mm Ref : TISVA LIGHTING (USHA INTERNATIONAL LTD): SL112162K	R/o	Nos	0.00	0.00
435	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) <b>Three phase 6 way</b> SS Double door for horizontal single phase outgoing	R/o	Ea	0.00	0.00
<b>Total Amount</b>					<b>0.00</b>
<b>J</b>	<b>Part-10 ( Rate Only item)</b>				
436	Providing & erecting 240 V <b>MCB double pole switch</b> for motor & inductive load <b>(C Curve)</b> having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (A) 6 to 32 Amp.	R/o	Ea	0.00	0.00
437	Providing & erecting 415V MCB <b>Four Pole Switch for Lighting Load (B curve)</b> having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (b)40 Amp. Cat.III	R/o	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
438	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables. B)4 core25 Sq. mm	R/o	Mtr	0.00	0.00
439	Providing & erecting weather proof, dust & vermin proof, floor mounted front operated indoor type cubical panel board having IP-64 protection made from 14 SWG thick CRC M.S. sheet for outer body & doors, 16 SWG thick CRC M.S.sheet for internal partitions with necessary supporting angles, flats including cutting, bending, drilling, welding, riveting with internal partitions & cable alley as per requirements & instruction of engineer-in-charge with erection of supplied switch gears, BUSBARS, with suitable size of inter connecting PVC copper wire / copper-aluminium strips, rubber grommets, rib, bakelite control fuses for measuring instruments, earth bus & earth bolts, foundation flange - bolts-base Plates, sufficient nos. of hinged doors, handles with locking arrangement and rubber gasket complete. The Panel shall be painted with epoxy powder coating. (The rates excludes the cost of switchgears, bus bars, inter connecting mains & Copper Aluminium strips, meters, Fuses etc. The dimension shall be measured excluding base beams) The panel shall be supplied with following approved manufacturers with following size. (A) The standard companies switch gear shall be used and only manufacturers at CPRI approved factory and shall be certified by that company whose switch gears are used after fabrication for beneficial use and having Logo on the Panel (ii) with 550 mm. Depth	R/o	SQMT	0.00	0.00
440	Supplying and erecting triple pole & neutral 440V/ 500V panel mounting <b>Aluminium Busbars</b> with four equal Nos. of bus having current density not more than 0.8 Amp. / sq.mm (Rated current / cross section area) duly wrapped with colour insulating tape for phase sequence of following current carrying capacity, erected with necessary bus bar supports /insulators, main cable socket to each busbar,erected in existing cubical panel with necessary connections. (C) Suitable for 300 Amp. Capacity	R/o	Ru Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
441	Supplying and erecting approved make panel mounting type Digital Voltmeter having 3 digits LED display, 0 to 750 AC Volts range erected on existing panel board with all connection, wiring etc .with manufacturers calibration certificate.	R/o	Each	0.00	0.00
442	Supplying and erecting approved make panel mounting type Digital Ammeter having 3 digits LED display, external CT operated, calibrated for 0 to 1000 Amps suitable to operate on 500 Volt AC , erected on existing panel board with all connection, wiring etc .with manufacturers calibration certificate.	R/o	Each	0.00	0.00
443	Supplying and erecting Ammeter / Voltmeter selector switch for 3 phase AC Supply 500 V on existing panel board with necessary connections.	R/o	Each	0.00	0.00
444	Providing & erecting L.T. Current Transformer with bar primary 50/5 to 1000/5 ratio 15 VA burden erected in existing CRCA box duly secured with insulating materials connected to the meter	R/o	Each	0.00	0.00
445	Supplying and erecting approved make set of indicator lamps of LED type lamp, lens cover, Bakelite holder complete erected with necessary connections.	R/o	Each	0.00	0.00
446	Providing , erecting , fabricating the M.S. structure as per requirement on site incorporating proper size of M.S. angles, flats, bars, channels, sections complete with cutting, welding, grinding & finishing duly painted with one coat of red oxide with erection on site as per direction of engineer in charge with necessary grouting, cementing, plastering & finishing complete.	R/o	Kg.	0.00	0.00
447	Supplying & erecting approved make Four Pole 415V change over switch interior for panel mounting with operating mechanism A.C.23 duty conforming to IS for (C)100-125A Cat-III	R/o	Each	0.00	0.00
448	Providing and erecting Approved make Four pole moulded case circuit breaker having breaking capacity ICU of 35 KA. and above at 415 V . having normal current rating 250A. with variable thermal & magnetic release suitable to work on A.C.supply 50 c/s. with all internal connections, spreader tinned copper & complete erected in existing 16 G.M.S. housing. ICS=100% of ICU only Cat III	R/o	Each	0.00	0.00
449	Providing and erecting Annealed bare Copper wire 8 to 16 SWG.	R/o	KG	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
450	Supplying under floor pregalvanised corrosion proof rectangular sheet steel cable trunking of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories, Junction Box, Joints as required and demanded by engineer-in-charge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Cat-III [13] 300mm x 38mm x 1.6 mm with Three Compartments	R/o	Mtr	0.00	0.00
451	SITC of CAT6 UTP 23AWG Solid: Per Meter	R/o	Mtr.	0.00	0.00
452	SITC of Fixed wall Mounting Bracket with Tilting Option	R/o	Nos	0.00	0.00
453	Artificial Planter/ indoor plant with Fibre finish pot as per approved sample. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	NOS	0.00	0.00
454	Natural plants with potting mix as approved: fycus lyarata, travellars palme, elephant ear, pichardia grandis or similar plants Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	NOS	0.00	0.00
455	Readymade fibre finish pots of size 300mm (12") dia height with bottom tray as per approved sample. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	NOS	0.00	0.00
<b>Total Amount</b>					<b>0.00</b>
<b>K</b>	<b>Part-11 (Buy Back item)</b>				



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
456	<p><b>Part-II: Buyback items:-</b>            Note: 1) The client reserves the right for hand over of any buy back items to bidder without assigning any reason thereof. The client reserves the right for any decision. 2) The Qty may vary for any buy back item as per actual site conditions.  <b>Break Out Area</b> : Granite top veneer finish Reception Table :            Size-@ 3600 x 800 x750</p>	1.00	Nos	0.00	0.00
457	<b>Break Out Area</b> : Half Height Wooden Storage :Size-@ 2860 x 500 x950	2.00	Nos	0.00	0.00
458	<b>Break Out Area</b> : Granite top veneer finish Table Size-@ 2100 x 900 x750	4.00	Nos	0.00	0.00
459	Banquet Hall : Sofa : 3 seater	1.00	Nos	0.00	0.00
460	Banquet Hall : Sofa : 2 seater	4.00	Nos	0.00	0.00
461	Banquet Hall : Center Table : 1200 x 750 mm Glass top & Wooden Finish leg	14.00	Unit	0.00	0.00
462	Banquet Hall : SS Top with wooden legs Table :1200 x 700 x 750 mm HT	5.00	Nos	0.00	0.00
463	Banquet Hall : Half Height Wooden Storage :2200 x 630 x 900 mm HT	5.00	Nos	0.00	0.00
464	Banquet Hall : Chair	3.00	Nos	0.00	0.00
465	Auditorium Chair :	160.00	Nos	0.00	0.00
466	Stage Chair :	7.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
467	Wooden center table : 750 x 750 x 450 mm HT : Laminate finish Table	3.00	Nos	0.00	0.00
468	Glass top with Wooden legs side table : 750 x 750x 450 mm HT : Glass top Wooden finish leg	6.00	Nos	0.00	0.00
469	Wooden Podium : Venner Finish : 750 x 750 x 1200 mm HT	1.00	Nos	0.00	0.00
470	Reception, Waiting Area & Foyer Area : Foyer -Dia-750 x 750 HT Veneer finish table * top stone finish	1.00	Nos	0.00	0.00
471	Reception Table-2700 x 900 x 750 HT Laminate finish	1.00	Nos	0.00	0.00
472	Reception Table Back Unit 2700 x 450 x 750 Ht : Laminate finish	1.00	Nos	0.00	0.00
473	Reception, Waiting Area & Foyer Area : Three seater sofa	4.00	Nos	0.00	0.00
474	Reception, Waiting Area & Foyer Area : Two seater sofa	2.00	Nos	0.00	0.00
475	Reception, Waiting Area & Foyer Area : Center Table : 900x900x450 mm HT Laminate finish table	4.00	Nos	0.00	0.00
476	All toilet block sanitary fittings like wash basin w.c. pan, Indian and Europeon type flushing tank, Urinal, all type of cock, accessories, basin counter etc. (Male & Female toilet)	2.00	Job	0.00	0.00
477	Tiled or stone floors, wall tiled / any type of cladding material	2200.00	Sq.mt	0.00	0.00
478	Existing All type of Door with frame all hardware's	36.00	Nos	0.00	0.00
479	Existing Glazing with frame work : Elevation facade & Atrium side	39.00	Sq.mt	0.00	0.00
480	Existing Electrical light fixtures, cables, trays etc	1.00	Job	0.00	0.00
481	Existing fabrication/ Steel structure / S.S. railing etc. work	6449.00	Kg	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
482	Existing Lift ( Passenger lift) : Lift lobby ( Basement to 8th floor) : OTIS make full collective duplex capsule passenger elevator of 1088 Kg capacity with rated speed 0.90 M/S ( Sr.No – H0071 & H0072 ) including 27 BP Machine with Wire rope,Outo doors Ms finish,Lift Car ,1) Guide rails 2) Counter weights 3) Safety governors 4) Ropes 5) All limit switches 6)All Landing doors with locking arrangements 7) Cabin door with locking arrangement 8) Cabin 9) Control panel-- 10) Drive's 11) limit switches 12) Buffer's 13)Electrical Cables 14) Old Shaft wiring's 15)All Brackets 16)Junction boxes 17)Lift motor with machine 18)Machine room Wiring all parts , accessories , fittings etc complete -Buy back rate of lift is inclusive of all labour, machinaries,tools, tackles , loading , unloading, transportation, shifting etc. complete to remove and shifting from site .	2.00	Nos	0.00	0.00
483	Existing Lift ( Passenger lift) : Wing A ( GF to 8th floor) : One nos. OTIS make passenger elevator of 408 Kg capacity with rated speed 1.0 M/S ( Sr.No – H0073 )including 27 BP Machine with Wire rope,Outo doors Ms finish,Lift Car ,1) Guide rails 2) Counter weights 3) Safety governors 4) Ropes 5) All limit switches 6)All Landing doors with locking arrangements 7) Cabin door with locking arrangement 8) Cabin 9) Control panel 10) Drive's 11) limit switches 12) Buffer's 13)Electrical Cables 14) Old Shaft wiring's 15)All Brackets 16)Junction boxes 17)Lift motor with machine 18)Machine room Wiring all parts , accessories , fittings etc complete --Buy back rate of lift is inclusive of all labour, machinaries,tools, tackles , loading , unloading, transportation, shifting etc. complete to remove and shifting from site .	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing B, Reception , Foyer , Entrance Porch , Central staircase ( BG to 8th floor) , Lift at GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

**PRICE BID**

Sr. No.	Item Description	QTY	Unit	Rate	Amount
484	Existing GI frame work in false ceiling / Partitions etc	21500.00	Kg	0.00	0.00
485	Existing GI pipe , M.S. Pipe , Cast iron any type of pipe etc with necessary fittings & fixtures	600.00	Kg	0.00	0.00
	<b>Total Amount</b>				<b>0.00</b>
Sr. no.	Summary Sheet				Amount
A	Sub Total : Part - 1				0.00
B	Sub Total : Part - 2				0.00
C	Sub Total : Part - 3				0.00
D	Sub Total : Part - 4				0.00
E	Sub Total : Part - 5				0.00
F	Sub Total : Part - 6				0.00
G	Sub Total : Part - 7				0.00
H	Sub Total : Part - 8				0.00
I	Sub Total : Part - 9 (Rate Only Item)				0.00
J	Sub Total : Part - 10 (Rate Only Item)				0.00
	<b>Total Amount (Rs.)</b>				<b>0.00</b>
K	Sub Total : Part -11 (Less Bay back Amount)				0.00
	<b>Grand Total Amount (Rs.)</b>				<b>0.00</b>

GST Extra as per Govt. Norms