

# GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED

**Name of work : New Construction Of Lease Boundary Pillars For Group of Bauxite Mines Gadhsisa,Ta:-  
Mandvi,Dist:-Kutch**

## PRICE BID

ITEM NO.	ITEM	QTY	Per	Rate	Amount
1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead. (D) Soft rock not requiring Blasting- Scope of work includes all required labour, tools, tackles , safety measures , mobilisation, de mobilisation etc. complete	87.45	cumt	0.00	0
2	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(E)--- Scope of work includes all required labour, tools, tackles , safety measures , mobilisation, de mobilisation etc. complete Hard Rock	58.30	cumt	0	0.00
3	Providing and laying controlled cement concrete M.200 exposed work with curing etc. complete including the cost of formwork but excluding the cost of reinforcement for R.C.C. work in (B) COLUMNS:(ii) Having cross-sectional area more than 0.08 Sq.M and upto 0.18 Sq.M---Scope of work includes all required materials, consumables, labour, tools, tackles , safety measures , mobilisation, de mobilisation etc. complete	192.00	cumt	0.00	0.00
4	Providing TMT Bar FE 415 reinforcement for R.C.C.work including bending, binding and placing in position complete .-Scope of work includes all required materials, consumables, labour, tools, tackles , safety measures , mobilisation, de mobilisation etc. complete	10394.00	kg	0	0
5	Applying priming coat over new wood and wood based surface after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting. (C) Ready mixed paint brushing priming for enamel-Scope of work includes all required materials, consumables, labour, tools, tackles , safety measures , mobilisation, de mobilisation etc. complete	2589.00	sqmt	0	0.00
6	Painting two coats ( excluding priming coat ) on new Sqm pillar based surface with enamel paint , interior to give an even shade including cleaning the surface of all dirt , dust and other foreign matter sand papering and stopping .-Scope of work includes all required materials, consumables, labour, tools, tackles , safety measures , mobilisation, de mobilisation etc. complete	2589.00	sqmt	0	0.00
7	Writing letter or figures on any surface with black japan paint (stops,comas, hyphens and the like not to be measured and paid for separately) (ii) Indian (Letters/Figures)	56100	per letter per cm/ht	0	0.00

8	Providing and laying cement concrete 1:4:8 (1- Cement :4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth-Scope of work includes all required materials, consumables, labour, tools, tackles , safety measures , mobilisation, de mobilisation etc. complete	65.00	cumt	0.00	0.00
9	Clearing and grubbing road land including uprootingrank vegetation grass bushes,shrubs,sapling and trees girth up to 300 mm removal of stumps of trees cutearlier and disposal of unserviceable materials(D) By mechanical means in area of thorny jungle - Scope of work includes all required labour, tools, tackles , safety measures , mobilisation, de mobilisation etc. complete	14.02	Hectare	0.00	0.00
				<b>Total</b>	