



**GUJARAT MINERAL DEVELOPMENT CORPORATION LTD.**  
(A Government of Gujarat Enterprise ),

Name of work:-Providing & Applying color work to different structures of mines and township at Lignite Project  
Mata No Madh, Tal.Nakhtrana , Dis- Kutch

**NOTE: The exterior and interior colour scheme and Shed will be as per GMDC's norms and brand will be of standard manufacturer like Asian , Dulux, Burger, Shalimar, British, Jonson & Nicholas etc.as per approved by EIC.**

**PRICE BID**

Sr No.	Description	Qty	Unit	Rate	Amount
1	Cutting out cracks of roof terrace to V- section , cleaning out, wetting , grouting with Cracksill material or cement and sand slurry 1:3 (1-cement 3-sand ) as directed by EIC , including all manpower, labor, tools, tackles, transportation,scaffolding/zulla, all lead and all height , safety measures etc as directed by EIC.	500	Rmt.	0	0
2	Removing Completely dry or oil bound distemper including putty or snowsem paint including putty by a washing and scraping and sand papering / Machine Scrapping the wall surface smooth including necessary repairs to scratches complete ready for new colorwork including all manpower, labor, tools, tackles, transportation,scaffolding/zulla, all lead and all height , safety measures etc as directed by EIC.	39938.5	Sq.mt.	0	0
3	Applying two coats of putty & two coats of primer of approved brand and manufacture on Scraped/Color Removed wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smoothincluding all manpower, labor, tools, tackles, transportation,scaffolding/zulla, all lead and all height , safety measures etc as directed by EIC.	17661.5	Smt.	0	0

Sr No.	Description	Qty	Unit	Rate	Amount
4	P &A suitable priming coat of distemper primer of approved brand and manufacture after thoroughly brushing the surface clean of all dust, dirt and other foreign Providing and applying two coats acrylic distemper of standard quality manufactured as per latest IS and approve brand like Asian , Nerolac, dulux & other equivalant etc. and of required shade of distemper surfaces to given an even brand and manufacture after thoroughly brushing the surface clean of all dust, dirt and other foreign matter with necessary scaffolding/Zulla , required manpower, tools , tackles, safety measure , transportation etc. complete as directed and specified as per instruction of EIC.	25716	Sq.mt.	0	0
5	Providing and finishing outside walls with Apex Ultima luxury exterior emulsion paint in 2 coats paints plus 2 coat primer with approved brand and manufacture to give an even shed of color of approved shade after scraping of existing water proof cement paint, thoroughly cleaning the walls by water and brushing to remove all dirt and remains of loose materials, up to all level above plinth complete ,Including cost of all type of tools, tackles, all labor, materials, transportation , cleaning at all floor at all level, lead and lift, performance waranty certificate , safety measures ,etc. work complete as per the detailed drawing, approved sample, specifications and instruction of EIC. Sample mock shall be approved by EIC.	22058	Smt.	0	0
6	Providing & applying two coats ( excluding priming coat) on previously painted wood and wood based surface with enamel paint to give an even shade of approved IS make and shade like Nerolac, Asian etc. as per instruction of engineer in charge after cleaning the surface to remove all dust, dirt and other foreign matter and including necessary scaffolding , Zula,all tools, tackles, labour, materials , all lead and height , safety measures etc. complete as directed and specified at all levels. <b>Note:</b> 1. Surface should be scrap and loose surface to be removed. (2) Rates are for all height of building and at all level.	6049	Sq.mt.	0	0
	Total				