

**GUJARAT MINERAL DEVELOPMENT CORPORATION LTD**

(A Government of Gujarat Enterprise)

Price Bid

**Works of (1) providing & fixing of main water supply pipeline from Overhead Tank to Colony Chamber valves & at Mines office Ambadungar,
(2) construction of new RCC road from officer colony main road to Guest house at Fluorspar project, Kadipani, Dist. Chhotaudepur.**

Item No.	Description of Item	Total Qty.	Unit	Rate	Amount
1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of EIC..(C) Hard Murrum	1929	CMT		
2	Filling available excavated earth (excluding rock) in trenches. plinth, sides of foundations etc. in layers not exceeding 20 cm. in depth consolidating each disposed layer by ramming and watering with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of EIC..	2196	CMT		
3	Collecting, carting and stracking of machine crushed black trap 40mm to 63mm size metal on road side with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of EIC..	88.65	CMT		
4	Collecting, carting and stracking of soft murrum/blindage on road side as directed with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of EIC..	30	CMT		
5	Spreading the stone aggregate for soiling and W.B.M including filling interstices forming the surface to required camber and gradient, Spreading of metal to be taken in two layers with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of EIC..	90	CMT		
6	Spreading blindage or road crust filling the gaps in metal levelling to camber and gradient with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of EIC. (I) murrum.	30	CMT		
7	Providing and laying cement concrete 1:4:8 (1 Cement: 4 sand: 8 machine crushed stone aggregate 40 mm nominal size) and curing complete excluding the cost of form work with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation etc complete as per instruction of EIC.. in : (A) Foundation and plinth	70	CMT		
8	Providing and laying controlled cement concrete M - 250 For a concrete pavement made by Trimix system and mixed with heavy duty floor handner at the rate of 4.00 Kg./Sq.M. including curing etc. completed over prepared sub base including providing and fixing centering of MS channels of required thickness as per required level slope, Grade and thickness of concrete road including leveling of thickness of concrete road including leveling of placed concrete with surface vibrators finishing surface with power floater and trowel light brooming on the surface including providing construction joint of 10 mm * 25 mm by using concrete cutter machine etc. complete as directed.	90	CMT		
9	Providing T.M.T. Fe-500 Steel reinforcement for RCC work including cutting, bending, binding and placing in position etc. complete for all floors.	5250	KG		
10	Providing & casting in situ ordinary cement concrete M 250 Mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating, curing and finishing completed without V - Groves. (H) Height from 0.0 M To 5.0 M.	48	CMT		

**GUJARAT MINERAL DEVELOPMENT CORPORATION LTD**

(A Government of Gujarat Enterprise)

Price Bid

**Works of (1) providing & fixing of main water supply pipeline from Overhead Tank to Colony Chamber valves & at Mines office Ambadungar,
(2) construction of new RCC road from officer colony main road to Guest house at Fluorspar project, Kadipani, Dist. Chhotaudepur.**

Item No.	Description of Item	Total Qty.	Unit	Rate	Amount
11	Rolling and consolidation of soling including filling in depression which occur during the process, with power roller 8 tonne to 12 tonne.	591	SMT		
12	Constructing brick masonry chamber for underground C.I. Inspection chamber and bends with bricks having crushing strength not less than 35Kg/Cm ² in C.M.1:5 C.I. cover with frame (Light duty) 455mm x 610mm internal dimensions total weight of cover with frame to be not less than 38Kg. (Wt. of cover 23 Kg.) and Wt. of frame 15Kg.) (R.C.C. top slab with 1:2:4 mix (1-cement :2-coarse sand :4-graded stone aggregate 20mm size) foundation concrete 1:5:10 inside plaster 15mm thick with cement mortar 1:3 finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete. (iii) Inside dimensions 600mm x 850 mm and 450mm deep for pipe lines with three or more inlets.	8	NOS		
13	Providing and supplying D.I Pipes for following nominal bore diameter with internal cement mortar lining including all taxes, insurance, transportation, freight charges, octroi, inspection charges, loading, unloading, conveyance to departmental stores, stacking etc. complete. (IS 8329-2000). 100 MM Dia DI - K7.	275	RMT		
14	Providing and supplying D.I Pipes for following nominal bore diameter with internal cement mortar lining including all taxes, insurance, transportation, freight charges, octroi, inspection charges, loading, unloading, conveyance to departmental stores, stacking etc. complete. (IS 8329-2000). 250 MM Dia DI - K7.	475	RMT		
15	Lowering, laying and jointing C.I.S & S Spun pipes suitable for Tyton joints / Mortar lined D.I Pipes of various classes with CI / MS specials of following diameters in proper position, grade and alignment as directed by Engineer-in-charge including hydraulic testing etc. comp. 100 MM Dia DI - K7.	275	RMT		
16	Lowering, laying and jointing C.I.S & S Spun pipes suitable for Tyton joints / Mortar lined D.I Pipes of various classes with CI / MS specials of following diameters in proper position, grade and alignment as directed by Engineer-in-charge including hydraulic testing etc. comp. 250 MM Dia DI - K7.	475	RMT		
17	Providing and supplying ISI mark C.I Air valve of make & quality double acting DS2 valves, 100 DIA including all taxes, insurance, transportation, freight charges, octroi, inspection charges, loading, unloading, conveyance, stacking etc.	3	NOS		
18	Providing and supplying ISI mark C.I Air valve of make & quality double acting DS2 valves, 200/250 DIA including all taxes, insurance, transportation, freight charges, octroi, inspection charges, loading, unloading, conveyance, stacking etc.	1	NOS		
19	Providing and supplying ISI mark C.I D/F Sluice valves as per IS 14846 (LATEST EDITION) of PD -1 & 100 DIA including all taxes, insurance, transportation, freight charges, octroi, inspection charges, loading, unloading, conveyance, stacking etc.	3	NOS		

**GUJARAT MINERAL DEVELOPMENT CORPORATION LTD**

(A Government of Gujarat Enterprise)

Price Bid

**Works of (1) providing & fixing of main water supply pipeline from Overhead Tank to Colony Chamber valves & at Mines office Ambadungar,
(2) construction of new RCC road from officer colony main road to Guest house at Fluorspar project, Kadipani, Dist. Chhotaudepur.**

Item No.	Description of Item	Total Qty.	Unit	Rate	Amount
20	Providing and supplying ISI mark C.I D/F Sluice valves as per IS 14846 (LATEST EDITION) of PD -1 & 200 DIA including,all taxes,insurance, transportation, freight charges, octroi, inspection charges,loading,unloading, conveyance, stacking etc.	2	NOS		
21	Manufacture ,Supply &Delivery of Ductile Iron flange spigot bends,tees,reducers or any other specials as per BS-EN-545/1995 class-A series K12 suitable for use with D.I. pipes manufactured as per IS:8329/1994 delivery of special,is to be made to GWSSB store or site of works any where in gujrat including all taxes ,loading,unloading, carting,stacking, insurance, inspection charges, octrol etc. complete.	150	KG		
22	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete.[A] 15 mm.	30	RMT		
23	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [C] 25 mm.	155	RMT		
24	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [E] 40mm.	410	RMT		
25	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [F] 50mm.	900	RMT		
26	Providing erecting and fixing double coated ISI water tank of required capacity each with all necessary fittings and connection etc. complete on terrace	8000	litre		
27	Providing and fixing ball cock of approved quality as directed (A) copper metal (i) 25mm dia.including all material , fittings, transportations, loading , unloading etc. complete and as directed by EIC.	3	NOS		