

# GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED

Name of work : T-No-10/LR/ BARBED WIRE FENCING/2025 (RE INVITE) - Providing and Fixing Barbed wire fencing surrounding the mine at GMDC lignite project Rajpari,Ta:-Jhagadiai,Dist:-Bharuch

## PRICE BID

ITEM NO.	ITEM	QTY	Per	Rate	Amount
1	Clearing and grubbing road land including uprooting rank vegetation grass bushes, shrubs, sapling and trees girth up to 300mm removal of stumps of trees cut earlier and disposal of unserviceable materials etc. by mechanical means in area of light jungle. Scope of work include required labour , tools, tackles , consuables, equipments, machinaries , loading , un loading , transportation, safety measures etc. complete and work completed as per direction of Engineer in charge.	3000	Smt		
2	Providing Supplying and fixing PSC Pole , 0.10x0.10x1.80 mt with GI barbed wire fencing , with 2 ply - 4 points weighing 9.38 Kg/100 Rmt Strained and fixed to Pole with GI Staples , fixing of 5 horizontal lines and 2 row diagonals . Pole to be grouted in CC 1:3:6 of 0.20 x0.20x0.50 size pit including excavation . Pole should be fixed at an interval of 3.00 mt. c/c and at every 27.0 meter interval extra stay Pole should be provided in either / other side of vertcal pole and at every corner extra pole should be at both the direction should be provided with necessary fixing arrangement in line and level.Including curing , tensiling of wire and white washing in three coats to poles etc. completed as directed by EIC. <b>Scope of work also include required all material, man power, equipments , tools , tackles , transportation, loadiung , unloading , safety measures etc. complete as directed by EIC.</b>	3200	Rmt		
				<b>Total</b>	