

BILL OF QUANTITY

Sr. No.	Item Description	Qty	Unit	Rate in Rs.	Total Amount in Rs.
1	<p>Precast concrete block masonry (including quoin blocks jamb blocks closer etc.) with solid concrete blocks of approved size of 16x8x6". Block masonry work on existing boundary wall height extended up to 2 feet and as per site requirement in cement mortar 1:6 (precast fly ash Block supply by GMDC free of cost at block production yard area.) and block loading, unloading, transportation at work site is in bidder scope. including at all lead, lift, height and levels sizes with necessary scaffolding, curing, for etc., complete as per specification and as directed by the EIC. including all type of material like cement, sand, water, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, etc complete as per instruction of Architect/EIC. NOTE: BLOCK WILL BE SUPPLY BY GMDC FREE OF COST. BLOCK LOADING, UNLOADING AND ALL TRANSPORTATION IN BIDDER SCOPE.</p>	1584	CMT		
2	<p>15 mm thick cement plaster : Providing and laying average 15 mm. thick single coat smooth finishing using steel float (mala finish) plaster in CM 1:4 (1 cement : 4 coarse river sand), on brickwork, RCC work, blocks, sills, soffits, jambs etc. at all floors, all levels, all heights, all shapes and for all sizes with necessary scaffolding, curing, chicken mesh at the junction of masonry & RCC work using screw / dhoba nails, making moulded, grooves, drip moulds, tapak, chemical bonding agent etc., for all lead, lift, height and levels etc., complete as per specification and as directed by the EIC. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.</p>	16080	SMT		
	Total Amount in Rs.				